

DRAFT


# ***Modeling of Green Infrastructure Components and Large Scale Test and Control Watersheds***

at Kansas City, Missouri

*Prepared for*  
USEPA Office of Research and Development  
Urban Watershed Management Branch

*Prepared by*  
Robert Pitt and Leila Talebi  
University of Alabama  
Department of Civil, Construction,  
and Environmental Engineering  
Tuscaloosa, AL 35487

*With contributions from*  
Deborah O'Bannon  
University of Missouri, Kansas City  
*and*  
Dustin Bambic and Jason Wright  
Tetra Tech, Fairfax, VA





**THIS PAGE INTENTIONALLY LEFT BLANK**



## Contents

<b>1. Introduction and Summary.....</b>	<b>1</b>
Project Summary .....	1
Overview of Watershed Model Development .....	1
Summary of WinSLAMM Description and Use for GI Projects .....	2
Summary of Site Characteristics Used in Stormwater Quality Modeling .....	3
Summary of Systemwide Observations and Model Calibration .....	5
Summary of Biofilter Measurements during Rain Events .....	6
Summary of Monitored and Modeled Performance of Stormwater Control Practices .....	10
Summary of Performance Production Functions for the Design and Analysis of Stormwater Management Controls .....	13
Summary of Decision Analysis Methods to Assist in the Selection of Stormwater Control Programs .....	19
Conclusions.....	19
<b>2. Description of WinSLAMM, the Source Loading and Management Model.....</b>	<b>26</b>
Basic Model Setup for Site Characteristics .....	27
Base Analyses with No Stormwater Controls .....	30
Sources of Pollutants of Interest.....	32
Summary of WinSLAMM Description and use for GI Projects .....	32
<b>3. Standard Land Use Development Characteristics used for WinSLAMM Calibration.....</b>	<b>34</b>
Land Characteristics Survey in Kansas City Test Watershed .....	34
Infiltration Rate Monitoring .....	38
Summary of Site Characteristics Used in Stormwater Quality Modeling.....	40
<b>4. Large-Scale Calibration of WinSLAMM: Modeled Stormwater Characteristics Compared to Observed Data.....</b>	<b>42</b>
Runoff Calibration for Test and Control Watersheds.....	42
Variability and Uncertainty with WinSLAMM Modeling.....	54
Summary of Systemwide Observations and Model Calibration.....	55
<b>5. Small-Scale Drainage Areas, Performance Monitoring during Rain Events, and Associated Model Calibration Factors for Stormwater Controls .....</b>	<b>58</b>
Infiltration Rates in Monitored Biofilters .....	60
Runoff Duration before Ponding in Biofilters .....	64
Maximum Water Depth Observed in Biofilters.....	65
Laboratory Column Tests of Infiltration Rates as a Function of Compaction .....	68
Laboratory Measurement of Porosity of Kansas City Soil Media .....	70
Laboratory Infiltration Results.....	70
Influent Water Quality to Curb-Side Biofilters .....	73
Summary of Biofilter Measurements during Rain Events.....	79
<b>6. Evaluation of Performance of Stormwater Control Practices .....</b>	<b>84</b>
Characteristics of Areas Treated and Not Treated by Stormwater Controls .....	84
Designs and Service Areas for Stormwater Controls in the Test (Pilot) Area .....	87



Modeling of Test (Pilot) Watershed Area with Stormwater Controls Compared to Observed Flows .....	96
Sources of Flows and Particulates in Untreated Watershed.....	98
Use of Stormwater Controls in Test (Pilot) Area.....	99
Summary of Monitored and Modeled Performance of Stormwater Control Practices.....	107
<b>7. Stormwater Control Production Functions .....</b>	<b>110</b>
Pavement and Roof Disconnections .....	111
Roof Runoff Rain Gardens .....	113
Curb-Cut Biofilters.....	119
Biofilter Data Entry.....	120
Use of Underdrains in Biofilters.....	124
Underdrain Testing Procedure .....	127
Effects of Slope, Lengths, and Sediment Load on the Drainage Characteristics of the SmartDrain™ .....	128
Production Functions of Curb-Cut Biofilters Using WinSLAMM.....	131
Porous Pavement .....	142
Grass Filters.....	144
Grass Swales.....	145
Cisterns and Water Storage Tanks .....	147
Calculating the Benefits of Rainwater Harvesting Systems .....	147
Regional Rainfall and Runoff Distributions Affecting Roof Runoff Harvesting .....	147
Water Harvesting Potential in Kansas City.....	149
Rain Barrels and Water Tanks for Roof Runoff Harvesting .....	152
Example Alternative Irrigation Water Use Calculations .....	155
Green Roofs.....	158
Summary of Performance Production Functions for the Design and Analysis of Stormwater Management Controls .....	159
<b>8. Economic and Decision Analyses using WinSLAMM .....</b>	<b>165</b>
Using WinSLAMM Decision Analyses to Select an Urban Runoff Control Program .....	167
Decision Analysis with Multiple Conflicting Objectives .....	170
Example Decision Analysis Application with Extended WinSLAMM Data Output.....	176
Attribute Levels Associated with Different Stormwater Management Programs.....	176
Calculated Performance of Stormwater Control Options .....	179
Summary of Decision Analysis Methods to Assist in the Selection of Stormwater Control Programs.....	186
<b>9. Conclusions .....</b>	<b>187</b>
Considerations That Affect Use of Different Stormwater Controls .....	188
Sodium Adsorption Ratio (SAR) .....	188
Clogging of Infiltration Devices .....	189
Groundwater Contamination Potential and Over-Irrigation .....	190
Retrofitting and Availability of Land .....	192
<b>10. References .....</b>	<b>193</b>



## Figures

Figure 1. Duration-infiltration rates for surface soils.....	4
Figure 2. Decreasing test (pilot) area event flows compared to control area flows during and after construction. ....	5
Figure 3. Observed versus modeled flows during final baseline conditions (after re-lining). ....	6
Figure 4. Measured infiltration rates in biofilters during actual rains.....	7
Figure 5. Maximum ponding depth observed in biofilters during actual rains. ....	7
Figure 6. Kansas City biofilter media infiltration rates during column tests for hand compacted density. ....	8
Figure 7. Particle size distribution for curb-cut influent stormwater samples. ....	9
Figure 8. Particulate solids concentration comparisons because of different analytical methods. ....	9
Figure 9. TSS by shake and pour versus TSS by stirring and pipetting.....	10
Figure 10. Areas receiving surface stormwater control before being discharged into the combined sewer.....	11
Figure 11. Modeled versus observed flows in the test (pilot) area after construction of stormwater controls. ....	12
Figure 12. Sources of runoff volume during different rain events (no control practices).....	12
Figure 13. Percentage reduction in annual roof runoff with rain gardens.....	14
Figure 14. Effects of underdrains in biofilters on annual runoff reductions for subsurface native soil infiltration rates of 0.5 in/hr.....	15
Figure 15. Percentage reduction in roof runoff with irrigation of landscaped areas in Kansas City. ....	18
Figure 16. Example parameter files selection. ....	28
Figure 17. Scatterplot of Kansas City, Missouri, rain file. ....	28
Figure 18. Base commercial conditions for examples. ....	29
Figure 19. Source area characteristics for the example problem. ....	29
Figure 20. Selection of pollutants to be evaluated. ....	30
Figure 21. Selection of output formats.....	30
Figure 22. Basic Summary Screen.....	31
Figure 23. Base flow duration plot.....	31
Figure 24. Flow sources for different rains.....	32
Figure 25. Detailed GIS coverage showing land cover components of different land uses in the Kansas City test watershed.....	35
Figure 26. Area description field sheet. ....	37
Figure 27. Set of three Turf-Tec infiltrometers for infiltration measurements in pre-development soils.....	38
Figure 28. Example infiltration plot in area soils.....	39
Figure 29. Decreasing infiltration rates as the rain event duration increases.....	40
Figure 30. Duration-infiltration rates for surface soils.....	41
Figure 31. Test (100 acres) and control (86 acres) watersheds in Marlborough area of Kansas City, Missouri.....	43
Figure 32. Flow monitoring locations at test and control area boundaries. ....	44
Figure 33. Test to control area total runoff volume ratios during complete study period (initial baseline, after re-lining, during construction, and after construction of stormwater controls).....	50



Figure 34. Test to control area total runoff volume ratios during and after construction of stormwater controls. .... 51

Figure 35. Test to control area total runoff volume ratios for different study periods..... 52

Figure 36. Observed versus modeled flows during final baseline conditions (after re-lining) ..... 53

Figure 37. Variabilities of runoff volumes observed and modeled..... 54

Figure 38. Decreasing test (pilot) area event flows compared to control area flows during and after construction. .... 56

Figure 39. Observed versus modeled flows during final baseline conditions (after re-lining). .... 57

Figure 40. Location of stormwater controls monitored in test (pilot) watershed..... 59

Figure 41. Box and whisker plots of observed infiltration rates in monitored biofilters. .... 62

Figure 42. Infiltration rate site categories. .... 63

Figure 43. Time to ponding in monitored biofilters..... 65

Figure 44. Maximum water depth observed in monitored biofilters..... 66

Figure 45. Categories of monitored sites having different ponding depths. .... 67

Figure 46. Media samples obtained from Kansas City biofilters..... 68

Figure 47. Lab column construction for flow test using Kansas City soil media: bottom of the columns secured with a fiberglass window screen, mixed soil media, and soil compaction. .... 68

Figure 48. Particle size distribution of Kansas City soil media used during lab compaction test. .... 69

Figure 49. Laboratory column setup for porosity and infiltration measurements..... 70

Figure 50. Laboratory infiltration measurements fitted with Horton equations: hand compaction tests for Kansas City biofilter media. .... 71

Figure 51a. Laboratory infiltration measurements fitted with Horton equations: standard proctor compaction test for Kansas City biofilter media. .... 72

Figure 51b. Laboratory infiltration measurements fitted with Horton equations: modified proctor compaction test for Kansas City biofilter media. .... 72

Figure 52. Particle size distributions of water entering the monitored biofilters..... 73

Figure 53. Comparison of particulate solids by different analytical methods. .... 74

Figure 54. TSS by stirring pipetting versus SSC with cone splitter..... 75

Figure 55. TSS by shaking and pouring versus TSS by stirring and pipetting. .... 75

Figure 56. TSS variations at monitored sites. .... 76

Figure 57. Site categories for TSS concentrations. .... 77

Figure 58. SSC for monitored sites..... 78

Figure 59. SSC monitored site categories..... 78

Figure 60. Measured infiltration rates in biofilters during actual rains..... 79

Figure 61. Maximum ponding depth observed in biofilters during actual rains. .... 80

Figure 62. Kansas City biofilter media infiltration rates during column tests for hand compacted density. .... 81

Figure 63. Particle size distribution for curb-cut influent stormwater samples. .... 82

Figure 64. Particulate solids concentration comparisons because of different analytical methods. .... 82

Figure 65. TSS by shake and pour versus TSS by stirring and pipetting..... 83

Figure 66. Map of test (pilot) area showing main surface characteristics..... 84

Figure 67. Map of test (pilot) area showing surface characteristics of areas receiving stormwater treatment. .... 85

Figure 68. Map of test (pilot) area showing surface characteristics of areas not receiving stormwater treatment. ....	86
Figure 69. Stormwater controls in the 100-acre test (pilot) study area (source: Tetra Tech). ....	88
Figure 70. Shallow bioretention device typical details for residential streets.....	90
Figure 71. Bioswale typical details for residential streets.....	91
Figure 72. Cascade rain garden typical details for residential streets. ....	92
Figure 73. Cascade rain garden typical details for residential streets (continued).....	93
Figure 74. Porous sidewalk typical details for residential streets. ....	94
Figure 75. Rain garden typical details for residential streets. ....	95
Figure 76. Below grade storage system typical details for residential streets.....	96
Figure 77. Observed and calculated flows after biofilter construction. ....	97
Figure 78. Sources of runoff volume during different rain events (no control practices).....	98
Figure 79. Sources of particulate solids during different rain events (no control practices). ....	98
Figure 80. Areas receiving surface stormwater control before being discharged into the combined sewer.....	107
Figure 81. Modeled versus observed flows in the test (pilot) area after construction of stormwater controls. ....	108
Figure 82. Sources of runoff volume during different rain events (no control practices).....	108
Figure 83. Disconnection of pitched roof to silty soil.....	111
Figure 84. Rain garden input screen. ....	114
Figure 85. Detailed media characteristics for rain gardens.....	114
Figure 86. Calculated roof runoff rain garden performance as a function of size. ....	115
Figure 87. Production function for rain garden use for control of total annual roof runoff volume.....	117
Figure 88. Performance function of roof runoff rain garden use and 1.4-in design storm <i>D</i> used for regulations. ....	119
Figure 89. Basis data entry screen for biofilters and bioinfiltration stormwater controls.....	121
Figure 90. Annual runoff volume reduction (%) for typical rain year (1990) for different numbers of simple curbcut rain gardens (100 ft <sup>2</sup> each) per 100-acre watershed.....	123
Figure 91. Durations of flows (percentage of time) for different numbers of simple curb-cut rain gardens.....	124
Figure 92. Initial design evaluation of alternative bioretention facility designs.....	125
Figure 93. Close-up photograph of SmartDrain™ material showing the microchannels on the underside of the 8-in-wide strip.....	126
Figure 94. Particle size distribution for medium-sized sand and SIL-CO-SIL250.....	126
Figure 95. SmartDrain™ installation procedures in the trough. ....	127
Figure 96. SmartDrain™ installation for the clogging test in the tall box. ....	128
Figure 97. Algae in the test tank during the biofouling tests. ....	130
Figure 98. Stage-discharge relationships for various test conditions for the SmartDrain™.....	131
Figure 99. September 2, 2008, to October 12, 2012, rains monitored in the Kansas City GI test area during the demonstration project monitoring period. ....	132
Figure 100. Bioinfiltration device, no underdrain, and no gravel storage. ....	133
Figure 101. Media characteristics used in the test (pilot) biofilters and bioinfiltration devices. ....	133
Figure 102. Bioinfiltration device with no underdrain but with gravel storage.....	134
Figure 103. Biofilter with SmartDrain™ underdrain with gravel storage. ....	134
Figure 104. Biofilter with conventional 3-in. underdrain and gravel storage.....	135

Figure 105. No underdrain alternatives, with varying native soil infiltration rates and with and without gravel storage. ....	136
Figure 106. Use of underdrains in soils having 0.2 in/hr native subsurface infiltration rates.....	137
Figure 107. Use of underdrains in soils having 0.5 in/hr native subsurface infiltration rates.....	137
Figure 108. Use of underdrains in soils having 1.0 in/hr native subsurface infiltration rates.....	138
Figure 109. Use of underdrains in soils having 2.5 in/hr native subsurface infiltration rates.....	139
Figure 110. Clogging potential for biofilters in test (pilot) area. ....	139
Figure 111. Porous pavement main input screen. ....	143
Figure 112. Grass filter strip form in Version 10.....	145
Figure 113. Grass swale input screen.....	146
Figure 114. Long-term rain depths for individual Kansas City, Missouri, rains (1972–1999).....	147
Figure 115. St. Louis, Missouri, rain and runoff distributions (1984–1992 rains). ....	148
Figure 116. ET by month. ....	151
Figure 117. Monthly rainfall.....	151
Figure 118. Monthly supplemental irrigation requirements to meet ET.....	151
Figure 119. Cistern/water tank WinSLAMM input screen. ....	153
Figure 120. Water use WinSLAMM input screen. ....	153
Figure 121. Irrigation storage requirements production function. ....	154
Figure 122. Plot of supplemental irrigation needs to match ET deficit for Essex County, New Jersey. (1 in/mo = 25 mm/mo). ....	156
Figure 123. Plot of supplemental irrigation needs to match heavily watered lawn (0.5 to 2.5 in./week) deficit for Essex County, New Jersey (1 in/mo = 25 mm/mo). ....	157
Figure 124. Green roof main input screen. ....	158
Figure 125. Percentage reduction in annual roof runoff with rain gardens.....	160
Figure 126. Effects of underdrains in biofilters on annual runoff reductions for subsurface native soil infiltration rate of 0.5 in/hr. ....	161
Figure 127. Percentage reduction in roof runoff with irrigation of landscaped areas in Kansas City. ....	163
Figure 128. Basic economic analyses input screen.....	165
Figure 129. U.S. cities already in the economic model ....	165
Figure 130. Annual runoff volume reduction (%) for typical rain year (1990) for different numbers of simple curb-cut rain gardens per 100-acre watershed. ....	166
Figure 131. Total capital costs and total annualized costs for different numbers of simple curb-cut rain gardens per 100-acre watershed. ....	166
Figure 132. Durations of flows (% of time) for different numbers of simple curb-cut rain gardens. ....	166
Figure 133. Percentage reduction of annual flows with 10 ft diameter x 5 ft tall cisterns (numbers per 100 acres) ....	166
Figure 134. WinSLAMM Batch Editor setup screen.....	168
Figure 135. Example utility function for a water quality attribute (TSS, mg/L). ....	172

## Tables

Table 1. Medium-density residential area site characteristics (%) .....	3
Table 2. Test (pilot) and control watershed flow comparisons during four monitoring periods .....	6
Table 3. Summary of the stormwater controls constructed in the test (pilot) watershed.....	13
Table 4. Porous pavement performance (paved parking and storage area; loam soil; 3-in underdrains every 20 ft.).....	16
Table 5. Grass filter performance for different soils and slopes .....	17
Table 6. Grass swale performance .....	17
Table 7. Calculated green roof performance.....	19
Table 8. Groundwater contamination potential for stormwater pollutants post-treatment .....	24
Table 9. Retrofitting problems for different stormwater management options.....	25
Table 10. Original GIS measurements by Kansas City, Missouri, for the test watershed .....	36
Table 11. Medium-density residential areas (%) .....	36
Table 12. Infiltration characteristics for area soils.....	39
Table 14. Rainfall characteristics during different flow monitoring periods.....	45
Table 15. Flow characteristics during different flow monitoring periods.....	46
Table 16. Statistical comparisons of flows during different flow monitoring periods.....	52
Table 17. Rain data with observed and modeled flow characteristics after re-lining of the combined sewer and before the construction of the stormwater controls (final baseline conditions). .....	53
Table 18. Expected modeling variability .....	55
Table 19. Test (pilot) and control watershed flow comparisons during four monitoring periods .....	56
Table 20. Sources of small-scale drainage area information .....	58
Table 21. Locations of Monitoring Stations .....	59
Table 22. 1324 E. 76th St. (site #1) infiltration rates and ponding times .....	60
Table 23. 1325 E. 76th St. (site #2) infiltration rates and ponding times .....	60
Table 24. 1419 E. 76th Terrace (site #3) infiltration rates and ponding times.....	60
Table 25. 1612 E. 76th St. (site #4) infiltration rates and ponding times .....	61
Table 26. 1336 E. 76th St. (site #5) infiltration rates and ponding times .....	61
Table 27. 1140 E. 76th Terrace (site #7) infiltration rates and ponding times.....	61
Table 28. 1222 E. 76th St. (site #8) infiltration rates and ponding times .....	61
Table 29. 1112 E. 76th Terrace (site #9) infiltration rates and ponding times.....	62
Table 30. Accumulative mass percentage (%) (summary for 20 influent samples).....	73
Table 31. Site characteristics for areas receiving stormwater treatment and other areas.....	87
Table 32. Impervious and pervious areas in subareas receiving stormwater treatment and other areas.....	87
Table 33. Summary of stormwater control design plan components.....	88
Table 34. Typical sizes of different types of stormwater controls used in the test (pilot) area.....	89
Table 35. Events after construction of stormwater controls in pilot watershed.....	97
Table 36. Major source areas contributing runoff and particulate solids.....	99
Table 37. Sizes and drainage area characteristics of subareas treated by stormwater controls .....	99
Table 38. Modeling characteristics for bioretention areas .....	101
Table 39. ET rates for Kansas City biofiltration devices (in/day) .....	102

Table 40. Modeling characteristics for porous pavement areas .....	102
Table 41. Modeling characteristics for swale drained areas .....	103
Table 42. Drainage areas to bioretention areas .....	103
Table 43. Drainage areas to porous pavements.....	103
Table 44. Drainage areas to swales.....	104
Table 45. Drainage areas not treated by stormwater controls.....	104
Table 46. Calculated stormwater control performance .....	105
Table 47. Calculated stormwater conditions for treated and untreated areas.....	106
Table 48. Summary of the stormwater controls constructed in the test (pilot) watershed .....	109
Table 49. Effectiveness of disconnecting impervious areas in 2.25-acre commercial site over 10 years.....	112
Table 50. Effectiveness of roof area disconnections.....	112
Table 51. Disconnected and directly connected roof runoff differences .....	113
Table 52. Rain garden performance for directly connected pitched roofs .....	115
Table 53. Numbers and sizes of rain gardens to provide specific roof runoff flow benefits .....	116
Table 54. Large rains close to 1.4-inch design storm <i>D</i> .....	117
Table 55. Roof runoff volumes for large rains close to 1.4-in design storm <i>D</i> .....	118
Table 56. Summary of performance of biofilter size, use of underdrains, and subsurface soil infiltration rates on desired performance objectives.....	140
Table 56. Summary of performance of biofilter size, use of underdrains, and subsurface soil infiltration rates on desired performance objectives (cont.) .....	141
Table 57. Porous pavement performance (paved parking and storage area; loam soil; 3-in underdrains placed 20 ft apart) .....	143
Table 58. Grass filter performance for different soils and slopes .....	145
Table 59. Grass swale performance .....	146
Table 60. 1973 through 1999 Kansas City Airport monthly rain depth totals (inches) .....	149
Table 61. Monthly irrigation requirements .....	150
Table 62. Monthly irrigation per household .....	150
Table 63. Roof runoff storage needs for beneficial use objectives .....	154
Table 64. Rain barrels and water tank equivalents .....	155
Table 65. Irrigation needs to satisfy ET requirements for Essex County, New Jersey .....	156
Table 66. Irrigation needs to satisfy heavily irrigated lawn for Essex County, New Jersey.....	157
Table 67. Calculated green roof performance.....	159
Table 68. Porous pavement performance (paved parking and storage area; loam soil; 3-in underdrains every 20 ft.).....	162
Table 69. Grass filter performance for different soils and slopes .....	162
Table 70. Grass swale performance .....	162
Table 71. Calculated green roof performance.....	164
Table 72. Approximate annual flow reductions (%) for combinations of large cisterns and simple curb-side rain gardens, per 100 acres .....	167
Table 73. Attributes of several different stormwater management programs.....	169
Table 74. Additional attributes of several different stormwater management programs.....	169
Table 75. Decision analysis attributes, measures, and ranges of values .....	171
Table 76. Definition of alternatives .....	171
Table 77. Estimated attribute levels for each alternative (fictional) .....	171



Table 78. Individual attribute utility values for each alternative ..... 175

Table 79. Utility of each alternative..... 175

Table 80. Example monthly average evaporation rates (in/day)..... 178

Table 81. Wet detention pond size and elevation characteristics..... 179

Table 82. Suspended solids reduction goals and costs (values in italics meet the numeric criterion  
of 80% TSS goals)..... 180

Table 83. Options and specific criteria (values in italics meet numeric criteria)..... 181

Table 84. Ranges of attributes for pre-screened options..... 182

Table 85. Utility and tradeoffs for different options..... 184

Table 86. Calculations of ranks for different stormwater management options ..... 185

Table 87. Groundwater contamination potential for stormwater pollutants post-treatment ..... 191

Table 88. Retrofitting problems for different stormwater management options..... 192



## **Acknowledgements**

The results presented in this report are a small portion of the full project activities associated with the National Demonstration of Advanced Drainage Concepts Using Green Solutions for CSO Control Project in Kansas City, funded by the USEPA Office of Research and Development, Urban Watershed Management Branch. The direction and support of the EPA Project Officers, Michelle Simon and Richard Field, are gratefully acknowledged. Other project participants, including Tetra Tech personnel (Dustin Bambic, Jason Hall, and Scott Struck, plus others), University of Missouri, Kansas City faculty and student researchers (under the direction of Dr. Deb O'Bannon), University of Alabama graduate students, the Kansas City Water Services Department, Dr. Michael Ports, and Mid-America Regional Council (MARC), were all instrumental in planning and carrying out this project and are also gratefully acknowledged.

## 1. Introduction and Summary

Green infrastructure includes practices and site-design techniques that store, infiltrate, evaporate, or detain stormwater runoff and in so doing, control the timing and volume of stormwater discharges from impervious surfaces (e.g., streets, building roofs, and parking lots) to the stormwater collection systems. EPA’s Office of Research and Development has the goal to provide detailed guidance and information on methodologies for selection, placement, and cost effectiveness and to document the benefits of green infrastructure applications in urban watersheds for new development, redevelopment, and retrofit situations.

The Kansas City Water Services Department (KCWSD) provides wastewater collection and treatment for approximately 650,000 people, located within the City and in 27 tributary or “satellite” communities. The City of Kansas City, Missouri has developed a project to demonstrate the application of green infrastructure for combined sewer overflow (CSO) control in the Middle Blue River. KCWSD has recently completed construction of a 100-acre retrofit of an aging neighborhood that has included sewer rehabilitation and implementation of over 100 green infrastructure (GI) solutions. This project is one of the largest in the United States and provides a unique opportunity for USEPA ORD to quantify the benefits of GI solutions on large scales (overall pilot project area) and small scales (individual GI solutions) and meet its GI-related goals.

This report describes efforts to develop a watershed model (WinSLAMM—the Source Loading and Management Model) and sewerage model (SWMM) for this area using the pre-construction flow and water quality data. The pre- and post-pilot flow monitoring has facilitated quantification of the benefits of the upland stormwater controls, and served as the basis for watershed model development. WinSLAMM was used to calculate the stormwater contributions to the combined sewerage system during wet weather by providing a time series of flows and water quality conditions, for various types of upland controls, while SWMM, with its detailed hydraulic modeling capabilities, focused on the interaction of these time series data with the sewerage flows and detailed hydraulic conditions in the drainage system. Both models were used interactively by the project team, emphasizing their respective strengths. This report addresses only the WinSLAMM analyses and evaluations. The study test (pilot) area is a 100-acre subcatchment. This watershed is mostly medium-density residential areas, with some commercial and institutional land uses. An adjacent 80-acre subcatchment was also monitored as a control watershed, with no stormwater controls, for comparison.

The project contractor is Tetra Tech, Inc., and associated subcontractors are the University of Alabama (UA), University of Missouri–Kansas City (UMKC), Mid-America Regional Council (MARC), and Michael Ports and Associates. Critical project leveraging and cooperation is provided by the Kansas City Water Services Department and EPA Region 7.

### Project Summary

The following summary is compiled from the end of section summaries, plus most of the conclusion section.

#### ***Overview of Watershed Model Development***

Model calibration requires detailed information pertaining to the areas where monitored data have been collected to compare to the modeled predictions. For this project, calibration of the WinSLAMM model was conducted in several steps:

- Regional calibration using water quality and flow data from the National Stormwater Quality Database (NSQD). This information was used to update and compare the original model calibrations that were mostly associated with Wisconsin and Alabama source data. The regional NSQD data, along with additional more recent Nebraska data, enabled significant amounts of data to be examined for the main land use categories for this geographical area in the US. The Kansas City area is in the central U.S. region, and those data were used for this step of the calibration process.
- Detailed land development characteristics were obtained for the study area, along with site soil infiltration measurements, by UMKC project teams. This allowed the model calibration based on these critical site characteristics to be included. Long-term continuous rain data were also used during the analyses to minimize the effects of any unusual conditions, along with the actual monitored rains.
- Site-specific rainfall-runoff data were obtained from four years of flow monitoring (from 2009 through 2012) in the test and control watersheds in the Marlborough study of Kansas City. Being a combined sewer system, the measured wet weather flows were adjusted by having the expected concurrent dry weather sanitary sewage flows (from adjacent dry period monitoring periods) subtracted from the combined sewer flows. These hydrograph separation analyses were conducted by the Tetra Tech project team. These flow data were used to verify the regional and site calibration conditions. The site development characteristics for the test and control watershed were used, along with the actual rain history during the flow monitoring period, to show how closely the calibrated model predicted the runoff characteristics that were monitored.
- As data become available, additional calibration verifications of the model were made. As an example, the sewer rehabilitation project was conducted between the first two monitored years. The effects of these sewer repairs on the monitored data are obvious. The data collected before the repairs are therefore not suitable for flow calibrations because the observed wet weather flows were substantially less than the flows observed after the repairs. Apparently, large amounts of sewage were leaking from the collection system, resulting in an artificially reduced runoff yield. In addition, the two demonstration rain gardens have two to three years of flow data available. Those observations were also used to verify the modeled expected performance of these controls. Other data now available includes the complete area green infrastructure (GI) components (mostly composed of curb-cut biofilters and porous pavement). Several of the GI components were constructed to enable localized monitoring, to supplement the large-scale monitoring.

### ***Summary of WinSLAMM Description and Use for GI Projects***

Over the years, WinSLAMM has been extensively revised and expanded and now includes a wide range of capabilities, including its ability to evaluate stormwater management options using a long series of rain events, especially important for evaluating combined sewer and GI issues. The effectiveness of the control practices in WinSLAMM are calculated on the basis of the actual sizing and other attributes of the devices, the source area or outfall location characteristics, and the calculated runoff characteristics. The model does a complete mass balance and routing of water volume and particulate mass, considering the combined effects of all controls. Hydraulic and particle size routing occurs for each device individually, and serial effects of multiple devices are now accurately considered in version 10.

WinSLAMM conducts a continuous water mass balance for every storm in the study period. As an example, for rain barrels, water tanks or cisterns, for harvesting roof runoff for later irrigation or other beneficial uses, the model fills the available storage during rains. Between rains, the storage tank is drained according to the water withdrawal use for each month. If the tank is almost full from a preceding close rain (and not enough time was available to drain the storage tank), excess water from the event would be discharged to the drainage system after the tank fills. Curb-cut rain gardens/biofilters along a



street are basically a cascading swale system where the site runoff is allowed to infiltrate. If the runoff volume is greater than the capacity of the rain gardens, the excessive water is discharged into the drainage system or possibly additional downgradient controls. When evaluated together, the cisterns treat the roof runoff first, but the excess water is discharged to the curb-cut biofilters for infiltration. The continuous simulation drains the devices between events according to the interevent conditions.

The first step in setting up a WinSLAMM analysis is to identify the rain and the calibrated parameter files to be used. The rain file describes the series of rains to be considered in the analysis. The 10 years of Kansas City rains from 1990 through 1999 had 920 rains that ranged from 0.01 to 3.79 inches (in.), with an average total annual rainfall of about 35 to 40 in. Land development characteristics describing local site conditions of the study area are used by WinSLAMM to calculate expected runoff characteristics. One of the important features of WinSLAMM is to calculate the sources of the flows and pollutants of interest for the study area under different rain conditions.

### **Summary of Site Characteristics Used in Stormwater Quality Modeling**

Land development information corresponding to the different land uses in an area is needed as an initial step in investigating stormwater management options for an area. The Marlborough study (pilot) area in Kansas City is mostly a medium-density residential area, constructed before 1960, with a small amount of strip commercial area along Troost Ave., and a small portion of a school. Detailed inventories were made of each of the approximately 600 homes in the area by graduate students from UMKC. Table 1 shows the breakdown of the surface areas in the medium density residential area portion of the test (pilot) watershed. The values shown on this table are the percentages of each subarea of the whole area, while the values shown in parentheses are the breakdown within a single subarea. For example, directly connected roofs make up about 1.87% of the complete 100 acre site, and represent about 15% of all roofs.


**Table 1. Medium-density residential area site characteristics (%)**

	Roofs	Driveways	Sidewalks	Parking/st orage	Streets	Landscaped	Isolated	Total
<b>Impervious</b>								
directly connected	1.87 (15%*)	4.12 (46%)	1.15 (46%)	1.59	9.35			18.07
disconnected	10.57 (85%)	4.03 (45%)	1.34 (54%)					15.95
<b>Pervious</b>								
unpaved (gravel, severely compacted)		0.81 (9%)						0.81
landscaped						65.13		65.13
isolated (swimming pools)							0.05	0.05
<b>Total residential area</b>	<b>12.44</b>	<b>8.95</b>	<b>2.49</b>	<b>1.59</b>	<b>9.35</b>	<b>65.13</b>	<b>0.05</b>	<b>100.00</b>

\* percentage of total subarea in this category; for example, 15% of all roofs are directly connected and 85% of all roofs are disconnected.

Detailed site information is needed for stormwater management evaluations. Only about 15% of the residential roofs are directly connected in the test (pilot) area. If all were assumed to be directly connected, large errors in the roof runoff contribution calculations would occur. Similarly, if roof runoff stormwater controls were located at all roofs, those located where the roofs were already disconnected would provide much lower additional benefits in decreasing the area's runoff quantity.

In addition to the site surveys, site soils surveys were also conducted for the area by the UMKC graduate students. Small-scale infiltrometers were used to measure infiltration rates in the disturbed urban soils of the test watershed area. The most precise measurements of infiltration, and which should be used in areas where large-scale infiltration units are being designed, should rely on full-scale tests. These are typically large trenches or boreholes, constructed to penetrate the depths of soil that the final units will use for infiltration, and use large volumes of water over extended periods. In the Kansas City study area, the constructed rain gardens and curb-cut biofilters have undergone full-scale inundation tests after construction to supplement the smaller scale tests. In addition, the rate of infiltration during the actual rains was also measured to obtain actual rates for the area and designs used. Figure 1 shows the measured infiltration rates from the small-scale tests in the test area.



**Figure 1. Duration-infiltration rates for surface soils.**

Figure 1 indicates that the infiltration rate would be between 1 and 10 inches per hour (in/hr) for rains that lasted up to about two hours, with likely decreasing infiltration rates for the long rains of interest for the critical combined sewer overflow (CSO) event design storm. Initial modeling efforts supporting the GI designs assumed an infiltration rate of about 0.3 in/hr. Deeper soil profiles indicated that this might be too large. Therefore, for the shallow rain gardens, an infiltration rate of 0.2 in/hr was used by the initial designers. However, actual infiltration measurements in the constructed biofilters after saturated conditions indicated system infiltration rates are generally between 1 and 2 in/hr, while modeling indicates that the subsurface infiltration rates in the native soils are likely close to 1 in/hr. Subsurface infiltration in areas of biofiltration device construction can be higher than surface rates because of typical decreased amounts of clays and reduced compaction. If care is taken to minimize compaction during construction, these higher rates might be preserved. The extended monitoring period will help verify the actual soil infiltration conditions.

### Summary of Systemwide Observations and Model Calibration

Runoff monitoring was conducted in the combined sewer system at several locations in the test and control watersheds. Events were monitored after the sewer was rehabilitated, and these data were used as a new baseline condition. WinSLAMM evaluated the test (pilot) and control watershed conditions during the two monitoring periods (post re-lining, as the new baseline versus after construction of controls) to verify the rainfall-runoff calibration based on site development characteristics and the actual rains monitored.

Figure 2 focuses on the time during construction of the GI components in the test watershed area and after most of the control construction was completed. The last period, since April 1, 2012, was therefore separated from the construction period as it represents a period when most of the GI stormwater controls were functioning. Only eight events are in this last critical category. However, the site monitoring will be continuing into the 2013 rain year for additional observations. All the last events have a reasonably constant flow volume ratio, except for one of the events that apparently produced more runoff from the test area (or less from the control area) than expected. The additional monitored events will be very important to establish greater confidence in the overall performance of the stormwater controls in the test (pilot) watershed.




Figure 2. Decreasing test (pilot) area event flows compared to control area flows during and after construction.


Table 2 summarizes the average test (pilot) to control area total flow ratios for each of the four monitoring periods and the percentage differences from the appropriate baselines, along with the Wilcoxon Rank-Sum test results indicating if the differences were statistically significant. The after-construction flow ratios were significantly different from the before construction baseline flow ratios. However, the after re-lining flow ratios were not shown to be significantly different from the before re-lining flow ratios because of the few data observations after the re-lining and before the start of the GI stormwater control construction period.

**Table 2. Test (pilot) and control watershed flow comparisons during four monitoring periods**

Monitoring period	Average test (pilot) to control area runoff volume ratio	% change compared to initial baseline (and p from Wilcoxon Rank-Sum test)	% change compared to final baseline (after re-lining) (and p from Wilcoxon Rank-Sum test)
Initial baseline	1.06	n/a	n/a
After re-lining (final baseline)	1.53	44% increase (p = 0.20)	n/a
During construction	1.02	4% decrease (p = 0.94)	33% decrease (p = 0.26)
After construction (after April 1, 2012)	0.46	55% decrease ( <b>p = 0.006</b> )*	70% decrease ( <b>p = 0.004</b> )*

\*Significant difference (p < 0.05)

Figure 3 is a scatterplot showing the observed versus the modeled test (pilot) watershed area total flows for each of the events during the after re-lining baseline period. As shown, these are all close to the line of equivalent values.




**Figure 3. Observed versus modeled flows during final baseline conditions (after re-lining).**

**Summary of Biofilter Measurements during Rain Events**

A tremendous amount of information was collected during this project, ranging from drainage area characteristics to runoff and flow monitoring data. The extended construction period resulted in only several events to be monitored after the construction period for analyses in this report, but the monitoring period is being extended into the next rainy season to obtain additional information and data.

The infiltration rates in the biofilters were monitored during actual rains by measuring the rate of drop of the ponded water during large rains. Statistical analyses identified three distinct groups of these data, as shown in the following list and group box and whisker plot (Figure 4):


- **Very low:** average 0.36 in/hr; range 0.19 to 0.62.
- **Moderate:** average 1.8 in/hr; range 0.08 to 5.0.
- **Very high:** average 3.2 in/hr; range 1.6 to 5.0.



**Figure 4. Measured infiltration rates in biofilters during actual rains.**

- The time to ponding after the rain started averaged about 0.5 hour, but it ranged from about 0.04 to 3.3 hours. The maximum depth of ponding was also separated into three categories, as shown below (separated by street addresses):
- **Shallow:** sites 2 (1325) and 8 (1222); average: 1.1 in., range: 0.0 to 5.6 in.
- **Moderate:** sites 1 (1324), 3 (1419), 4 (1612), 5 (1336), and 7 (1140); average: 3.3, range: 0.0 to 13.2
- **Deep:** site 9 (1112); average: 5.4, range: 2.8 to 8.3

Figure 5 is a group box and whisker plot showing these three combined sets of data for maximum depth of ponding.



**Figure 5. Maximum ponding depth observed in biofilters during actual rains.**



Laboratory column tests were conducted to investigate the biofilter media used at the Kansas City sites. Columns were constructed to measure the infiltration rates as a function of compaction (and therefore density). The density of the media column with hand compaction was 1.00 grams per cubic centimeter ( $\text{g}/\text{cm}^3$ ); the density of the standard proctor media column was 1.13  $\text{g}/\text{cm}^3$ , and the density of the modified proctor column was 1.12  $\text{g}/\text{cm}^3$ . The soil media has a median particle size ( $D_{50}$ ) of about 1.9 millimeters (mm) and a very high uniformity coefficient ( $C_u$ ) of 39. The porosity of the media for the hand compaction columns was 0.36, 0.15 for the standard proctor compaction columns, and 0.25 for the modified compaction columns.

Infiltration data for different test trials were fitted to Horton equation by using multiple nonlinear regressions to estimate  $f_c$  (the saturated soil infiltration rate),  $f_0$  (the initial rate), and  $k$  (the rate coefficient), using the observed data. The saturated rates were of greatest interest as they would apply during most of the operation during events. The estimated infiltration rates of the saturated media ranged from 0.4 to 0.8 in/hr for the hand compaction tests (initial rates were about 0.75 to 3 in/hr), and 0.4 to 0.9 in/hr for the standard proctor compaction tests, and 0.03 to 0.33 in/hr for the modified proctor compaction tests. Only the modified compaction level significantly affected the infiltration rates. More than 90% of the media is larger than 100 micrometers ( $\mu\text{m}$ ), with appreciable fractions clearly in the coarse sand category, resulting in a relatively robust media with minimal compaction potential. Media with large amounts of sand do not compact as much as media having more fines because of the structural support of the sand grains. Figure 6 contains example plots of laboratory infiltration measurements fitted to the Horton equation for the hand compaction (least dense) tests.





Figure 6. Kansas City biofilter media infiltration rates during column tests for hand compacted density.


Samples were also collected of inflowing water entering the biofilters for analyses. Figure 7 is a particle size distribution (PSD) plot for the 20 influent samples. The median particle size (by mass) is about 30  $\mu\text{m}$ , and about 25% were larger than 100  $\mu\text{m}$ . The observed median size is typical for stormwater

gutter/inlet samples, but it is larger than would be expected at a stormwater outfall (the larger particles are subjected to deposition in the drainage system).




**Figure 7. Particle size distribution for curb-cut influent stormwater samples.**

The stir plate and pipette total suspended solids (TSS) method has been shown to have the highest yield and most consistent results compared to the suspended solids concentration (SSC) values as standards. The shake and pour method shows reduced values compared to the pipette and SSC methods. The relationship between the shake and pour TSS and stir plate and pipette TSS values are consistent but with about a 25% bias with the shake and pour results being less, as shown in Figures 8 and 9.



1: TSS by shake and pour; 2: TSS by stir and pipette; 3:SSC by cone splitter

**Figure 8. Particulate solids concentration comparisons because of different analytical methods.**



**Figure 9. TSS by shake and pour versus TSS by stirring and pipetting.**

The SSC data are statistically separated into two categories, as shown below:

Group	Size	Mean	Std Dev	COV	Max	Min
1222 and 1325 SSC	21	101	141	1.4	693	25
1324 and 1419 SSC	12	171	129	0.8	543	59

Notes: COV = coefficient of variation value; Std Dev = standard deviation

**Summary of Monitored and Modeled Performance of Stormwater Control Practices**

The Kansas City GI demonstration project site is unique because a very large portion of the test (pilot) area receives direct treatment from many separate stormwater control devices, and the large area is being monitored to demonstrate the actual flow reductions. However, as in all retrofit installations, stormwater controls could not be placed to treat all the flows from the entire watershed area because of interferences from existing infrastructure, large trees, and surface drainage paths. Figure 10 is a map showing the subareas having stormwater control before being discharged into the combined sewer. The blanked-out areas drain into the combined sewers directly without any surface infiltration or retention control. Some areas are treated by multiple control units, with overflows from upgradient devices flowing into downgradient controls.



**Figure 10. Areas receiving surface stormwater control before being discharged into the combined sewer.**

The total impervious area for the area being treated is about 45%; the total impervious area for the untreated area is about 37%, indicating greater flows from the treated areas than indicated if based only on the total subareas. The calculations and modeling efforts determine the maximum amounts of stormwater control possible, reflecting the different land development characteristics in the treated and untreated subareas, and shows the sensitivity of the native soil conditions on biofilter performance.

Figure 11 compares the modeled to the monitored events that occurred after the majority of the site construction was completed. The model used a native soil infiltration rate of 1 in/hr below the biofilters, which results in reasonable predictions as shown in this figure. Lower native infiltration rates (as in the initial design calculations) resulted in significantly decreased calculated discharges, resulting in poor fits of the data.




Figure 11. Modeled versus observed flows in the test (pilot) area after construction of stormwater controls.

One of the main features of WinSLAMM is its ability to calculate these source contributions for varying rain conditions. Figure 12 illustrates the source contributions for the test (pilot) area without stormwater controls, for rains ranging from 0.01 to 4 in. The sources of flows (and pollutants) vary with the rain characteristics, but the directly connected areas are most important for the small- and intermediate-sized rains, with pervious contributions becoming more important as the rains increase in size.




Figure 12. Sources of runoff volume during different rain events (no control practices).



Table 3 summarizes the characteristics for each category of stormwater control used in the test (pilot) area, including the number of each device type and the average areas being treated by each type of control. The device areas as a percentage of drainage area are also shown and range from about 1.5 to 2% for the biofilters to 9% for the bioswale. The porous pavement sidewalks treat 100% of the sidewalk areas because they do not receive runoff from adjacent areas.

**Table 3. Summary of the stormwater controls constructed in the test (pilot) watershed**

Design plan component	Structural description	Number of this type of stormwater control units in test (pilot) area	Drainage area to device area ratio	Device as a % of the drainage area	Drainage area for each unit (ac)	Total area treated by these devices (ac)
Bioretention	Bioretention without curb extension	24	61.8	1.6%	0.40	9.6
	Curb extensions with bioretention	28	66.1	1.5%	0.40	11.2
	Shallow bioretention	5	61.8	1.6%	0.40	2.0
Bioswale	Vegetated swale infiltrates to background soil	1	11.2	8.9%	0.50	0.5
Cascade	Terraced bioretention cells in series	5	53.0	1.9%	0.40	2.0
Porous sidewalk or pavement	With underdrain	18	1.0	100.0%	0.015	0.3
	With underground storage cubes	5	1.0	99.9%	0.015	0.1
Rain garden	Rain garden without curb extension	64	35.8	2.8%	0.40	25.6
	Curb extensions with rain gardens	8	66.0	1.5%	0.40	3.2
Total number of control units (w/o porous pvt):		135			Total area treated:	54.4
Total area treated (acres):		54.4				
Area per unit:		0.40				

The calculated runoff volume reductions range from 86 to 100% for a 4-year continuous simulation period corresponding to the site total monitoring period (September 2008 through October 2012). The predicted maximum water depths in the biofilters ranged from about 2 to 5 in., similar to the water depths observed. The maximum ponding times for the biofilters ranged from about 60 to 90 hours. Only a single event in the 4 years of simulation had a holding time longer than 3 days, the typical criterion for mosquito control. Only about one-third of the events likely have any surface or underdrain discharges, and these amounts would be very small compared to the untreated volumes.

**Summary of Performance Production Functions for the Design and Analysis of Stormwater Management Controls**

The first stormwater control that should be considered in an area is disconnecting the currently directly connected impervious areas, such as roofs and paved parking lots. The directly connected roofs in the test area contribute only about 5.8% of the total area flows, whereas the much greater area of disconnected roofs contribute about 7.2% of the annual runoff from the whole 100-acre area. The current flow

contributions of all roofs in the area total about 13%. If all the roofs were directly connected, they would contribute about 31% of the total area runoff, and the runoff from the total area would increase by about 25%, a significant increase. In contrast, if the currently directly connected roofs were disconnected through a downspout disconnection program, the total roof contribution would decrease to about 9%, and the total area runoff would decrease by about 5%. Because about 85% of the existing roofs in the area are already disconnected, the benefits of controlling the remaining directly connected roofs are, therefore, limited. Directly connected roofs in the study area contribute about 4.5 times the amount of runoff per unit area as the disconnected roofs. This indicates that about 78% of the annual runoff from the disconnected roofs is infiltrated as it passes over previous areas on the way to the drainage system. Therefore, it is much less cost-effective to use roof runoff controls for the runoff from the disconnected roofs compared to runoff controls for the directly connected roofs. The benefits of disconnecting currently connected paved parking or storage areas are similar to the benefits shown above for roofs.

Private rain gardens for controlling roof runoff are being used in the residential areas in the test (pilot) area. As runoff enters the device, water infiltrates through the engineered soil or media (or natural soil, as in a rain garden). If the entering rain cannot all be infiltrated through the surface layer, the water ponds. If the ponding becomes deep, it can overflow through the broad-crested weir, or other surface outlet. The percolating water moves down through the device until it reaches the bottom and intercepts the native soil. If the native soil infiltration rate is greater than the percolation water rate, there is no subsurface ponding; if the native soil infiltration rate is slower than the percolation water rate, ponding occurs. As shown in Figure 13, as the rain garden size increases in relationship to the roof area, less water is discharged to the collection system. About 90% of the long-term runoff would be infiltrated for a rain garden that is about 20% of the roof area (similar to the monitored roof runoff rain gardens in this study).




Figure 13. Percentage reduction in annual roof runoff with rain gardens.

Rain gardens 20% of the roof area would also provide about 90% runoff reductions from the directly connected roofs during the 1.4-in regulatory design storm *D*.

Biofilter performance is based on the characteristics of the flow entering the device, the infiltration rate into the native soil, the filtering capacity and infiltration rate of the engineered media fill if used, the amount of rock fill storage, the size of the device and the outlet structures for the device. WinSLAMM was used with the calibration files prepared for the Kansas City demonstration project to examine alternative biofilter and bioinfiltration device designs for the residential test (pilot) area. Four infiltration rates for the native subsurface soil were examined: 0.2, 0.5, 1.0, and 2.5 in/hr (corresponding to sandy silt loam, loam, sandy loam, and loamy sand soils, respectively). The lowest rate (0.2 in/hr) was the assumed early infiltration rate used by the design consultants for the original designs. Site surface soil measurements in the test watershed indicated 1 in/hr, or greater, infiltration rates for rains lasting 2 hours or less. Site measurements of the biofilters during storms indicated infiltration rates of the media and device at 1.8 in/hr, and modeling indicated likely subsurface rates of about 1 in/hr (or greater) to result in the observed performance during the rains (almost complete infiltration with very little overflow or subsurface underdrain discharges). The use of gravel storage is important for only the low infiltration rate conditions: once the infiltration rate is about 1 in/hr, or more, this additional storage is not needed, as far as benefiting the long-term infiltration conditions. As shown in Figure 14, for the low infiltration rates, the use of underdrains degrades the performance of the biofilters because the underdrains discharge subsurface ponding water before it can completely infiltrate (but underdrains do decrease surface ponding, a desired objective). The use of a slow underdrain (as indicated here by the SmartDrain™), results in an intermediate effect, while also decreasing periods of long surface ponding. As with the gravel storage, underdrains have very little effect on performance when the native subsurface native infiltration rate is about 1 in/hr, or greater.




Figure 14. Effects of underdrains in biofilters on annual runoff reductions for subsurface native soil infiltration rates of 0.5 in/hr.

Biofilter media is likely to fail, resulting in very low infiltration rates with rapid and excessive particulate solids loadings. Generally, particulate loads of between 10 and 25 kilograms per square meter (kg/m<sup>2</sup>) might lead to significantly reduced infiltration. A planted biofilter is likely to be able to incorporate this additional material into the soil as healthy plants can keep the infiltration rates at a desired level, if this accumulative load occurs over at least 10 years. However, if this load occurs in just a few years, it is likely to overwhelm the system, resulting in premature clogging. This is more of a problem for small biofilters receiving runoff having high particulate solids concentrations, such as parking lots where space is limited. Pretreatment using grass filters or swales can reduce these problems. For this study area, if the biofilters are at least 1 to 3 percent of the residential drainage area, the particulate loading is not likely to be a problem. The biofilters and bioinfiltration devices in the test (pilot) area are about 1.5 to 2% of the residential drainage areas. For the 1 in/hr subsurface infiltration rate, this size of treatment device is expected to provide about a 90% reduction in the annual flows for the areas treated, with very little overflows. The SmartDrain™ installation is expected to have only about 1% of the annual flows being captured by this underdrain. These calculated conditions are all similar to the observed conditions during the brief monitoring period.

The WinSLAMM porous pavement control in version 10 has full routing calculations associated with subsurface porous media storage and also allows runoff from adjacent areas. Table 4 summarizes the calculated performance of porous pavements located at paved parking/storage areas. The given underlying soil is a loam soil. A conventional 3-in. perforated pipe underdrain was also assumed. As indicated, even the smallest area examined (25% of the area as porous pavement) had very good runoff volume reductions. The porous pavement was cleaned every year, restoring much of the lost surface infiltration rate capacity in this example. If the area was not cleaned, clogging would be expected in about 8 years, based on field experience. Care needs to be taken to prevent runoff of stormwater having high particulate solids loads, or excessive leaf debris on the porous pavement because both conditions can result in premature failure. Porous pavements are also not recommended for areas having substantial traffic or receiving other more highly contaminated runoff (especially snowmelt in areas using deicing chemicals) to reduce groundwater contamination potential. Sidewalks and walkways, along with residential driveways are the most suitable areas for porous pavement installations.

**Table 4. Porous pavement performance (paved parking and storage area; loam soil; 3-in underdrains every 20 ft.)**

Porosity as a % of paved parking area	Rv	Volume reduction (%)	Expected habitat conditions	TSS (mg/L)	Solids discharged (lbs/yr)	TP (mg/L)	TP load (lbs)	Cu (µg/L)	Cu load (lbs)
none	0.75	n/a	poor	130	812	0.21	13	21	1.3
25%	0.06	92	good	130	60	0.21	0.98	21	0.098
50%	0.05	93	good	130	58	0.32	0.94	12	0.093
100%	0.05	93	good	130	58	0.21	0.94	21	0.093

Note: Cu = copper; Rv = volumetric runoff coefficient, the ratio of runoff to rain volume; TP = total phosphorus; TSS = total suspended solids

Grass filters have broad, shallow flows. WinSLAMM calculations for grass filters are based on extensive pilot-scale and field measurements of grass swales and filters. Table 5 summarizes the performance of grass filters for controlling runoff from 2 acres of an impervious area. As the grass filters become steep, they lose some of their performance because of the faster flowing water reducing the effective infiltration rates.

**Table 5. Grass filter performance for different soils and slopes**

Description	Rv	% runoff volume reduction	TSS (mg/L)	Solids yield (lbs/yr)	% solids yield reduction	Peak runoff rate (cfs)	% peak runoff rate reduction	TP (mg/L)	TP load (lbs)	Cu (µg/L)	Cu load (lbs)
base conditions, no controls	0.55		100	1040		4.6		0.28	29	17	1.7
grass filter 0.5% slope	0.17	69	91	300	71	2.6	43	0.27	8.7	16	0.52
grass filter 2 to 25% slopes	0.22	60	90	376	64	3.5	24	0.26	11	16	0.67

Note: cfs = cubic feet per second; Cu = Copper; Rv = Volumetric runoff coefficient; TP = total phosphorus; TSS = total suspended solids


Grass swales are evaluated in WinSLAMM with the same general processes as for grass filters, except that concentration flows occur. Table 6 summarizes the performance of a swale for two different soil conditions. As expected, the swale water volume and pollutant reduction performance is better for the loam soil than for the silty soil.

**Table 6. Grass swale performance**

Description	Rv	% runoff volume reduc.	Expected habitat conditions	TSS (mg/L)	% solids yield reduc.	Solids yield (lbs/yr)	Peak runoff rate (cfs)	% peak runoff rate reduc.	TP (mg/L)	TP load (lbs)	Cu (µg/L)	Cu load (lbs)
base conditions, no controls	0.55		poor	100		1040	4.6		0.28	29	17	1.7
silty soil	0.33	40	poor	86	92	535	4.4	4	0.25	16	16	0.98
loam soil	0.16	71	fair	87	92	263	2.9	37	0.26	7.8	16	0.47

Note: cfs = cubic feet per second; Cu = Copper; Rv = Volumetric runoff coefficient; TP = total phosphorus; TSS = total suspended solids

Benefits associated with stormwater use for irrigation and other on-site uses can be calculated on the basis of site specific information. Irrigation of land on the homeowner’s property was considered the beneficial use of most interest. Rain barrel/water cistern effectiveness is related to supplemental irrigation and how that matches the rainfall deficit (evapotranspiration [ET], minus rainfall) for each season. The continuous simulations used a typical one-year rain series and average monthly ET values for varying amounts of roof runoff storage. Figure 15 shows the expected roof runoff reductions for different storage tank volumes. One 35-gallon rain barrel is expected to reduce the total annual directly connected roof runoff by about 24%, if the water use could be closely regulated to match the irrigation requirements, such as with an automated irrigation system with soil moisture sensors (not likely to be used in conjunction with a few rain barrels, but more likely with a large tank that can be pressurized). If four rain barrels were used for each house, such as one at each corner of a house receiving runoff from separate roof downspouts, the total annual roof runoff volume reductions from the roofs could be as high as about 40%. A small water storage tank about 5 ft in diameter and 6 ft tall could result in about 75% total annual runoff reductions from directly connected roofs; a larger 10-ft diameter tank that is 6 ft tall could approach complete roof runoff control. The 5-ft diameter tank is also expected to provide almost complete control of runoff from the regulatory design storm *D*. These calculations are very sensitive to location as the rainfall deficit varies greatly throughout the country. The central part of the United States (including Kansas City) has a relatively large rainfall deficit with rainfall occurring at relatively optimal times for enhanced beneficial uses of roof runoff. Other areas of the county are not as suitable for this control.



**Figure 15. Percentage reduction in roof runoff with irrigation of landscaped areas in Kansas City.**

For maximum use of the roof runoff to decrease runoff volumes, it is desired to irrigate at the highest rate possible, without causing harm to the plants. For a healthy lawn, total water applied (including rain) is generally about 25 mm (1 in.) of water per week, or 100 mm (4 in.) per month. Excessive watering is harmful to plants, so indiscriminate over-watering is to be avoided. Some plants can accommodate additional water. As an example, Kentucky bluegrass, the most common lawn plant in the United States, needs about 64 mm/week (2.5 in/week), or more, during the heat of the summer and should receive some moisture during the winter.

The biofilter option in WinSLAMM can be configured to represent green roofs. Basically, the green roof area is used as the area of the biofilter and no natural infiltration allowed. The only outlets include the required broad crested weir for surface overflows, underdrains, and ET. Partial roof coverage can be modeled by using a smaller area for the biofilter to represent the area dedicated to green roof processes. Table 7 summarizes the calculated performance of a green roof system for different roof coverages. The concentrations are similar for all scenarios because almost all the water is filtered by the roof media, with little being discharged to the surface overflows. The available ET resulted in about 25% reductions in runoff volume reductions. If more surface storage is provided in the green roof design and if more efficient plants are used, it is likely that these runoff volume reductions could be about double the reductions shown here.



**Table 7. Calculated green roof performance**

Green roof as a % of flat roof area (3-in conventional underdrains every 20 ft)	Rv	Volume reductions (%)	TSS (mg/L)	Solids discharged (lbs/yr)	Peak runoff rate (cfs)	Peak rate reductions (%)	TP (mg/L)	TP load (lbs)	Cu (µg/L)	Cu load (lbs)
none	0.8	n/a	33	55	0.76	n/a	0.22	3.6	11	0.18
25%	0.71	11	24	35	0.57	25	0.17	2.4	9.8	0.14
50%	0.66	18	24	33	0.45	41	0.16	2.2	9.7	0.13
100%	0.6	25	24	29	0.38	50	0.16	2	9.7	0.12

Note: cfs = cubic feet per second; Cu = Copper; Rv = volumetric runoff coefficient; TP = total phosphorus; TSS = total suspended solids

### **Summary of Decision Analysis Methods to Assist in the Selection of Stormwater Control Programs**

Stormwater quality models can produce copious amounts of information for large numbers of alternative management programs that contain a wide variety of individual stormwater control practices, as described by Pitt and Clark (2008). In most cases, just a few of the values are sufficient for quick comparisons. These include the overall percent runoff and particulate solids reductions, the final Rv and runoff volume, and the resulting particulate solids yields and concentrations. WinSLAMM also calculates the life-cycle costs and the expected habitat conditions of the receiving waters to be compared, in addition to flow-duration information. The use of decision analysis procedures, based on methods developed by Keeney and Raiffa (1976) with the WinSLAMM batch processor allows semi-automatic formal evaluations of alternative stormwater control programs considering multiple conflicting objectives.

This decision analysis approach has the flexibility of allowing for variable levels of analytical depth, depending on the problem requirements. The preliminary level of defining the problem explicitly in terms of attributes often serves to make the most preferred alternatives clear. The next level of analysis might consist of a first-cut assessment and ranking. Several different utility function curve types can be used with a simple additive model. Spreadsheet calculations with such a model are easily performed, making it possible to conduct several decision analysis evaluations using different tradeoffs, representing different viewpoints. It is possible there will be a small set of options that everyone agrees are the best choices. Also, this procedure documents the process for later discussion and review. Sensitivity analyses can also be conducted to identify the most significant factors that affect the decisions. The deepest level of analysis can use all the analytical information one collects, such as probabilistic forecasts for each of the alternatives and the preferences of experts over the range of individual attributes. Monte Carlo options available in WinSLAMM can also be used that consider the uncertainties in the calculated attributes for each option.

Therefore, decision analysis has several important advantages. It is very explicit in specifying tradeoffs, objectives, alternatives, and sensitivity of changes to the results. It is theoretically sound in its treatment of tradeoffs and uncertainty. Other methods ignore uncertainty and often rank attributes in importance without regard to their ranges in the problem. This decision analysis procedure can be implemented flexibly with varying degrees of analytical depth, depending on the requirements of the problem and the available resources.

### **Conclusions**

WinSLAMM has been undergoing development and changes since the mid-1970s and now includes a wide range of options. Over the years, periodic major upgrades have occurred to take advantage of advancing computer capabilities and knowledge gained through stormwater research, and to respond to requests by users.

The expected major sources of runoff from the test area vary for different rain depth categories. A detailed land survey found that most of the homes in the test watershed already have disconnected roofs (85% of all roof areas) and that the total roof areas account for 13% of the total study area. The directly connected roofs, which make up only 2% of the study area, contribute 6% of the total annual flows. The disconnected roofs, which constitute 11% of the area, contribute 7% of the total flows. Thus complete control of the runoff from the directly connected roofs would reduce the total area runoff by only a very small amount, less than can be reliably detected by monitoring the total runoff from the area. The modeling calculations illustrate the different effects of using rain gardens, rain barrels or tanks, or simple disconnections of the directly connected roofs. The results are presented on the basis of the effects for the directly connected roofs alone; if calculated for the entire drainage area, the contribution would be less than 5%. If all the roofs were directly connected, they would then contribute 30% of the annual flows, and the outfall consequences for the whole area from these roof controls would be substantially larger.

Performance plots were prepared comparing the size of rain gardens to the roof areas to result in expected roof runoff flow reductions. Rain gardens that are 20% of the roof areas are expected to result in about 90% reductions of the total annual flow compared to directly connected roofs. This rain garden size is about 200 ft<sup>2</sup>/house (about 20 m<sup>2</sup>/house) which could, for example, be composed of several smaller rain gardens each located at a downspout. Reductions of 50% in the total annual flows could be obtained if the total rain garden area per house was 7% of the roof area.

Rain barrel effectiveness is related to the need for supplemental irrigation and how that matches the rains for each season, or the use of water resistant plants. The continuous simulations used a typical one-year rain series and average monthly ET values for varying amounts of roof runoff storage. A single 35-gal (133 L) rain barrel is expected to reduce the total annual runoff by 24% from the directly connected roofs, if the water use can be closely regulated to match the irrigation requirements. If four rain barrels were used (such as one on each corner of a house and receiving runoff from separate roof downspouts), the total annual volume reductions could be as high as 40%. Larger storage quantities result in increased usage but likely require larger water tanks. A small tank with a 5-ft (1.5 m) diameter and 6 ft (1.8 m) high is expected to result in 75% total annual runoff reductions; a larger, 10-ft (3 m) diameter tank that is 6 ft (1.8 m) tall would approach complete roof runoff control.

The use of rain barrels and rain gardens together at a home is more effective than using either method alone: the rain barrels would overflow into the rain gardens, so their irrigation use is not quite as critical. To obtain reductions of 90% in the total annual runoff, it is necessary to have at least one rain garden/house, unless the number of rain barrels is more than 25 (or one small water tank)/house. In such a case, the rain gardens can be reduced to 80 ft<sup>2</sup>/house (7 m<sup>2</sup>/house).

The best combination of control options is not necessarily obvious. The CSO control program must meet permit requirements, which specify certain amounts of upland storage in the watershed. Other elements, including costs, aesthetics, improvements to streetside infrastructure, and other potential benefits, must also be considered in a decision analysis framework. Caution is needed when comparing the amount of site runoff storage provided by these upland controls to the total storage goals to meet the objective of the CSO control program (288,000 gal). As an example, storage provided at directly connected roofs needs to be discounted by a factor of about 1.4 because not all the storage is available during all rains, and because their drainage is influenced by low infiltration rates through the native soils, compared to flow controls directly connected to the combined sewers. In addition, the curbcut biofilters also have access to almost all the flows in the area, so their storage volumes are more effectively used. More significantly, if storage was provided at roofs that are already disconnected, their storage volumes would need to be discounted by a factor of 4.5 when compared to the total site storage goals, because of the existing infiltration already occurring from the disconnected roofs.

Cost-effective designs of biofilters for the area can be identified by examining the production functions provided in this report. For slowly infiltrating native subsoils (less than 1 in/hr), the use of additional subsurface storage and restricted underdrains can be very beneficial. For higher rate soils, these features have minimal benefit on performance. The biofilters being about 1.5 to 2% of the drainage area in the residential area are expected to provide about 90% long-term reductions in stormwater runoff to the combined sewer for the areas treated. However, only about half of the test (pilot) watershed received runoff control, so the overall runoff volume reduction benefit is expected to be about 40 to 50%. Subsurface drainage water from the biofilters undergo substantial retention (several hours) which would benefit peak combined sewer flows, but the volume affected is relatively small.

### **Considerations that Affect Use of Different Stormwater Controls**

Certain site conditions could restrict the applicability of some of these controls. The following comments are mostly summarized from Pitt et al. (2008a) and from preliminary research reported by others at recent technical conferences.

#### *Sodium Adsorption Ratio (SAR)*

The SAR can radically degrade the performance of an infiltration device, especially when clays are present in the media or underlying soils. Media or soils with an excess of sodium ions, compared to calcium and magnesium ions, remain in a dispersed condition, and are almost impermeable to rain or applied water. A *dispersed* soil is extremely sticky when wet, tends to crust, and becomes very hard and cloddy when dry. Water infiltration is therefore severely restricted. Dispersion caused by sodium can result in poor physical soil conditions and water and air do not readily move through the soil. An SAR value of 15 or greater indicates that an excess of sodium will be adsorbed by the soil clay particles. This can cause the soil to be hard and cloddy when dry, to crust badly, and to take water very slowly. SAR values near 5 can also cause problems, depending on the type of clay present. Montmorillonite, vermiculite, illite and mica-derived clays are more sensitive to sodium than other clays. Additions of gypsum (calcium sulfate) to the soil can be used to free the sodium and allow it to be leached from the soil in some situations, but recent laboratory tests with biofilter media at UA indicate minimal improvement.

The SAR is calculated by using the concentrations of sodium, calcium, and magnesium (in meq) in the following formula:

$$SAR = \frac{Na^+}{\sqrt{\frac{(Ca^{+2} + Mg^{+2})}{2}}}$$

SAR has been documented to be causing premature failures of biofiltration devices in northern communities, such as several in the Madison, Wisconsin, area documented by University of Wisconsin soil science student projects. These failures occur when snowmelt water is allowed to enter a biofilter that has clay in the soil mixture. To minimize this failure potential, the following are recommended:

1. Do not allow snowmelt water to enter a biofilter unit. As an example, roof runoff likely has little salt and SAR problems seldom occur for roof runoff rain gardens, even in areas having large amounts of clay in the soil. However, if driveway or walkway runoff waters affected by saline deicing chemicals are discharged to these devices, problems can occur. The largest problem is associated with curb-cut biofilters or parking lot biofilters in areas with snowmelt entering these devices, especially if clay is present in the engineered backfill soil/media.
2. The biofilter media should not have any clay. It appears that even a small percent of clay in the media can cause a problem, but little information is available on the tolerable clay content of biofilter soils. Some biofilter guidance documents recommend an appreciable clay content to

slow the water infiltration rate (and therefore increase the hydraulic detention time in the system) to improve pollutant capture. Instead of clay used to control the infiltration rates, restrictive underdrains, such as the SmartDrain™, should be used. Guidance documents recommending fines in the biofilter mixture are usually from areas having mild climates with little or no snowmelt (and deicing chemical use).

3. The most robust engineered soil mixtures used in biofilters tend to be mixtures of sand and an organic material (such as compost, if nutrient leaching is not a concern, or Canadian peat for a more stable material having little nutrient leaching potential). Other mixtures of biofilter media can be used targeting specific pollutants, but these are usually expensive and likely only appropriate for special applications.
4. If a suitable soil mixture not having clay (should be less than 3% based on preliminary information), and if snowmelt water will affect the system, biofilters should not be used in the area. As noted above, rain gardens receiving only roof runoff might be suitable in most situations because of the absence of excessive sodium in the runoff water.

The Kansas City biofilter media is being further tested, but it appears to have minimal amounts of clays. It is expected that system monitoring during the winter and spring will enable decreased performance to be detected, if present.

#### *Clogging of Infiltration Devices*

The designs of infiltration devices need to be checked for their clogging potential. For example, a relatively small and highly efficient biofilter (especially in an area having a high native infiltrating rate) could capture a large amount of sediment. Having a small surface area, this sediment would accumulate rapidly over the area, possibly reaching a critical clogging load early in its design lifetime. Therefore, the clogging potential can be calculated on the basis of the predicted annual discharge of suspended solids to the biofiltration device and the desired media replacement interval. Infiltration and bioretention devices can show significantly reduced infiltration rates after about 2 to 5 lb/ft<sup>2</sup> (10 to 25 kg/m<sup>2</sup>) of particulate solids have been loaded (Clark 1996, 2000; Urbonas 1999). Deeply rooted vegetation and a healthy soil structure can extend the actual life much longer. However, abuse (especially compaction and excessive siltation) can significantly reduce the life of the system. If this critical load accumulates relatively slowly (taking about 10 or more years to reach this total load) and if healthy vegetation with deep roots are present, the infiltration rate might not significantly degrade because of the plant's activities in incorporating the imported sediment into the soil column. If this critical load accumulates in just a few years, or if healthy vegetation is not present, the premature failure from clogging could occur. Therefore, relatively large surface areas might be necessary in areas having large sediment content in the runoff, or suitable pretreatment to reduce the sediment load before entering the biofilter or infiltration device would be necessary.

For some of the calculated Kansas City biofilter size options, the sediment loading rates are high (mostly because of treatment of relatively large areas compared to the size of the biofilters), which could result in premature failure if the minimum sizes were used according to infiltration goals alone. Therefore, a larger area might actually be needed to prevent premature failure because of clogging. The following considerations apply to infiltration/biofiltration devices to minimize clogging failure:

1. Use a sufficient infiltration area to enable at least 10 years before the critical sediment loading (10 to 25 kg/m<sup>2</sup>) occurs and maintain a healthy, deep-rooted plant community to incorporate the sediment into the soil horizon.
2. Use pretreatment to reduce the sediment load entering a biofilter to reduce the TSS concentrations to match the desired maintenance or clogging interval. Using a grass filter/grass swale before a biofilter can significantly reduce the loading to the device, extending the operational life.

The characteristics for the Kansas City biofilters in the test area indicate that most are likely sufficiently sized to result in minimal clogging potential. However, there might be a desire to reduce the sizes appreciably during future construction to reduce costs, which could result in early failure.

#### *Groundwater Contamination Potential and Over-Irrigation*

The potential for infiltrating stormwater to contaminate groundwater is dependent on the concentrations of the contaminants in the infiltrating stormwater and how effective those contaminants might travel through the soils and vadose zone to the groundwater. Source stormwater from residential areas are not likely to be contaminated with compounds having significant groundwater contaminating potential (with the exception of high salinity snowmelt). In contrast, commercial and industrial areas are likely to have greater concentrations of contaminants of concern that might adversely affect the groundwater. Therefore, pretreatment of the stormwater before infiltration might be necessary, or treatment media can be used in a biofilter or as a soil amendment to hinder the migration of the stormwater contaminants of concern to the groundwater. Again, these concerns are usually more of a problem in industrial and commercial areas than in residential areas.

Pitt et al. (2010a) summarized prior research on potential groundwater contamination. Table 8 can be used for initial estimates of contamination potential of stormwater affecting groundwater. This table includes likely worst case mobility conditions using sandy soils having low organic content. If the soil is clayey or has a high organic content (or both), most of the organic compounds would have less mobility than shown. The abundance and filterable fraction information is generally applicable for warm-weather stormwater runoff at residential and commercial area outfalls. The concentrations and detection frequencies would likely be greater for critical source areas (especially vehicle service areas) and critical land uses (especially manufacturing industrial areas), with greater groundwater contamination potential.

Therefore, groundwater contamination potential of infiltrating stormwater can be reduced by

1. Careful placement of the infiltrating devices and selection of the source waters. Most residential stormwater is not highly contaminated with the problematic contaminants, except for chlorides associated with snowmelt.
2. Commercial and industrial area stormwater would likely need pretreatment of reduce the potential of groundwater contamination associated with stormwater. The use of specialized media in the biofilter, or external pretreatment might be needed in these other areas.

The Kansas City test area is expected to have minimal groundwater contamination potential because it has relatively uncontaminated stormwater, and the soil has appreciable clay. However, snowmelt salts could be a problem if deicing salt use is not restricted in the area.

**Table 8. Groundwater contamination potential for stormwater pollutants post-treatment**

Compound class	Compounds	Subsurface injection with minimal pretreatment	Surface infiltration with sedimentation (along with sorption, if possible)*	Surface infiltration and no pretreatment*
Nutrients	Nitrates	Low/moderate	Low/moderate	Low/moderate
Pesticides	2,4-D	Low	Low	Low
	γ-BHC (lindane)	Moderate	Low	Moderate
	Atrazine	Low	Low	Low
	Chlordane	Moderate	Low	Moderate
	Diazinon	Low	Low	Low
Other organics	VOCs	Low	Low	Low
	1,3-dichlorobenzene	Low	Low	<b>High</b>
	Benzo(a) anthracene	Moderate	Low	Moderate
	Bis (2-ethyl-hexyl) phthalate	Moderate	Low	Moderate
	Fluoranthene	Moderate	Moderate	<b>High</b>
	Naphthalene	Low	Low	Low
	Phenanthrene	Moderate	Low	Moderate
	Pyrene	Moderate	Moderate	<b>High</b>
Pathogens	Enteroviruses	<b>High</b>	<b>High</b>	<b>High</b>
	<i>Shigella</i>	Low/moderate	Low/moderate	<b>High</b>
	<i>P. aeruginosa</i>	Low/moderate	Low/moderate	<b>High</b>
	Protozoa	Low	Low	<b>High</b>
Heavy metals	Cadmium	Low	Low	Low
	Chromium	Low/moderate	Low	Moderate
	Lead	Low	Low	Moderate
	Zinc	Low	Low	<b>High</b>
Salts	Chloride	<b>High</b>	<b>High</b>	<b>High</b>

Source: Modified from Pitt et al. 1994

Note: Overall contamination potential (the combination of the subfactors of mobility, abundance, and filterable fraction) is the critical influencing factor in determining whether to use infiltration at a site. The ranking of these three subfactors in assessing contamination potential depends of the type of treatment planned, if any, before infiltration.

\* Even for those compounds with low contamination potential from surface infiltration, the depth to the groundwater must be considered if it is shallow (1 m or less in a sandy soil). Infiltration might be appropriate in an area with a shallow groundwater table if maintenance is sufficiently frequent to replace contaminated vadose zone soils.

### *Retrofitting and Availability of Land*

Most of the control options being used in GI approaches to minimize combined sewer problems are retrofitted in existing urban areas. Their increased costs and availability of land can be detrimental in developing highly effective control programs. The selection and construction of stormwater controls at the time of development (rather than retrofits) is usually much more cost-effective and can provide a higher level of control. However, many controls can be retrofitted into existing areas. Practices that can usually be easily retrofitted get the most attention in stormwater management program in existing areas. Table 9 summarizes some of the problems associated with different stormwater retrofitting options in combined sewer areas.



**Table 9. Retrofitting problems for different stormwater management options**

Controls	Ability to retrofit	Land requirements
<b>Roof Runoff Controls</b>		
Rain Gardens	Easy in areas having landscaping	Part of landscaping area
Disconnections	Suitable only if the adjacent pervious area is adequate (mild slope and long travel path)	Part of landscaping area
Rain Barrels and Water Tanks	Easy, if placed close to a building, or underground large tanks	Supplements landscaping irrigation, no land requirements
<b>Pavement Controls</b>		
Disconnections	Suitable only if adjacent pervious area is adequate (mild slope and long travel path)	Most large, paved areas are not adjacent to suitable large turf areas, except for schools; no additional land requirements, but land is needed.
Biofiltration/bioinfiltration	Easy if one can rebuild parking lot islands as bioinfiltration areas; perimeter areas also possible (especially good if existing stormwater drainage system can be used to easily collect overflows)	Part of landscaped islands in parking areas, along parking area perimeters, or sacrifice some existing parking areas.
Porous Pavement	Difficult as a retrofit must replace complete pavement system; possible if during rebuilding effort	Uses parking area
<b>Street Side Drainage Controls</b>		
Grass Swales	Difficult to retrofit. Suitable if existing swales are to be rebuilt.	Part of street right of way
Curb-cut Biofilters	Difficult to retrofit, but much easier than simple swales. Usually built to work with existing drainage system. Can do extensions into parking lanes/shoulders to increase areas.	Part of street right of way, but can be major nuisance during construction and can consume street side parking. Can be used to rebuild street edge and improve aesthetics.

The range of difficulties and land requirements varies, mostly depending on available opportunities. In some communities, extensive retrofitting is occurring, including installing curb-cut biofilters, during scheduled street improvement projects. These can also be installed during scheduled repaving and sidewalk repairs that usually occur in many areas every few decades. Rain gardens are usually installed by the homeowners with no cost to the city. Many areas have organized efforts encouraging these, for example. Redevelopment and new construction periods are the most suitable times for installing many of these controls to have the least interferences with residents and for the least costs.

## 2. Description of WinSLAMM, the Source Loading and Management Model

WinSLAMM was developed starting in the mid-1970s as part of early EPA street cleaning and receiving water projects in San Jose (Pitt 1979) and Coyote Creek, California (Pitt and Bozeman 1982). The primary purpose of the model is to identify sources of urban stormwater pollutants and to evaluate the efficiency of control practices. During the mid-1980s, the model was expanded to include more management options beyond street cleaning. The Nationwide Urban Runoff Program (NURP) projects (USEPA 1983) provided a large data set for models, specifically, the Alameda County, California (Pitt and Shawley 1982); Bellevue, Washington (Pitt and Bissonnette 1984); and Milwaukee, Wisconsin (Bannerman et al. 1983) projects were used in major expansions of WinSLAMM. Research funded by the Ontario Ministry of the Environment (Ottawa) (Pitt 1987) and the Toronto Area Watershed Management Strategy study in the Humber River (Pitt and McLean 1986) also provided much information on bacteria sources in urban areas. During the mid-1980s, the model started to be used by the Wisconsin Department of Natural Resources (DNR) in its Priority Watershed Program (Pitt 1986). The first Windows version of the model was developed in 1995, and version 10 was recently released. The model is continuously being updated according to user needs and new research (recent and current support from Stormwater Management Authority of Jefferson County, Alabama; the Tennessee Valley Authority, Economic Development group; Wisconsin DNR; U.S. Geological Survey (USGS); Contech Stormwater Solutions; and Hydro-International, for example). Version 10 includes drag and drop watershed elements and more complete flow and particle size routing components, enabling more accurate serial evaluations of stormwater controls in complex arrangements.

Over the years, WinSLAMM has been extensively revised and expanded and now includes a wide range of capabilities. The following lists several important model features:

- The model can evaluate a long series of rain events, usually 1 to 5 years of typical rains are used, but several decades of rain data can also be evaluated.
- The model is based on actual field data. Street dirt accumulation and washoff equations and direct runoff from paved surfaces during all rains are used, for example, based on many thousands of actual measurements.
- The effects of compacted urban soils are also considered.
- Uncertainties of many modeling parameters are represented by built-in Monte Carlo components.
- Costs of control practices can be directly calculated and considered in model runs.
- Runoff flow-duration probability distributions and associated receiving water biological conditions are calculated on the basis of site conditions and the control measures being used.
- The model can be interfaced with several other models for more detailed drainage system and receiving water evaluations.

Prior descriptions of WinSLAMM have been presented during the earlier Engineering Foundation and in the Urban Water Modeling Conference series, and in other publications (Pitt 1986, 1997, 1999; Pitt and Voorhees 2002 for example). The model website (<http://www.winslamm.com/>) also contains further model descriptions and references.


The effectiveness of the control practices in WinSLAMM are calculated using the actual sizing and other attributes of the devices, the source area or outfall location characteristics, and the calculated runoff characteristics. The model does a complete mass balance and routing of water volume and particulate mass, considering the combined effects of all controls. Hydraulic and particle size routing occurs for each device individually, and serial effects of multiple devices are accurately considered in version 10 of the model. The effects of the sedimentation controls are calculated using modified Puls hydraulic routing with surface overflow rate particulate routing. The performance of wet ponds has been verified by extensive monitoring of several ponds (Wisconsin DNR and USGS, with extensive documentation at <http://unix.eng.ua.edu/~rpitt/SLAMMDETPOND/WinDetpond/WinDETPOND%20user%20guide%20and%20documentation.pdf>). The infiltration and biofiltration devices use a combination of hydraulic routing with infiltration and evaporation losses, plus any pumped withdrawals, and have been verified using both small- and large-scale field tests conducted by the USGS (Selbig and Bannerman 2008; Selbig and Balster 2010) and the Kansas City EPA demonstration monitoring (Pitt and Voorhees 2010; Struck 2009), for example. ET losses are also included in the performance calculations. Underdrain filtering is based on extensive tests of media filtration (Pitt et al. 2010b; Sileshi et al. 2010, 2012a, 2012b). Grass swale performance is calculated on the basis of extensive laboratory and outdoor testing of particulate trapping of shallow flowing water and infiltration losses (Kirby et al. 2005; Johnson et al. 2003; Nara and Pitt 2005). Porous pavement performance is calculated on the basis of infiltration losses and clogging effects. Street cleaning and catchbasin benefits are based on extensive EPA research and newer updated research that have examined modern equipment. Hydrodynamic devices are based on the basic sedimentation processes but have been verified by tests conducted by the USGS and the Wisconsin DNR, plus continued tests at UA.

As noted, WinSLAMM conducts a continuous water mass balance for every storm in the study period. As an example, for rain barrels, water tanks or cisterns, capturing roof runoff, the model fills the available storage during rains. Between rains, the storage tank is drained according to the water demands for each month. If the tank is almost full from a preceding close rain (and not enough time was available to drain the storage tank), excess water from the event would be discharged to the drainage system after the tank fills. Curb-cut rain gardens/biofilters along a street are basically a cascading swale system where the site runoff is allowed to infiltrate. If the runoff volume is greater than the capacity of the rain gardens, the excessive water is discharged into the drainage system, or possibly additional downgradient controls. When evaluated together, the cisterns treat the roof runoff first, but the excess water is discharged to the curb-cut rain gardens for infiltration. The continuous simulation drains the devices between events, depending on the interevent conditions.


## Basic Model Setup for Site Characteristics

The first step in setting up a WinSLAMM analysis is to identify the rain and the calibrated parameter files to be used, as shown in Figure 16. The rain file describes the series of rains to be considered in the analysis. In this example shown below, the Kansas City rain file was selected, as shown in Figure 17. The 10 years of rain data from 1990 through 1999 are selected from the complete series. During this period, 920 rains occurred that were 0.01 in., or larger. The largest rain observed in this period was 3.79 in. WinSLAMM has a utility that creates rain files from National Oceanic and Atmospheric Administration data sources. EarthInfo (Santa Monica, California) CDs of these data are most convenient, for example, having many decades of rainfall records from throughout the United States. Figure 16 also shows several other selections for the calibrated parameter files. These describe the rainfall-runoff relationships for the different source areas for the different land uses. These relationships are based on the small storm hydrology concepts described by Pitt (1987) and summarized in a chapter in the urban water systems modeling monograph series (Pitt 1999). The pollutant probability distribution files and the particulate solids concentration files are based on field data, also summarized by Pitt et al. (2005a, 2005b) in chapters published in the urban water systems modeling monograph series. These files contain probability

distributions of the expected particulate-bound pollutant concentrations and the filtered pollutant concentrations for the different source areas. Monte Carlo sampling methods can be optionally used to randomly vary these characteristics for different events, as observed during field monitoring. The street dirt accumulation and washoff mechanisms are specifically modeled, as described by Pitt (1987; Pitt et al. 2005c). Delivery functions are used to describe deposition and transport of the particulates through the storm drainage systems and are again based on field observations.



**Figure 16. Example parameter files selection.**



**Figure 17. Scatterplot of Kansas City, Missouri, rain file.**

Land development characteristics describing local site conditions of the study area are used by WinSLAMM to calculate expected runoff characteristics. Figure 18 is a screenshot for entered site conditions for the commercial example being used in this demonstration; Figure 19 contains screenshots describing the five source areas used in this example. It has two roof area types—one paved parking area, and two landscaped areas. The soils are described as silty in texture (corresponding to originally sandy soils that are typically compacted because of urban activities, or silt-loam soils that have been restored to their natural density conditions; Pitt et al. 2009). Bochs et al. (2008) describe land use patterns and development characteristics, including the procedures used to collect that needed information.

Source Area No.	Source Area	Area (acres)	H	W	P	O	S	B	Source Area Parameters
61	Roofs 1	0.250							Entered
62	Roofs 2	0.250							Entered
63	Roofs 3								
64	Roofs 4								
65	Roofs 5								
66	Paved Parking/Storage 1	1.000							Entered
67	Paved Parking/Storage 2								
68	Paved Parking/Storage 3								
69	Unpaved Prkng/Storage 1								
70	Unpaved Prkng/Storage 2								
71	Playground 1								
72	Playground 2								
73	Driveways 1								
74	Driveways 2								
75	Driveways 3								
76	Sidewalks/Walks 1								
77	Sidewalks/Walks 2								
78	Street Area 1								
79	Street Area 2								
80	Street Area 3								
81	Large Landscaped Area 1								
82	Large Landscaped Area 2								
83	Undeveloped Area								
84	Small Landscaped Area 1	0.250							Entered
85	Small Landscaped Area 2	0.500							Entered
86	Small Landscaped Area 3								
87	Isolated/Water Body Area								
88	Other Pervious Area								
89	Other Dir Cnctd Imp Area								
90	Other Part Cnctd Imp Area								

Figure 18. Base commercial conditions for examples.

Land Use: Commercial  
Source Area: Roofs 1  
Total Area: 0.25 acres

Roofs:  Flat Roof  Pitched Roof

Is the Source Area:  
 Directly Connected or Draining to a Directly Connected Area  
 Draining to a Pervious Area (partially connected impervious area)

Soil Type:  Sandy  Silty  Clayey

Building Density:  Low  Medium or High

Alleys present:  Yes  No

Continue

Roof 1 (directly connected flat roof)

Land Use: Commercial  
Source Area: Roofs 2  
Total Area: 0.25 acres

Roofs:  Flat Roof  Pitched Roof

Is the Source Area:  
 Directly Connected or Draining to a Directly Connected Area  
 Draining to a Pervious Area (partially connected impervious area)

Soil Type:  Sandy  Silty  Clayey

Building Density:  Low  Medium or High

Alleys present:  Yes  No

Continue

Roof 2 (directly connected pitched roof)

Land Use: Commercial  
Source Area: Paved Parking/Storage 1  
Total Area: 1 acres

Is the Source Area:  
 Directly Connected or Draining to a Directly Connected Area  
 Draining to a Pervious Area (partially connected impervious area)

Soil Type:  Sandy  Silty  Clayey

Building Density:  Low  Medium or High

Alleys present:  Yes  No

Continue

Paved parking/storage area 1 (directly connected)

Land Use: Commercial  
Source Area: Small Landscaped Area 1  
Total Area: 0.25 acres

Is the Source Area:  
 Directly Connected or Draining to a Directly Connected Area  
 Draining to a Pervious Area (partially connected impervious area)

Soil Type:  Sandy  Silty  Clayey

Building Density:  Low  Medium or High

Alleys present:  Yes  No

Continue

Small landscaped area 1 (filter strip area)

Land Use: Commercial  
Source Area: Small Landscaped Area 2  
Total Area: 0.5 acres

Is the Source Area:  
 Directly Connected or Draining to a Directly Connected Area  
 Draining to a Pervious Area (partially connected impervious area)

Soil Type:  Sandy  Silty  Clayey

Building Density:  Low  Medium or High

Alleys present:  Yes  No

Continue

Small landscaped area 2 (other pervious areas)

Figure 19. Source area characteristics for the example problem.

Figure 20 shows the pollutant selection form. The pollutants shown are a function of those that are included in the pollutant probability distribution file and are calibrated for the area of interest. In this example, particulate solids (SSC or TSS, depending on the laboratory method used in the monitoring activities; for this file, TSS are used), total phosphorus, and total copper have been selected as examples. As noted, it is possible to select the particulate-bound or dissolved forms of the pollutants separately, or the total concentrations. Special studies have focused on urban area bacteria and for polycyclic aromatic hydrocarbons (PAHs), for example, and those constituents can be described in the pollutant probability distribution file and then selected in this form.

Figure 21 illustrates the form that can be used to select the main output formatting desired. If not selected, option 4 (selected here) is used, which gives a brief summary of the calculated results for the outfall (total study area). It is possible to also select more detailed output formats. However, for many years of rainfall data, some of these options can be very extensive. After the calculations and when viewing the output summary form, it is possible to view the other output forms by having the data reformatted, if desired, without having to rerun the model scenario.

	Particulate	Dissolved	Total
Solids	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Phosphorus	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Nitrates	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
TKN	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
CDD	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Fecal Coliform Bacteria			
Chromium			
Copper	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Lead	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Zinc	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Cadmium (ug/L)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Pyrene	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Other 3			
Other 4			
Other 5			
Other 6			

The pollutants listed above are in the file  
C:\PROGRAM FILES (X86)\WINSLAMM\W1\_GEO01.PPD  
Select a pollutant to evaluate it.

Select All  Clear All  Continue

Figure 20. Selection of pollutants to be evaluated.

Output Format Options

- 1. Source Areas by Land Use for Each Rain - Complete Printout
- 2. Source Area Totals and Outfall Summaries
- 3. Outfall Data Only for Each Rain
- 4. Outfall Summaries Only
- 5. One Line per Event Runoff and Flow Summary
- 6. Continuous Hydrograph With 6 Minute Time Increments
- 7. Continuous Hydrograph With 15 Minute Time Increments
- 8. Continuous Hydrograph With 60 Minute Time Increments

Water Balance Summary of All Detention Ponds

Save Outfall Runoff and Particulate Loading for WinDETPOND Analysis

Save Model Output for Input into CE-QUAL-RIV1

File Name:

Continue

Figure 21. Selection of output formats.

## Base Analyses with No Stormwater Controls

When this basic information is entered in the model, the model scenario is executed and the results are presented in different forms. Figure 22 is the summary output screen that is displayed when the model run is completed. This screen shows runoff quantity and TSS conditions at different locations in the test area. If selected, different costs associated with described stormwater controls are also shown, along with expected receiving water habitat conditions (based on the Center for Watershed Protection’s Impervious Cover Model). This form also has a selection to show the flow-duration curves for the base conditions and with the stormwater controls for the area, as shown in Figure 23. This base example has no stormwater controls, so the two plots are identical. It is also possible to see these data in much higher resolution by selecting another output option.




Figure 22. Basic Summary Screen.




Figure 23. Base flow duration plot.



## Sources of Pollutants of Interest

One of the important uses of WinSLAMM is to calculate the sources of the flows and pollutants of interest for the study area under different rain conditions. Figure 24 is a simple area plot created in Excel from imported values from WinSLAMM. The rain file used for this analysis contains only 12 events, ranging from 0.01 to 4.0 in.

This plot is for runoff volume sources and indicates that the large paved parking/storage area is the major runoff source for all events (from about 85% in the smallest rains to about 55% in the largest rains). The runoff contributions from the roofs combined range from about 15 to 35%, while the landscaped areas start to contribute flows after only about 0.25 in. and reach their maximum contributions after 2.0 in., approaching about 10% of the total flows from the area. This type of plot can be created for each of the constituents selected in the model run and indicate locations for the most effective source controls, or if the sources are too diverse, if outfall or drainage system controls should be stressed. For this example, it is not surprising that the paved parking/storage areas should receive the most attention, followed by the directly connected roofs.




Figure 24. Flow sources for different rains.

## Summary of WinSLAMM Description and use for GI Projects

Over the years, WinSLAMM has been extensively revised and expanded and now includes a wide range of capabilities, including its ability to evaluate stormwater management options using a long series of rain event data, especially important for evaluating combined sewer issues and GI issues. The effectiveness of the control practices in WinSLAMM are calculated on the basis of the actual sizing and other attributes of the devices, the source area or outfall location characteristics, and the calculated runoff characteristics. The model does a complete mass balance and routing of water volume and particulate mass, considering the combined effects of all controls. Hydraulic and particle size routing occurs for each device individually, and serial effects of multiple devices are now accurately considered in version 10.

WinSLAMM conducts a continuous water mass balance for every storm in the study period. As an example, for rain barrels, water tanks or cisterns, for harvesting roof runoff for later irrigation or other beneficial uses, the model fills the available storage during rains. Between rains, the storage tank is drained according to the water withdrawal use for each month. If the tank is almost full from a preceding close rain (and not enough time was available to drain the storage tank), excess water from the event

would be discharged to the drainage system after the tank fills. Curb-cut rain gardens/biofilters along a street are basically a cascading swale system where the site runoff is allowed to infiltrate. If the runoff volume is greater than the capacity of the rain gardens, the excessive water is discharged into the drainage system, or possibly additional downgradient controls. When evaluated together, the cisterns treat the roof runoff first, but the excess water is discharged to the curb-cut biofilters for infiltration. The continuous simulation drains the devices between events, according to the interevent conditions.

The first step in setting up a WinSLAMM analysis is to identify the rain and the calibrated parameter files to be used. The rain file describes the series of rains to be considered in the analysis. The 10 years of Kansas City rains from 1990 through 1999 had 920 rains that ranged from 0.01 to 3.79 in., with an average total annual rainfall of about 35 to 40 in. Land development characteristics describing local site conditions of the study area are used by WinSLAMM to calculate expected runoff characteristics. One of the important features of WinSLAMM is to calculate the sources of the flows and pollutants of interest for the study area under different rain conditions.


### **3. Standard Land Use Development Characteristics used for WinSLAMM Calibration**

Land development information corresponding to the different land uses is needed as an initial step in investigating stormwater quality for an area. This is especially true when modeling expected stormwater characteristics under a variety of conditions. Detailed land use characteristics for a wide variety of land uses are available from several stormwater research projects. These available data were used in conjunction with the detailed, house-by-house surveys conducted in the study area. These data were used in conjunction with the site soils infiltration and density measurements also conducted in the test area.

The Marlborough study area in Kansas City is mostly a medium-density residential area, constructed before 1960, with a small amount of strip commercial area along Troost Avenue and a small portion of a school. UMKC graduate students made detailed inventories of each of the approximately 600 homes in the area by. These data, along with initial modeling results, have been summarized in publications and conferences (Pitt and Voorhees 2009, 2011).

#### **Land Characteristics Survey in Kansas City Test Watershed**

In many areas, detailed aerial coverage with GIS data sets are becoming available, showing and quantifying the finer elements of an area. Figure 25 is an example GIS map from Kansas City, Missouri, showing parts of the study area. This high-resolution GIS data shows all the main elements, but field surveys were still needed to verify the drainage pattern for each impervious element in the test watershed and to identify many other site elements used in stormwater quality modeling.



**Land Use and Impervious Surfaces**



**Figure 25. Detailed GIS coverage showing land cover components of different land uses in the Kansas City test watershed.**

Dr. Deb O'Bannon and her graduate students at UMKC conducted a detailed survey of the development characteristics in the study area. This information was used in conjunction with the overall GIS information describing each land element to identify the specifics needed for the continuous modeling. They surveyed 576 homes in the 100-acre area (90.6 acres was residential). The housing density is therefore about 6.4 homes per acre. Tables 10 and 11 show the original GIS information for the test watershed, from Kansas City, Missouri, city sources and the detailed site data after categorizing by the site data information. The

values shown on Table 11 are the percentages of each subarea of the whole area, while the values shown in parentheses are the breakdown within a single subarea. For example, directly connected roofs make up about 1.87% of the complete 100 acre site, and represent about 15% of all roofs.

**Table 10. Original GIS measurements by Kansas City, Missouri, for the test watershed**

	Decks and patios	Gravel surfaces	Paved roads	Paved parking/storage	Sidewalks	Roofs	Pools	Pervious areas	Sum
<b>All Commercial:</b>									
acres	0.00	0.14	1.92	3.41	0.24	1.36	0.00	1.25	8.32
%	0.00	1.68	23.10	40.93	2.87	16.37	0.00	15.06	100.00
<b>All Office</b>									
acres	0.00	0.00	0.00	0.26	0.03	0.17	0.00	0.11	0.58
%	0.00	0.00	0.00	45.86	5.80	29.72	0.00	18.63	100.00
<b>All Institutional</b>									
acres	0.00	0.00	0.31	0.01	0.04	0.00	0.00	0.19	0.56
%	0.00	0.00	56.07	2.59	6.36	0.00	0.00	34.98	100.00
<b>All Residential</b>									
acres	0.94	0.25	8.08	8.17	2.03	11.72	0.02	59.35	90.56
%	1.04	0.27	8.93	9.02	2.24	12.94	0.02	65.54	100.00
<b>All Combined</b>									
acres	0.94	0.39	10.32	11.85	2.34	13.25	0.02	60.91	100.02
%	0.94	0.39	10.32	11.85	2.34	13.25	0.02	60.89	100.00

**Table 11. Medium-density residential areas (%)**

	Roofs	Driveways	Sidewalks	Parking/storage	Streets	Landscaped	Isolated	Total
<b>Impervious</b>								
directly connected	1.87 (15%)	4.12 (46%)	1.15 (46%)	1.59	9.35			18.07
disconnected	10.57 (85%)	4.03 (45%)	1.34 (54%)					15.95
<b>Pervious</b>								
unpaved (gravel, severely compacted)		0.81 (9%)						0.81
landscaped						65.13		65.13
isolated (swimming pools)							0.05	0.05
<b>Total residential area</b>	<b>12.44</b>	<b>8.95</b>	<b>2.49</b>	<b>1.59</b>	<b>9.35</b>	<b>65.13</b>	<b>0.05</b>	<b>100.00</b>

Even though the major categories for the site agreed when the GIS information and the site surveys were compared, the site surveys were able to distinguish the different categories of pervious surfaces and to quantify how much of the impervious areas were directly connected to the drainage system. This addition information has dramatic effects on the actual stormwater quality and quantity, especially for the small and intermediate storms that produce most of the annual runoff, and even for the 1.4-in. design storm used for the CSO evaluations. As an example, only about 15% of the residential roofs are directly connected. If all were assumed to be connected, large errors in the roof runoff contribution calculations would occur. Similarly, if roof runoff stormwater controls were located at all roofs, those located where the roofs were

already disconnected would have much lower additional benefits in decreasing the area's runoff quantity. Therefore, even though the detailed GIS information is very helpful, the area still needed site surveys. An *Area Description* field sheet is used to record important characteristics of the homogeneous land use areas during the field surveys (Figure 26).

Location:	Site number:
Date:	Time:
Photo numbers:	
<u>Land-use and industrial activity:</u>	
Residential: low medium high density single family multiple family trailer parks high rise apartments	
Income level: low medium high	
Age of development: <1960 1960-1980 1980-2000 >2000	
Institutional: school church hospital other (type):	
Commercial: strip shopping center/mall downtown hotel offices	
Industrial: light medium heavy (manufacturing) describe:	
Open space: undeveloped park golf cemetery	
Other: freeway utility ROW railroad ROW other:	
<u>Maintenance of building:</u> excellent moderate poor	
<u>Heights of buildings:</u> 1 2 3 4+ stories	
<u>Roof drains:</u> % underground % gutter % impervious % pervious	
<u>Roof types:</u> flat composition shingle wood shingle metal other:	
<u>Sediment source nearby?</u> No Yes (describe):	
<u>Treated wood near drainage system or directly connected pavement?</u> No telephone poles fence other:	
<u>Landscaping near road or directly connected impervious surfaces:</u>	
Quantity: none some much	
Type: deciduous evergreen lawn	
Maintenance: excessive adequate poor	
Leafs on street: none some much	
<u>Topography:</u>	
Street slope: flat (<2%) medium (2-5%) steep (>5%)	
Land slope (next to street): flat (<2%) medium (2-5%) steep (>5%)	
<u>Traffic speed:</u> <25mph 25-40mph >40mph	
<u>Traffic density:</u> light moderate heavy	
<u>Parking density:</u> none light (20 to 50%) moderate (50 to 80%) heavy (>80%)	
<u>Width of street:</u> number of parking lanes: number of driving lanes:	
<u>Condition of street:</u> good fair poor	
<u>Texture of street:</u> smooth intermediate rough very rough	
<u>Pavement material:</u> asphalt concrete unpaved	
<u>Driveways:</u> paved unpaved	
Condition: good fair poor	
Texture: smooth intermediate rough	
<u>Gutter material:</u> grass swale lined ditch concrete asphalt	
Condition: good fair poor	
Street/gutter interface: smooth fair uneven	
<u>Litter loadings near street:</u> clean fair dirty	
<u>Parking/storage areas</u> (describe):	
Condition of pavement: good fair poor	
Texture of pavement: smooth intermediate rough unpaved	
Directly connected to drainage: yes no	
<u>Other paved areas</u> (such as alleys and playgrounds), describe:	
Condition: good fair poor	
Texture: smooth intermediate rough	
Directly connected to drainage: yes no	
<u>Other notes/comments:</u>	

**Figure 26. Area description field sheet.**



## Infiltration Rate Monitoring

In addition to the site surveys described above, site-specific soils information is also needed for the area. Disturbed urban soils have infiltration rates that are usually substantially less than the assumed rates according to general county soil maps. For the Kansas City project, small-scale infiltrometers (Figure 27) were used to measure infiltration rates in the disturbed urban soils of the test watershed area, as shown in the photograph below. Using several of these units simultaneously and in relatively close proximity also enables measurements of variability to be determined. Any standard or small double-ring infiltrometer likely overestimates the actual infiltration rates for a site. The relatively small areas being tested, even with the larger traditional units, have substantial edge effects, especially if the area's soils are not saturated. Also, double-ring infiltrometer measurements do not use large amounts of water that would be needed to cause groundwater mounding, and then saturated flow conditions, with resultant highly reduced infiltration rates. The most precise measurements of infiltration, and which should be used in areas where large infiltration units are being designed, should rely on full-scale tests. These are typically large trenches or boreholes, constructed to penetrate the depths of soil that the final units will use for infiltration, and use large volumes of water over extended periods. For small stormwater biofiltration units, this approach is usually not warranted, while it would be for infiltration galleries that are critical for drainage in enclosed areas. In the Kansas City study area, the constructed rain gardens and curb-cut biofilters have undergone full-scale inundation tests to supplement the smaller scale tests. In addition, infiltration rates during the monitored rains were also measured to obtain actual rates for the areas and designs used.



**Figure 27. Set of three Turf-Tec infiltrometers for infiltration measurements in pre-development soils.**

Infiltration rates are strongly affected by the soil density. In fact, for sandy soils, Pitt et al. (1999, 2008b) show that soil density has a greater effect on infiltration rates than soil moisture; for clayey soils, soil density has about the same effect on infiltration as does soil moisture. Unfortunately, most stormwater models effectively track soil moisture, but they ignore soil density. It is important to also measure soil density with the infiltration rates. WinSLAMM has a Monte Carlo component that can describe the highly variable infiltration rates actually observed.

Infiltration rates were monitored at several locations near the streets throughout the project area by the UMKC students. Figure 28 shows the average infiltration responses from three sets of measurements at six locations, representing 18 individual infiltration tests. Initial infiltration rates were several in/hr, but the instantaneous rates were reduced to about 1 in/hr after about one hour.





Figure 28. Example infiltration plot in area soils.

Table 12 shows the observed infiltration rates, averaged for different event durations (in/hr), and plotted in Figure 29.

**Table 12. Infiltration characteristics for area soils**

	5-min event	15-min event	30-min event	60-min event	90-min event	120-min event
Average	12.15	4.12	2.73	1.58	1.15	0.90
St dev	20.42	6.28	5.04	3.79	3.17	2.78
COV	1.68	1.52	1.84	2.39	2.76	3.10
Min	0.00	0.00	0.00	0.00	0.00	0.00
Max	138.75	30.00	30.00	30.00	30.00	30.00



**Figure 29. Decreasing infiltration rates as the rain event duration increases.**


This graph indicates that the infiltration rate would be between 1 and 10 in/hr for rains that lasted up to about 2 hours, with likely decreasing infiltration rates for the long rains of interest for the critical CSO event design storm. Initial modeling efforts assumed infiltration rates of about 0.3 in/hr, but later measurements and deeper soil profiles indicated that this might be too large for the site. Therefore, for the shallow rain gardens considered during the initial analysis, infiltration rates of 0.2 in/hr were used. However, actual infiltration measurements in the biofilters after saturated conditions indicated system infiltration rates generally between 1 and 2 in/hr, while modeling indicates that the subsurface infiltration rates are likely close to 1 in/hr. Subsurface infiltration in areas of biofiltration device construction can be higher than surface rates because of typical decreased amounts of clays and fewer compacted conditions (Pitt and Talebi 2012). If care is taken to minimize compaction during construction, these higher rates could be preserved.

## Summary of Site Characteristics Used in Stormwater Quality Modeling

Land development information corresponding to the land uses in an area is needed as an initial step in investigating stormwater management options for an area. The Marlborough study (pilot) area in Kansas City is mostly a medium-density residential area, constructed before 1960, with a small amount of strip commercial area along Troost Avenue and a small portion of a school. UMKC graduate students made detailed inventories of each of the approximately 600 homes in the area.

Detailed site information is needed for stormwater management evaluations. Only about 15% of the residential roofs are directly connected in the test (pilot) area. If all were assumed to be directly connected, large errors in the roof runoff contribution calculations would occur. Similarly, if roof runoff stormwater controls were located at all roofs, those located where the roofs were already disconnected would provide much lower additional benefits in decreasing the area's runoff quantity.

In addition to the site surveys, the UMKC students conducted site-specific soils surveys for the area. Small-scale infiltrometers were used to measure infiltration rates in the disturbed urban soils of the test watershed area. The most precise measurements of infiltration, and which should be used in areas where large-scale infiltration units are being designed, should rely on full-scale tests. These are typically large trenches or boreholes, constructed to penetrate the depths of soil that the final units will use for infiltration, and use large volumes of water over extended periods. In the Kansas City study area, the constructed rain gardens and curb-cut biofilters have undergone full-scale inundation tests after construction to supplement the smaller scale tests. In addition, the rate of infiltration during the actual rains was also measured to obtain actual rates for the area and designs used. Figure 30 shows the measured infiltration rates from the small-scale tests in the test area.



**Figure 30. Duration-infiltration rates for surface soils.**

Figure 30 indicates that the infiltration rate would be between 1 and 10 in/hr for rains that lasted up to about 2 hours, with likely decreasing infiltration rates for the long rains of interest for the critical CSO event design storm. Initial modeling efforts supporting the GI designs assumed infiltration rates of about 0.3 in/hr. Deeper soil profiles indicated that this might be too large. Therefore, for the shallow rain gardens, an infiltration rate of 0.2 in/hr was used by the initial designers. However, actual infiltration measurements in the constructed biofilters after saturated conditions indicated system infiltration rates are generally between 1 and 2 in/hr, while modeling indicates that the subsurface infiltration rates in the native soils are likely close to 1 in/hr. Subsurface infiltration in areas of biofiltration device construction can be higher than surface rates because of typical decreased amounts of clays and reduced compaction. If care is taken to minimize compaction during construction, these higher rates could be preserved. The extended monitoring period will help verify the actual soil infiltration conditions.

## **4. Large-Scale Calibration of WinSLAMM: Modeled Stormwater Characteristics Compared to Observed Data**

### **Runoff Calibration for Test and Control Watersheds**

Runoff monitoring was conducted in the combined sewer system at several locations in the test and control watersheds. This sampling arrangement enabled flows to be separated for the test (pilot) and the control watersheds. Nine complete events were monitored in the area in 2009, and six events were monitored in 2010. These data were used to do an initial verification of the WinSLAMM runoff calculations. Because sewer rehabilitation was occurring during this period in the test watershed, only the control area data were used for these analyses. Additional events were monitored after the sewer was rehabilitated, and these data were used as a new baseline condition. Construction of the stormwater controls when occurred, with the final seven events from April 1 to the first part of June 2012 representing built conditions with the stormwater controls. These analyses do not include events after these June events because of lag times in data summaries. The project will continue to collect data into 2013, and further analyses will be conducted with the complete data set.

As noted previously, the detailed land development and land use information for the test and control watersheds enabled the verification of the water quantity portion of WinSLAMM using the site rainfall and runoff data. Figures 31 and 32 show the test and control watershed boundaries and the locations of the flow monitoring stations. Monitoring station S128-427 measures the flows portions of the control watershed; station S128-498 measures the flows from the test (pilot) watershed alone.








Figure 32. Flow monitoring locations at test and control area boundaries.

Appendix D contains the flow data observed during the monitoring periods. These tables contain the observed values and the calculated rain and flow parameters based on the observed data. The raw flow data represent both the dry and wet weather flows together in the monitored combined sewers. However, because we are interested in the wet weather flows, the flow values in the wet weather flow tables below have had the dry weather sanitary sewage flows subtracted. The preceding dry weather period (showing the diurnal flow fluctuations that vary by day of the week and time of day) were subtracted from the combined flows to result in the separate rainfall-runoff contributions by Tetra Tech project personnel. These data are also used in the model calibration efforts.

WinSLAMM evaluated the test (pilot) and control watershed conditions during the two (post re-lining, as the new baseline versus after construction of controls) monitoring periods to verify the rainfall-runoff calibration based on site development characteristics and the actual rains monitored.

Tables 14 and 15 are divided into four sections: the initial baseline (before sewer rehabilitation); during re-lining (no flow data available from the test watershed as the sensors were removed); after re-lining (the new baseline); and during construction of the stormwater controls. Table 14 describes the rain conditions, the second set describes the observed runoff conditions, and the third set describes the calculated rain and runoff parameters for each of these four periods.

Figure 33 is a plot of the ratios of the test to control total runoff volumes for each event, indicating the differences in each monitoring period.



**Table 14. Rainfall characteristics during different flow monitoring periods**

	Antecedent dry days	Rain dur. (hrs)	Total rain (in)	5-minute peak rain intensity (in/hr)	Avg. rain int. (in/hr)
<b>Initial baseline</b>					
number	93	93	93	93	93
average	6.6	11.1	0.77	1.37	0.17
median	3.2	7.4	0.47	0.95	0.07
st dev	16.6	11.4	0.75	0.98	0.33
COV	2.5	1.0	1.0	0.7	2.0
min	0.5	0.1	0.11	0.29	0.01
max	157.4	68.4	3.98	4.25	2.64
<b>Relining</b>					
number	24	24	24	24	24
average	5.9	9.8	0.72	1.81	0.22
median	3.8	6.8	0.41	1.01	0.08
st dev	5.3	11.5	0.70	2.11	0.43
COV	0.9	1.2	1.0	1.2	2.0
min	0.6	0.1	0.11	0.31	0.02
max	19.6	42.0	2.29	8.61	2.16
<b>New baseline</b>					
number	14	14	14	14	14
average	11.0	8.9	0.46	1.05	0.08
median	5.2	5.6	0.33	0.94	0.07
st dev	12.9	8.2	0.37	0.67	0.07
COV	1.2	0.9	0.8	0.6	0.8
min	0.9	1.2	0.12	0.47	0.01
max	43.5	30.6	1.22	2.36	0.27
<b>Construction of controls</b>					
number	55	55	55	55	55
average	7.9	9.1	0.64	1.41	0.24
median	5.6	7.8	0.51	1.08	0.10
st dev	8.7	9.1	0.46	0.90	0.62
COV	1.1	1.0	0.7	0.6	2.6
min	0.6	0.1	0.12	0.47	0.01
max	45.3	37.5	2.01	4.44	4.44

**Table 15. Flow characteristics during different flow monitoring periods**

	Pipe flow duration (hrs)	Pipe flow duration (hrs)	Total pipe flow discharge volume (ft <sup>3</sup> )	Total pipe flow discharge volume (ft <sup>3</sup> )	Total discharge (in)	Total discharge (in)	Peak pipe flow discharge rate (cfs)	Peak pipe flow discharge rate (cfs)	Avg. pipe flow discharge rate (cfs)	Avg. pipe flow discharge rate (cfs)
	100 ac test	80 ac control	100 ac test	80 ac control	100 ac test	80 ac control	100 ac test	80 ac control	100 ac test	80 ac control
<b>Initial baseline</b>										
number	81	82	81	82	81	81	81	82	81	82
average	22.4	22.9	40,969	49,599	0.11	0.16	5.96	8.47	0.75	0.94
median	19.3	19.6	26,421	24,636	0.07	0.08	3.63	2.70	0.62	0.61
st dev	10.7	10.9	43,249	89,114	0.12	0.29	6.49	15.29	0.53	0.96
COV	0.5	0.5	1.1	1.8	1.1	1.8	1.1	1.8	0.7	1.0
min	11.9	12.0	362	1,501	0.00	0.01	0.04	0.30	0.01	0.23
max	80.2	80.3	220,686	602,981	0.61	2.08	30.80	109.39	2.78	5.39
<b>Relining</b>										
number		23		23		23		23		23
average		21.5		22,004		0.08		8.52		0.39
median		18.6		10,455		0.04		2.30		0.28
st dev		11.7		27,964		0.10		14.90		0.31
COV		0.5		1.3		1.3		1.7		0.8
min		12.0		1,930		0.01		0.34		0.17
max		53.9		121,291		0.42		55.92		1.27

**Table 15. Flow characteristics during different flow monitoring periods (cont.)**

	Peak/avg. pipe flow rate ratio	Peak/avg. pipe flow rate ratio	Rv	Rv	Pipe flow/rain duration ratio	Pipe flow/rain duration ratio	Ratio of test to control total discharges (in/in)
	100 ac test	80 ac control	100 ac test	80 ac control	100 ac test	80 ac control	
<b>Initial baseline</b>							
number	81	82	81	81	81	82	79
average	10.5	8.5	0.16	0.19	7.1	7.1	1.06
median	6.2	5.2	0.14	0.14	2.6	2.6	1.01
st dev	16.6	10.3	0.09	0.17	18.3	18.3	0.62
COV	1.6	1.2	0.6	0.9	2.6	2.6	0.6
min	0.3	1.2	0.00	0.02	1.2	1.2	0.10
max	110.3	69.9	0.40	0.92	143.0	144.0	2.73
<b>Relining</b>							
number		23		23		23	
average		14.7		0.09		14.0	
median		9.4		0.09		2.8	
st dev		12.7		0.04		30.7	
COV		0.9		0.4		2.2	
min		1.3		0.04		1.3	
max		45.5		0.18		144.0	

**Table 15. Flow characteristics during different flow monitoring periods (cont.)**

	Pipe flow duration (hrs)		Total pipe flow discharge volume (ft <sup>3</sup> )		Total discharge (in)		Peak pipe flow discharge rate (cfs)		Avg. pipe flow discharge rate (cfs)	
	100 ac test	80 ac control	100 ac test	80 ac control	100 ac test	80 ac control	100 ac test	80 ac control	100 ac test	80 ac control
<b>New baseline</b>										
number	8	8	7	8	7	8	7	8	7	8
average	20.2	20.3	31,119	17,741	0.09	0.06	4.09	2.21	0.63	0.38
median	16.3	16.4	13,056	8,395	0.04	0.03	1.78	1.55	0.65	0.30
st dev	9.7	9.7	44,635	28,987	0.12	0.10	5.96	2.44	0.35	0.19
COV	0.5	0.5	1.4	1.6	1.4	1.6	1.5	1.1	0.6	0.5
min	13.7	13.8	2,246	2,143	0.01	0.01	0.12	0.39	0.18	0.16
max	42.5	42.5	129,497	88,973	0.36	0.31	16.84	7.94	1.18	0.72
<b>Construction of controls</b>										
number	24	20	24	20	24	19	24	20	24	20
average	22.8	20.5	26,324	27,590	0.07	0.07	3.93	6.43	0.47	0.57
median	20.6	20.0	17,291	10,579	0.05	0.03	1.08	3.03	0.45	0.42
st dev	8.7	8.5	27,787	36,907	0.08	0.08	5.15	7.48	0.26	0.41
COV	0.4	0.4	1.1	1.3	1.1	1.1	1.3	1.2	0.6	0.7
min	11.8	12.0	1,249	1,628	0.00	0.01	0.08	0.28	0.11	0.15
max	41.3	41.5	120,835	148,512	0.33	0.31	18.36	23.61	0.98	1.88

**Table 15. Flow characteristics during different flow monitoring periods (cont.)**

	Peak/avg. pipe flow rate ratio	Peak/avg. pipe flow rate ratio	Rv	Rv	Pipe flow/rain duration ratio	Pipe flow/rain duration ratio	Ratio of test to control total discharges (in/in)
	100 ac test	80 ac control	100 ac test	80 ac control	100 ac test	80 ac control	
<b>New baseline</b>							
number	8	8	7	8	8	8	7
average	4.3	5.2	0.17	0.11	3.9	3.9	1.53
median	2.4	3.1	0.15	0.10	3.7	3.7	1.16
st dev	4.8	3.5	0.11	0.06	2.0	2.0	0.84
COV	1.1	0.7	0.6	0.6	0.5	0.5	0.6
min	0.7	2.3	0.05	0.05	1.4	1.4	0.81
max	14.3	11.1	0.29	0.25	7.5	7.5	3.05
<b>Construction of controls</b>							
number	24	20	24	19	24	20	15
average	8.5	9.2	0.11	0.11	10.2	19.9	0.72
median	3.2	7.9	0.09	0.11	2.3	2.5	0.63
st dev	14.7	7.0	0.07	0.06	28.6	43.0	0.45
COV	1.7	0.8	0.7	0.6	2.8	2.2	0.6
min	0.6	1.9	0.03	0.02	1.4	1.4	0.23
max	71.7	27.4	0.30	0.24	142.0	144.0	1.50




Figure 33. Test to control area total runoff volume ratios during complete study period (initial baseline, after re-lining, during construction, and after construction of stormwater controls).

Figure 34 is a scatter plot that focuses on the time during construction and after most of the stormwater control construction was completed. The last period, since April 1, 2012, was therefore separated from the construction period because it represents a period when most of the stormwater controls were functioning. Only eight events are in this last critical category. However, the site monitoring will be continuing into 2013 rain year for additional observations. All these last events have a reasonably constant flow volume ratio, except for one. The additional monitored events will be very important to establish greater confidence in the performance of the stormwater controls in the test (pilot) watershed.





Figure 34. Test to control area total runoff volume ratios during and after construction of stormwater controls.

Figure 35 is a box and whisker plot that shows the test to control area runoff volume ratios for the events in each period, including the *after construction* period (the period during the re-lining is not shown because the test watershed sensors were removed during the rehabilitation efforts).





**Figure 35.** Test to control area total runoff volume ratios for different study periods.

The Kruskal-Wallis One Way Analysis of Variance on Ranks test was conducted to indicate any significant differences between these categories. This test indicated that at least one category was significantly different from the others ( $p = 0.015$ ). The *after construction* period (even with the one unusual event) was found to be significantly different from the other three periods. Table 16 summarizes the average test (pilot) to control area total flow ratios for each of these four periods and the percentage differences from the appropriate baselines, along with the Wilcoxon Rank-Sum test results indicating if the differences were statistically significant.

**Table 16. Statistical comparisons of flows during different flow monitoring periods**

Monitoring Period	Average test (pilot) to control area runoff volume ratio	% change compared to initial baseline (and p from Wilcoxon Rank-Sum test)	% change compared to final baseline (after re-lining) (and p from Wilcoxon Rank-Sum test)
Initial baseline	1.06	n/a	n/a
After re-lining (final baseline)	1.53	44% increase ( $p = 0.20$ )	n/a
During construction	1.02	4% decrease ( $p = 0.94$ )	33% decrease ( $p = 0.26$ )
After construction (after April 1, 2012)	0.46	55% decrease ( $p = 0.006$ )*	70% decrease ( $p = 0.004$ )*

Significance difference ( $p < 0.05$ )

As shown in Table 16, the after construction period had significantly different flow volume ratios compared to both the initial baseline (before re-lining) and the final baseline (after re-lining). When compared to the new baseline, a total period flow reduction of about 70% was noted. Additional data will increase the power of this comparison and the reliability of the differences. The few data and variable conditions noted for the *new baseline* condition results in a wide range of likely values, but these analyses definitely show a significant reduction with the construction of the stormwater controls. Also, the results


after re-lining do not indicate a significant increase in the runoff compared to pre-lined conditions ( $p = 0.20$ ), due to the variability in the results and the few data observations available.

Table 17 lists the seven events that were observed in the test (pilot) watershed, after the re-lining was completed and before the construction of the stormwater controls. Also shown are the modeled runoff volume values and the ratio comparing the observed to the modeled flows.

**Table 17. Rain data with observed and modeled flow characteristics after re-lining of the combined sewer and before the construction of the stormwater controls (final baseline conditions).**


Event #	Rain start date	Rain start time	Rain end date	Rain end time	Total rain (in)	Total pipe flow discharge volume (ft <sup>3</sup> )	modeled runoff (ft <sup>3</sup> )	ratio of flows (obs/modeled)
119	1/22/2011	12:20	1/23/2011	3:40	0.12	2,246	6,021	0.37
120	2/24/2011	9:00	2/25/2011	3:00	0.35	33,011	21,124	1.56
121	2/26/2011	13:50	2/28/2011	8:20	1.22	129,497	103,676	1.25
122	3/4/2011	11:10	3/5/2011	1:40	0.24	23,412	12,694	1.84
123	3/8/2011	8:10	3/9/2011	1:10	0.39	13,056	24,597	0.53
124	3/13/2011	23:00	3/15/2011	0:25	0.20	10,708	10,035	1.07
125	3/19/2011	14:30	3/20/2011	4:15	0.32	5,900	18,662	0.32
Sum:					2.84	217,830	196,809	Ratio of sums: 1.11

For the seven events monitored, the sum of the observed flows was about 11% greater than the sum of the modeled flows. Figure 36 is a scatterplot showing the observed versus the modeled total flows for each of these seven events. As shown, these are all close to the line of equivalent values.



**Figure 36. Observed versus modeled flows during final baseline conditions (after re-lining)**

Figure 37 is a box plot that compares the single event observed flows to the modeled flows. The boxes substantially overlap, but the observed flows are much more variable than the modeled flows.



**Figure 37. Variabilities of runoff volumes observed and modeled.**

The Mann-Whitney Rank Sum Test (using SigmaPlot ver 11) was used to compare the observed with the modeled runoff volumes. The seven pairs of data were not sufficient to detect a significant difference in the two sets of runoff volumes:

Group	N	Missing	Median	25%	75%
obs flows	7	0	13,056	5,900	33,011
modeled flows	7	0	18,662	10,035	24,597

Mann-Whitney U Statistic= 23.000

T = 51.000; n (small) = 7; n (big) = 7; P (est.) = 0.898; P (exact) = 0.902

The difference in the median values between the two groups is not great enough to exclude the possibility that the difference is because of random sampling variability; there is not a statistically significant difference ( $p = 0.902$ ).

## Variability and Uncertainty with WinSLAMM Modeling

WinSLAMM contains various Monte Carlo components that enable uncertainty to be evaluated during the model runs. These are available for the infiltration rates for the various infiltration and biofiltration devices and for the pollutant concentrations. During field investigations, these model parameters have been recognized as having the greatest variabilities that are not explained by the model. The Monte Carlo elements are described by probability distributions, with average and coefficient of variation values (COV) provided, and assumes log-normal distributions of the actual values. If these uncertainty options are selected, the model randomly selects a value of the parameter from this distribution for each rain event. The long-term simulations therefore result in calculated concentrations and loadings of the constituents and the runoff volumes that vary in a similar manner as observed during monitoring. For the calculations in this report, when different options are being directly compared, the Monte Carlo option was not used because that could affect the average ordering of the different options. However, several different scenarios were repeatedly analyzed and the different concentrations and loads were examined to estimate the likely variability in the relative model outcomes. The absolute errors are described above

with the calibration and verification discussions. As noted, the flow calculations might have a low to moderate bias by underreporting the expected runoff quantities; this bias will be further reduced by additional calibration during later project phases when additional data become available.

Table 18 summarizes these Monte Carlo results by showing the groups of constituents associated with different ranges of variability and uncertainty. As an example, when calibrated, WinSLAMM is able to predict the runoff volumes and particulate solids loads more accurately than the other constituents. With COV values (the relative standard deviations compared to the average values) of about 5% of the average values, the 95% confidence range of these constituents would be within about 10% of the average (for normal distributions, about 95% of the data are obtained within  $\pm 2$  times the standard deviation values). However, for zinc concentrations, the 95% confidence interval is about  $\pm 20$  to 30% of the average values. The bacteria data has an even wider range for the confidence interval, as expected ( $\pm 60$  to 70% for *Escherichia coli* and even wider for fecal coliforms). The relative runoff volume (the primary stormwater characteristic of interest in the Kansas City project) and TSS mass load reduction predictions for the alternative stormwater control programs are expected to be more precise, and it might be possible to distinguish control programs that are much closer.

**Table 18. Expected modeling variability**

COV (standard deviation as a percentage of average concentration)	
< 5%	runoff volume Rv total and filterable total Kjeldahl nitrogen (TKN) TSS
5 to 10%	total and filterable copper total and filterable lead nitrates
10 to 15%	total and filterable zinc total and filterable chemical oxygen demand (COD) TDS
30 to 35%	<i>E. coli</i> bacteria total and filterable phosphorus
65%	fecal coliform bacteria

## Summary of Systemwide Observations and Model Calibration

Runoff monitoring was conducted in the combined sewer system at several locations in the test and control watersheds. Events were monitored after the sewer was rehabilitated, and these data were used as a new baseline condition. WinSLAMM evaluated the test (pilot) and control watershed conditions during the two monitoring periods (post re-lining, as the new baseline versus after construction of controls) to verify the rainfall-runoff calibration based on site development characteristics and the actual rains monitored.

Figure 38 focuses on the time during construction and after most of the stormwater control construction was completed. The last period, since April 1, 2012, was therefore separated from the construction period because it represents a period when most of the stormwater controls were functioning. Only eight events are in this last critical category. However, the site monitoring will be continuing into the 2013 rain year for additional observations. All these last events have a reasonably constant flow volume ratio, except for one of the events that apparently produced more runoff from the test area (or less from the control area) than expected. The additional monitored events will be very important to establish greater confidence in the overall performance of the stormwater controls in the test (pilot) watershed.




Figure 38. Decreasing test (pilot) area event flows compared to control area flows during and after construction.


Table 19 summarizes the average test (pilot) to control area total flow ratios for each of the four monitoring periods and the percentage differences from the appropriate baselines, along with the Wilcoxon Rank-Sum test results indicating if the differences were statistically significant. The after-construction flow ratios were significantly different from the before construction baseline flow ratios. However, the after re-lining flow ratios were not shown to be significantly different from the before re-lining flow ratios because of the few data observations after the re-lining and before the start of the GI stormwater control construction period.

**Table 19. Test (pilot) and control watershed flow comparisons during four monitoring periods**

Monitoring period	Average test (pilot) to control area runoff volume ratio	% change compared to initial baseline (and p from Wilcoxon Rank-Sum test)	% change compared to final baseline (after re-lining) (and p from Wilcoxon Rank-Sum test)
Initial baseline	1.06	n/a	n/a
After re-lining (final baseline)	1.53	44% increase (p = 0.20)	n/a
During construction	1.02	4% decrease (p = 0.94)	33% decrease (p = 0.26)
After construction (after April 1, 2012)	0.46	55% decrease (p = 0.006)*	70% decrease (p = 0.004)*

\*Significance difference (p < 0.05)

Figure 39 is a scatterplot showing the observed versus the modeled test (pilot) watershed area total flows for each of the events during the after re-lining baseline period. As shown, these are all close to the line of equivalent values.



**Figure 39. Observed versus modeled flows during final baseline conditions (after re-lining).**

## 5. Small-Scale Drainage Areas, Performance Monitoring during Rain Events, and Associated Model Calibration Factors for Stormwater Controls

The objective of this chapter is to summarize the drainage area characteristics for the GI control devices being monitored. For each of the devices, areas for different urban surfaces (including rooftops, streets, landscaped areas, sidewalks, driveways, and parking lots) have been measured using aerial photos and site visits, plus GIS shapefile layers. This information, along with the attributes of the designs of each control, was used as input for the WinSLAMM model. Table 20 lists the information sources that were used to obtain the information described in this chapter and in Appendix A.

**Table 20. Sources of small-scale drainage area information**

Document/Material	Source
100% design plans and street side topographic info.	<a href="https://sites.tetrattech.com/projects/100-KCADC/default.aspx">https://sites.tetrattech.com/projects/100-KCADC/default.aspx</a>
Subwatershed shapefile	Mr. John Riverson, Tetra Tech (from Sustain KC maps)
Sewer network shapefile	Mr. John Riverson, Tetra Tech (from Sustain KC maps)
Stormwater controls shapefile	Mr. John Riverson (TT) and <a href="https://sites.tetrattech.com/projects/100-KCADC/default.aspx">https://sites.tetrattech.com/projects/100-KCADC/default.aspx</a>
Bing aerial maps	Basemap available in ArcMap 10
Listing of locations and sampling equipment	Table supplied by Dr. Deb O'Bannon, UMKC
USGS topo maps (10 ft contours)	Basemap available in ArcMap 10
Topographic maps (1 ft) jpgs	Project map supplied by Dr. Deb O'Bannon, UMKC
"Monitoring water balance of a rain garden by installation of flow monitoring devices on a residential property." Thesis by Jason Nall, UMKC.	<a href="https://sites.tetrattech.com/projects/100-KCADC/default.aspx">https://sites.tetrattech.com/projects/100-KCADC/default.aspx</a>
Site photos	Robert Pitt – Site visit on October 25 and 26, 2012


Table 21 is a list of the ten monitoring station locations in the test (pilot) watershed prepared by UMKC researchers. Figure 40 shows these locations on the map of the test area. They were mostly along East 76<sup>th</sup> Street and East 76<sup>th</sup> Terrace. Detailed site information is contained in Appendix A, including subarea drainages for each area draining to each stormwater control being monitored (including the land surface breakdowns). Example designs for each type of stormwater control being monitored are included in Appendix B. Appendix C contains detailed information concerning the observed infiltration rates in each of the stormwater controls. The information presented in these three appendices was then used to calibrate WinSLAMM for the site-specific conditions. The following summaries in this section focus on the infiltration rates observed during the monitored events.



**Table 21. Locations of Monitoring Stations**

No.	Stormwater control type	Address	Design station
1	Curb Extension	1324 E 76 <sup>th</sup> St.	19+79.61
2	Curb Extension	1325 E 76 <sup>th</sup> St.	19+79.61
3	Curb Extension	1419 E 76 <sup>th</sup> Terr.	26+51.65
4	Rain Garden Extension	1612 E 76 <sup>th</sup> St.	31+31.12
5	Rain Garden Extension	1336 E 76 <sup>th</sup> St.	21+29.95
6	Site abandoned due to theft of monitoring equipment		
7	Rain Garden w/ Smart Drain	1140 E 76 <sup>th</sup> Terr.	15+37.75
8	Rain Garden w/ Smart Drain	1222 E 76 <sup>th</sup> St.	16+28.15
9	Cascade	1112 E 76 <sup>th</sup> Terr.	12+18.80
10	Private rain garden	1312 E. 79 <sup>th</sup> St.	Mrs. Thomas
11	Private rain garden	1505 E. 76 <sup>th</sup> St.	Mrs. Moss

Source: UMKC



**Figure 40. Location of stormwater controls monitored in test (pilot) watershed.**

**Infiltration Rates in Monitored Biofilters**

Tables 22 through 29 summarize the infiltration rates calculated using the monitored data obtained during the rains. As shown in Appendix D, plots of the water depths in the biofilters were used to identify recession limbs of the infiltration periods as recorded from the water level recorders in the biofilters. In some cases, runoff was still entering the devices during the infiltration period. The basic infiltration rates were all very consistent for a recession limb, with no decreasing rate with time. This indicates that the systems were already saturated, and the rates represent the lowest values occurring. If measured during inflowing conditions, the rates were listed as greater than the calculated rates.

**Table 22. 1324 E. 76th St. (site #1) infiltration rates and ponding times**

	Maximum water depth in biofilter (in)	Time duration before Ponding (days)	Final (constant) infiltration rate (in/hr)
Number of infiltration recession curves	9	9	7
Average	1.72	0.97	1.85
Min	0.24	0.25	0.08
Max	3.72	3.28	5.04
St dev	1.40	0.89	2.17
COV	0.81	0.92	1.17

**Table 23. 1325 E. 76th St. (site #2) infiltration rates and ponding times**

	Maximum water depth in biofilter (in)	Time duration before ponding (days)	Final (constant) infiltration rate (in/hr)
Number of infiltration recession curves	9	5	5
average	1.28	0.28	1.38
min	0	0.01	0.24
max	5.64	0.84	4.80
st dev	1.77	0.35	1.93
COV	1.39	1.25	1.40

**Table 24. 1419 E. 76th Terrace (site #3) infiltration rates and ponding times**

	Maximum water depth in biofilter (in)	Time duration before ponding (days)	Final (constant) infiltration rate (in/hr)
Number of infiltration recession curves	7	5	5
average	3.84	0.27	0.36
min	0	0.10	0.19
max	7.04	0.57	0.62
st dev	3.02	0.18	0.19
COV	0.79	0.67	0.53

**Table 25. 1612 E. 76th St. (site #4) infiltration rates and ponding times**

	Maximum water depth in biofilter (in)	Time duration before ponding (days)	Final (constant) infiltration rate (in/hr)
Number of infiltration recession curves	10	7	6
average	4.76	0.30	2.56
min	0	0.04	1.54
max	9.84	0.83	3.96
st dev	4.13	0.28	0.95
COV	0.86	0.94	0.37

**Table 26. 1336 E. 76th St. (site #5) infiltration rates and ponding times**

	Maximum water depth in biofilter (in)	Time duration before ponding (days)	Final (constant) infiltration rate (in/hr)
Number of infiltration recession curves	21	19	12
average	3.65	0.42	1.61
min	0	0.02	0.62
max	13.2	1.26	4.71
st dev	3.43	0.36	1.15
COV	0.94	0.86	0.72

**Table 27. 1140 E. 76th Terrace (site #7) infiltration rates and ponding times**

	Maximum water depth in biofilter (in)	Time duration before ponding (days)	Final (constant) infiltration rate (in/hr)
Number of infiltration recession curves	10	5	4
average	2.28	0.51	1.57
min	0	0.01	0.71
max	5.4	1.27	2.74
st dev	2.19	0.54	0.89
COV	0.96	1.06	0.56


**Table 28. 1222 E. 76th St. (site #8) infiltration rates and ponding times**

	Maximum water depth in biofilter (in)	Time duration before ponding (days)	Final (constant) infiltration rate (in/hr)
Number of infiltration recession curves	8	3	3
average	0.81	0.23	2.63
min	0	0.06	1.17
max	2.88	0.49	3.36
st dev	1.24	0.23	1.26
COV	1.53	0.96	0.48

**Table 29. 1112 E. 76th Terrace (site #9) infiltration rates and ponding times**

	Maximum water depth in biofilter (in)	Time duration before ponding (days)	Final (constant) infiltration rate (in/hr)
Number of infiltration recession curves	8	8	2
average	5.42	0.72	4.42
min	2.75	0.07	3.85
max	8.28	1.63	4.99
st dev	1.88	0.66	0.81
COV	0.35	0.91	0.18

Figure 41 is a SigmaPlot (ver 11) box and whisker plot that compares the infiltration rates observed at the eight different biofilter installations. There were 3 to 19 observations at each site, for about 80 total separate infiltration observations. Statistical analyses indicated that at least one of the sites was significantly different ( $p = 0.011$ ) from the others, as indicated in the following Kruskal-Wallis analysis.



**Figure 41. Box and whisker plots of observed infiltration rates in monitored biofilters.**

Kruskal-Wallis One Way Analysis of Variance on Ranks

Group	N	Missing	Median	25%	75%
1324 #1	11	4	0.960	0.280	4.850
1325 #2	7	2	0.480	0.355	2.850
1419 #3	6	1	0.240	0.215	0.555
1612 #4	10	4	2.515	1.555	3.442
1336 #5	19	7	1.215	0.890	2.062
1140 #7	6	2	1.420	0.808	2.490
1222 #8	3	0	3.360	1.170	3.360
1112 #9	8	6	4.420	3.850	4.990


H = 18.110 with 7 degrees of freedom. (P = 0.011)

The differences in the median values among the treatment groups are greater than would be expected by chance; there is a statistically significant difference (p = 0.011).

An all pairwise multiple comparison procedure (Dunn’s Method) was used to identify the group or groups that differ from the others. On the basis of these further tests and data observations, the data were separated into three groups:

1. **Very low:** site 3 (1419); average 0.36 in/hr; range 0.19 to 0.62.
2. **Moderate:** sites 1 (1324), 2 (1325), 5 (1336), 7 (1140), and 8 (1222); average 1.8 in/hr; range 0.08 to 5.0.
3. **Very high:** sites 4(1612) and 9 (1112); average 3.2 in/hr; range 1.6 to 5.0.

These three groups are shown in Figure 42.



**Figure 42. Infiltration rate site categories.**

The following Kruskal-Wallis One Way Analysis of Variance on Ranks test confirmed that at least one group was significantly different ( $p = 0.01$ ) from the others.

Group	N	Missing	Median	25%	75%
low rate	5	0	0.24	0.22	0.56
mod rates	30	0	1.19	0.62	2.70
high rates	7	0	3.27	2.49	3.96

H = 13.439 with 2 degrees of freedom. ( $p = 0.001$ )

The differences in the median values among the treatment groups are greater than would be expected by chance; there is a statistically significant difference ( $p = 0.001$ ).

During the all pairwise multiple test, the low rate group was found to be significantly different from both the moderate and the high rate groups, but not enough data were available to indicate that there was a significant difference between the moderate and high rate groups:

All pairwise multiple comparison procedures (Dunn's Method):

Comparison	Diff of Ranks	Q	P < 0.05
high rates vs low rate	<b>26.314</b>	<b>3.663</b>	<b>Yes</b>
high rates vs mod rates	11.314	2.197	No
mod rates vs low rate	15.000	2.531	Yes


The following table summarizes some of the basic statistical features of these three infiltration rate groups.

Group	Size	Mean	Std Dev	COV	Max	Min
low rate	5	0.36	0.19	0.53	0.62	0.19
mod rates	30	1.80	1.62	0.89	5.04	0.08
high rates	7	3.24	1.14	0.35	4.99	1.56

### **Runoff Duration before Ponding in Biofilters**

A similar analysis was conducted to investigate the time since the beginning of flow entering the biofilters to the beginning of ponding. The total amount of rain or runoff before ponding might be a more useful measure, but those data were not available. The time before ponding was obtained from the inflow hydrograph and ponding depth measurements presented in Appendix D. Figure 43 is a box and whisker plot showing the ranges and percentiles of these durations before ponding for each of the eight monitored biofilters.





**Figure 43. Time to ponding in monitored biofilters.**

The Kruskal-Wallis One Way Analysis of Variance on Ranks test did not indicate that any of the sites were significantly different from any of the others ( $p = 0.18$ ). Site #1 at 1324 E. 76<sup>th</sup> St. seems higher than the others, but the high variability in the values requires more observations to detect any significant differences.

Group	N	Missing	Median	25%	75%
1: 1324 #1	11	2	0.750	0.536	0.917
2: 1325 #2	7	2	0.0833	0.0365	0.625
3: 1419 #3	6	1	0.205	0.141	0.443
4: 1612 #4	10	3	0.240	0.0729	0.458
5: 1336 #5	19	0	0.333	0.0833	0.829
6: 1140 #7	6	1	0.274	0.0660	1.066
7: 1222 #8	3	0	0.153	0.0625	0.490
#8: 1112 #9	8	0	0.615	0.115	1.375

H = 10.110 with 7 degrees of freedom. (P = 0.182)


The differences in the median values among the treatment groups are not great enough to exclude the possibility that the difference is because of random sampling variability; there is not a statistically significant difference ( $p = 0.182$ ).

The overall weighted mean is 0.5 hour, with an overall range of 0.04 to 3.3 hours.

### **Maximum Water Depth Observed in Biofilters**

The maximum depth observed in the biofilters was also obtained for each monitored event in each of the biofilters and examined using similar procedures as described above. Figure 44 is a box and whisker plot showing the median and ranges for each of the eight sites.





**Figure 44. Maximum water depth observed in monitored biofilters.**

The Kruskal-Wallis One Way Analysis of Variance on Ranks test indicates a significant probability ( $p = 0.006$ ) that at least one site is different from the others:

Group	N	Missing	Median	25%	75%
1324 #1	11	2	0.84	0.54	3.12
1325 #2	9	0	0.96	0.06	1.68
1419 #3	7	0	5.40	0.00	6.50
1612 #4	10	0	4.80	0.00	9.48
1336 #5	21	0	3.60	1.10	4.26
1140 #7	10	0	2.52	0.00	4.05
1222 #8	8	0	0.06	0.00	2.19
1112 #9	8	0	5.80	3.39	6.64

H = 20.001 with 7 degrees of freedom. (P = 0.006)


The differences in the median values among the treatment groups are greater than would be expected by chance; there is a statistically significant difference ( $p = 0.006$ ). An all pairwise multiple comparison procedure (Dunn's Method) was used to isolate the group or groups that differ from the others. Three categories of sites were determined.

Shallow: sites 2 (1325) and 8 (1222)

Moderate: sites 1 (1324), 3 (1419), 4 (1612), 5 (1336), and 7 (1140)

Deep: site 9 (1112)

Figure 45 is a box and whisker plot showing these three combined sets of data.



**Figure 45. Categories of monitored sites having different ponding depths.**

The Kruskal-Wallis One Way Analysis of Variance on Rank test indicated a significant difference ( $p < 0.001$ ) that at least one of the site groups are different from the others.

Group	N	Missing	Median	25%	75%
Shallow	17	0	0.24	0.00	1.68
Moderate	57	0	2.64	0.48	4.68
Deep	8	0	5.79	3.39	6.64

H = 15.982 with 2 degrees of freedom ( $p = < 0.001$ ).

The differences in the median values among the treatment groups are greater than would be expected by chance; there is a statistically significant difference ( $p = < 0.001$ ).

An all pairwise multiple comparison procedure (Dunn's Method) indicated that the deep and shallow groupings are significantly different and that the moderate and shallow groupings are significantly different. However, the deep and moderate groupings were not significantly different at the  $p = 0.05$  level.

Comparison	Diff of Ranks	Q	p < 0.05
Deep vs. Shallow	39.375	3.856	Yes
Deep vs. Moderate	21.164	2.354	No
Moderate vs. Shallow	18.211	2.767	Yes

The following describe some values for these three categories:

Group	Size	Mean	Std Dev	COV	Max	Min
Shallow	17	1.06	1.5	1.4	5.64	0.00
Moderate	57	3.33	3.2	0.9	13.2	0.00
Deep	8	5.42	1.9	0.4	8.28	2.75

## Laboratory Column Tests of Infiltration Rates as a Function of Compaction

The effects of different compaction levels on the infiltration rates through the Kansas City soil media were examined during laboratory column testing in the UA Environmental Engineering Laboratory, as part of ongoing dissertation research by Redahegn Sileshi focusing on biofiltration media and underdrain systems (Sileshi et al. 2010, 2012a, 2012b). Figure 46 shows photographs of the media, illustrating its heterogeneous nature.



Figure 46. Media samples obtained from Kansas City biofilters.

Four-in. (100 mm) diameter PVC pipe (Charlotte Pipe TrueFit 100 mm PVC Schedule 40 Foam-Core Pipe) purchased from a local building supply store in Tuscaloosa, Alabama, was used to construct the columns for these tests. The columns were filled with about 2 in (5 cm) of cleaned pea gravel purchased from a local supplier. To separate the gravel layer from the media layer, a permeable fiberglass screen was placed over the gravel layer and then filled with the soil media. The media layer was about 1.5 ft (0.5 m) thick. The bottom of the columns had a fiberglass window screen secured to contain the media as shown in Figure 47.



Figure 47. Lab column construction for flow test using Kansas City soil media: bottom of the columns secured with a fiberglass window screen, mixed soil media, and soil compaction.

Three levels of compaction levels were tested. The tests were compacted by hand, standard proctor, and modified proctor methods. Both standard and modified proctor compactions follow ASTM standard (D 1140-54). The standard proctor compaction hammer is 24.4 kN and has a drop height of 300 mm. The modified proctor hammer is 44.5 kN and has a drop height of 460 mm. For the standard proctor setup, the hammer is dropped on the test soil 25 times on each of three soil layers, while for the modified proctor test, the heavier hammer was also dropped 25 times, but on each of five soil layers and using the heavier hammer. The modified proctor test therefore results in a much more compacted soil and usually reflects the most compacted soil observed in the field. The hand compaction is done by gently hand pressing the media material to place it into the test cylinder with as little compaction as possible, with no voids or channels. The hand compacted soil columns therefore have the least amount of compaction. The densities were directly determined by measuring the weights and volume of the media material added to each column. The density of the media column with hand compaction was 1.00 g/cm<sup>3</sup>, the density of the standard proctor media column was 1.13 g/cm<sup>3</sup>, and the density for the modified proctor media column was 1.12 g/cm<sup>3</sup>. The soil media has a median particle size (D<sub>50</sub>) of about 1.9 mm and a uniformity coefficient (C<sub>u</sub>) of 39, as shown in the soil's particle size distribution plot (Figure 48).




Figure 48. Particle size distribution of Kansas City soil media used during lab compaction test.

The media samples are also being analyzed by the Auburn University's Soil Testing Laboratory, where basic soil texture (% sand, % silt, and % clay), organic matter, cation exchange capacity (CEC), sodium adsorption ratio (SAR), major constituents, and general nutrients are being analyzed.



### **Laboratory Measurement of Porosity of Kansas City Soil Media**

Porosity ( $\phi$ ) is the portion of the soil's volume that is not occupied by solid material. The pore volume of the soil media was determined from the volume of water needed to saturate the media in the columns. To keep water from coming out of the soil columns during the porosity measurements, we formed a seal using plastic sheeting sealed with duct tape on the inside, wet mat secured using screw-type radiator hose clamps on the outside and bottom of the columns. The bottoms of the columns were placed in buckets so that when the seals were lifted up, the water flowed into the buckets (Figure 49).

The volume of the void in the 2-in pea gravel placed in the bottom of each column was subtracted from the total void volume of a water-saturated soil and gravel layer in the columns to get the void in soil media alone. The porosity of the soil media alone for the hand compacted media column was 0.36, 0.15 for the standard proctor compaction tests, and 0.25 for the modified proctor tests.



**Figure 49. Laboratory column setup for porosity and infiltration measurements**

### **Laboratory Infiltration Results**

The infiltration rates through the soil media were measured in each column using municipal tap water. The surface ponding depths in the columns ranged from 11 to 14 in (28 - 36 cm). Infiltration rates in the soil media were determined by measuring the rates of the water level drops with time until apparent steady state rates were observed.

Observed infiltration data for different test trials were fitted to the Horton infiltration equation by using multiple nonlinear regressions to estimate  $f_c$  (the saturated soil infiltration rate),  $f_o$  (the initial rate), and  $k$  (the rate coefficient). The saturated rates were of greatest interest as they would apply during most of the event durations. The infiltration rates of the saturated media ranged from 0.4 to 0.8 in/hr for the hand compaction tests, 0.4 to 0.9 in/hr for the standard proctor compaction tests, 0.03 to 0.33 in/hr for the modified proctor compaction tests. The COV of the laboratory infiltration rates through the soil media were 0.36, 0.41, and 1.1 for hand compaction, standard proctor, and modified proctor compaction tests, respectively. Figures 50, 51a, and 51b are plots of the data and the derived Horton equations with fitted curves for the different test trials, comparing different compaction conditions. Previous researches indicated that soil compaction has a significant on the infiltration rates (Gregory et al. 2006; Pitt et al. 2008b; Thompson et al. 2008; Sileshi et al. 2012a, 2012b); however the effect of soil compaction on the

infiltration rates for the Kansas City media was not observed, except for the modified proctor compaction tests.

The following are the infiltration rates measured in the field during the actual rains. The very low rate category corresponds to the laboratory observations during the hand and standard proctor column tests. The very high rate measurements are likely associated with media having a more uniform or larger particle size characteristic (or both). As noted on the particle size distribution plot, more than 90% of the media is larger than 100  $\mu\text{m}$ , with appreciable fractions clearly in the coarse sand category. Media with large amounts of sand do not compact as much as media having more fines, because of the structural support of the sand grains. However, these materials usually have greater infiltration rates than measured during these column tests. The organic content of the Kansas City media might be relatively large which could reduce the effective typical pore sizes, resulting in lower infiltration rates. The uniformity coefficient was also quite large for this media which also adversely affects the infiltration rates.

- Very low: average 0.36 in/hr; range 0.19 to 0.62.
- Moderate: average 1.8 in/hr; range 0.08 to 5.0.
- Very high: average 3.2 in/hr; range 1.6 to 5.0.




Figure 50. Laboratory infiltration measurements fitted with Horton equations: hand compaction tests for Kansas City biofilter media.




Figure 51a. Laboratory infiltration measurements fitted with Horton equations: standard proctor compaction test for Kansas City biofilter media.




Figure 51b. Laboratory infiltration measurements fitted with Horton equations: modified proctor compaction test for Kansas City biofilter media.



## Influent Water Quality to Curb-Side Biofilters

The UMKC team sampled water coming into the biofilters and discharged by underdrains or overflows. When sufficient sample volumes were available, the UA team also analyzed the samples for TSS, SSC, and PSD. UA analyzed 20 influent and 2 effluent samples. For the other events, there were no underdrain or overflow samples, with almost the entire study period runoff being infiltrated by the biofilters. The methods used were ASTM, EPA, USGS, or *Standard Methods* for TSS and SCC that have been described and compared by Clark and Siu 2008; Clark and Pitt 2008; and Clark et al. 2008.

Figure 52 is a PSD plot for the 20 influent samples. The median particle size (by mass) is about 30  $\mu\text{m}$ , and about 25% were larger than 100  $\mu\text{m}$ . Table 30 lists the variability for each particle size range. The COV (the standard deviation divided by the mean, COV) is much smaller for the larger particles than for the small particles.





Figure 52. Particle size distributions of water entering the monitored biofilters.

Table 30. Accumulative mass percentage (%) (summary for 20 influent samples)

Particle size ( $\mu\text{m}$ )	Average	Min	Max	St dev	COV	Median
< 0.45	0.00	0.00	0.00	0.00	n/a	0.00
< 3	0.41	0.05	1.64	0.39	0.94	0.27
< 12	14.53	2.70	32.36	9.28	0.64	12.02
< 30	50.96	18.03	77.46	15.19	0.30	51.36
< 60	67.68	25.31	86.95	16.03	0.24	71.16
< 120	75.58	36.40	91.71	14.37	0.19	77.66
< 250	78.59	44.45	94.44	13.39	0.17	79.95
< 1,180	100.00	100.00	100.00	0.00	0.00	100.00

The TSS samples were analyzed using both stir plates/pipetting and shake and pour methods; the SCC was determined by subsampling using a cone splitter. The stir plate and pipette method has been shown to have the highest yield and most consistent results compared to the SCC value, as shown by prior studies (Clark and Siu 2008; Clark and Pitt 2008; Clark et al. 2008). Figure 53 is a box and whisker plot comparing the parallel test results for these particulate solids analyses. The shake and pour method shows reduced values compared to the pipette and SSC methods. The pipette and SSC methods appear similar.



**Figure 53. Comparison of particulate solids by different analytical methods.**

The Kruskal-Wallis One Way Analysis of Variance on Rank test compared these three methods, but it did not detect any significant differences ( $p = 0.25$ ), although the medians of the shake and pour measurements were about 25 to 30% less than the other two methods.

Figures 54 and 55 are scatterplots comparing the stir plate and pipetting TSS results with the SSC results, along with the two TSS methods as analyzed in the UA Environmental Engineering Lab. The stir plate and pipetting TSS values are consistently very close to the SSC values, with an overall bias of less than 1%. The relationship between the shake and pour TSS and stir plate and pipette TSS values are consistent, but with about a 25% bias, with the shake and pour results being less.




Figure 54. TSS by stirring pipetting versus SSC with cone splitter.





Figure 55. TSS by shaking and pouring versus TSS by stirring and pipetting.

Figure 56 contains box and whisker plots comparing the stir plate and pipette TSS results for the influent samples from the four monitored locations. It is apparent that there are large differences in the observed values between the sites, even for 1324 and 1325 East 76<sup>th</sup> Street that are across the street from each other. However, Mann-Whitney Rank Sum test indicated that these two sites were not statistically significantly different ( $p = 0.26$ ), with not enough samples to overcome the wide variation in the observed values.




**Figure 56. TSS variations at monitored sites.**

The Kruskal-Wallis One Way Analysis of Variance on Rank test indicated that there is a statistically significant difference for at least one site compared to the other sites ( $p = 0.014$ ).

Group	N	Missing	Median	25%	75%
1222 TSS pipe	10	0	89.000	38	112
1324 TSS pipe	5	0	178.000	66	356
1325 TSS pipe	11	0	64.000	32	82
1419 TSS pipe	7	0	122.000	98	212

H = 10.611 with 3 degrees of freedom ( $p = 0.014$ ).

Figure 57 is a group box and whisker plot for the two combined sites having lower TSS values compared to the two combined sites having higher TSS values.



**Figure 57. Site categories for TSS concentrations.**

The Mann-Whitney Rank Sum Test indicated a highly significant difference between the medians of the two sites ( $p = 0.002$ ):


Group	N	Missing	Median	25%	75%
1222 and 1325 TSS pipe	21	0	68	36	94
1324 and 1419 TSS pipe	12	0	125	98	204

Mann-Whitney U Statistic= 43.5  
 $T = 286.500$ ;  $n$  (small) = 12;  $n$  (big) = 21;  $P = 0.002$

The following are additional summaries of these two categories:


Group	Size	Mean	Max	Min	Std Dev	COV
1222 and 1325 TSS pipe	21	98.6	696	26	142	1.4
1324 and 1419 TSS pipe	12	167	531	62	126	0.8

Similar comparison tests were also conducted with the SSC data, as shown in Figures 58 and 59. The box and whisker plot and the Kruskal-Wallis One Way Analysis of Variance on Ranks test indicated that at least one site was significantly different from the others ( $p = 0.022$ ). The sites were then grouped into two having lower SSC concentrations and two having higher SSC concentrations.



**Figure 58. SSC for monitored sites.**

Figure 59 is a group box and whisker plot showing the two site groupings.



**Figure 59. SSC monitored site categories.**

The Mann-Whitney Rank Sum test indicated that these two groups had significantly different median values ( $p = 0.003$ ).

Group	N	Missing	Median	25%	75%
1222 and 1325 SSC	21	0	68	38.5	96.5
1324 and 1419 SSC	12	0	123	109	209

Mann-Whitney U Statistic= 46.000  
 T = 284; n (small) = 12; n (big) = 21;  $p = 0.003$

Additional site SSC characteristics are shown below:


Group	Size	Mean	Std Dev	COV	Max	Min
1222 and 1325 SSC	21	101	141	1.4	693	25
1324 and 1419 SSC	12	171	129	0.8	543	59

### Summary of Biofilter Measurements during Rain Events

A tremendous amount of information was collected during this project, ranging from drainage area characteristics to runoff and flow monitoring data. The extended construction period resulted in only several events to be monitored after the construction period for analyses in this report, but the monitoring period is being extended into the next rainy season to obtain additional data.

The infiltration rates in the biofilters were monitored during actual rains by measuring the rate of drop of the ponded water during large rains. Statistical analyses identified three distinct groups of these data, as shown in the following list and group box and whisker plot (Figure 60).

- Very low: average 0.36 in/hr; range 0.19 to 0.62
- Moderate: average 1.8 in/hr; range 0.08 to 5.0
- Very high: average 3.2 in/hr; range 1.6 to 5.0




**Figure 60. Measured infiltration rates in biofilters during actual rains.**



The time to ponding after the rain started averaged about 0.5 hour, but it ranged from about 0.04 to 3.3 hours. The maximum depth of ponding was also separated into three categories, as shown below (separated by street addresses):

- Shallow: sites 2 (1325) and 8 (1222); average: 1.1 in., range: 0.0 to 5.6 in.
- Moderate: sites 1 (1324), 3 (1419), 4 (1612), 5 (1336), and 7 (1140); average: 3.3, range: 0.0 to 13.2
- Deep: site 9 (1112); average: 5.4, range: 2.8 to 8.3

Figure 61 is a group box and whisker plot showing these three combined sets of data for maximum depth of ponding.



**Figure 61. Maximum ponding depth observed in biofilters during actual rains.**

Laboratory column tests were conducted to investigate the biofilter media used at the Kansas City sites. Columns were constructed to measure the infiltration rates as a function of compaction (and therefore density). The density of the media column with hand compaction was  $1.00 \text{ g/cm}^3$ ; the density of the standard proctor media column was  $1.13 \text{ g/cm}^3$ , and the density for the modified proctor media column was  $1.12 \text{ g/cm}^3$ . The soil media has a median particle size ( $D_{50}$ ) of about 1.9 mm and a very high uniformity coefficient ( $C_u$ ) of 39. The porosity of the media for the hand compaction columns was 0.36, 0.15 for the standard proctor compaction columns, and 0.25 for the modified proctor compaction columns.

Infiltration data for different test trials were fitted to the Horton equation by using multiple nonlinear regressions to estimate  $f_c$  (the saturated soil infiltration rate),  $f_0$  (the initial rate), and  $k$  (the rate coefficient), using the observed data. The saturated rates were of greatest interest as they would apply during most of the operation during events. The estimated infiltration rates of the saturated media ranged from 0.4 to 0.8 in/hr for the hand compaction tests (initial rates were about 0.75 to 3 in/hr), 0.4 to 0.9 in/hr for the standard proctor compaction tests, and 0.03 to 0.33 in/hr for the modified proctor compaction tests. Only the modified compaction level significantly affected the infiltration rates. More than 90% of the media is larger than  $100 \mu\text{m}$ , with appreciable fractions clearly in the coarse sand category, resulting in a relatively robust media with minimal compaction potential. Media with large amounts of sand do not

compact as much as media having more fines, because of the structural support of the sand grains. Figure 62 contains example plots of the laboratory infiltration measurements fitted to the Horton equation for the hand compaction (least dense) tests.






Figure 62. Kansas City biofilter media infiltration rates during column tests for hand compacted density.

Samples were also collected of inflowing water entering the biofilters for analyses. Figure 63 is a PSD plot for the 20 influent samples. The median particle size (by mass) is about 30  $\mu\text{m}$ , and about 25% were larger than 100  $\mu\text{m}$ . The observed median size is typical for stormwater gutter/inlet samples but is larger than would be expected at a stormwater outfall (the larger particles are subjected to deposition in the drainage system).




**Figure 63. Particle size distribution for curb-cut influent stormwater samples.**

The stir plate and pipette TSS method has been shown to have the highest yield and most consistent results compared to the SCC values as standards. The shake and pour method shows reduced values compared to the pipette and SSC methods. The relationship between the shake and pour TSS and stir plate and pipette TSS values are consistent, but with about a 25% bias with the shake and pour results being less, as shown in Figures 64 and 65.



1: TSS by shake and pour; 2: TSS by stir and pipette; 3:SSC by cone splitter

**Figure 64. Particulate solids concentration comparisons because of different analytical methods.**



**Figure 65. TSS by shake and pour versus TSS by stirring and pipetting.**

The SSC data are statistically separated into two categories, as shown below:

Group	Size	Mean	Std Dev	COV	Max	Min
1222 and 1325 SSC	21	101	141	1.4	693	25
1324 and 1419 SSC	12	171	129	0.8	543	59

## 6. Evaluation of Performance of Stormwater Control Practices

### Characteristics of Areas Treated and Not Treated by Stormwater Controls

One of the important steps in urban stormwater quality modeling is to quantify the drainage area characteristics. The Kansas City GI demonstration site is unique because a very large portion of the test (pilot) area receives direct treatment from many separate stormwater control devices. However, as in all retrofit installations, stormwater controls could not be placed to treat the complete watershed area. Hindrances to installations of stormwater controls in established urban areas are mature trees that need to be protected, right-of-way restrictions and utility interferences, and other attributes such as the presence of driveways. The micro drainages resulting from original site grading at the time of initial construction seldom allows efficient installations of retrofitted controls compared to stormwater controls installed at the time of new construction.

Figure 66 is a map showing the test (pilot) watershed with all major source area components.




Figure 66. Map of test (pilot) area showing main surface characteristics.



Figure 67 is a similar map, but with only the details for the areas having stormwater control shown. The blanked-out areas drain into the combined sewer without any control. Some of the treated area's runoff flows some distance along the curbs and gutters before it enters the stormwater control practices. In addition, other areas are treated by multiple control units, as previously shown, with overflows from upgradient devices flowing into downgradient controls. This figure includes both the direct and the indirectly treated areas, with the untreated areas flowing directly into the combined sewers without any treatment indicated as blanked out.



**Figure 67. Map of test (pilot) area showing surface characteristics of areas receiving stormwater treatment.**

Figure 68 is a map showing the surface characteristics of the areas not being treated by any of the stormwater control devices before their runoff enters the combined sewer.



**Figure 68.** Map of test (pilot) area showing surface characteristics of areas not receiving stormwater treatment.

Table 31 summarizes the source areas for each of the controlled and uncontrolled subareas in the test (pilot) watershed. About 45% of the complete watershed does not receive any control and drains directly into the combined sewer, and about 55% of the area is treated. Therefore, the absolute upper limit of control is about 55%, assuming both subareas have identical source area makeups. However, the following table and associated maps indicate that the areas being treated are generally closer to the streets (including sidewalks, most of the driveways, and many of the roofs). The untreated areas have a greater portion of landscaped areas that drain through yard drains directly into the combined sewer system.



**Table 31. Site characteristics for areas receiving stormwater treatment and other areas**

Land component	Areas in subwatersheds with no stormwater controls		Areas in subwatersheds with stormwater controls		Total area (ac)
	Area (acres)	Percentage	Area (acres)	Percentage	
roofs - directly connected	1.11	2.40%	1.05	1.9%	2.16
roofs - drain to landscaped	6.29	13.7%	5.95	10.9%	12.24
driveway - directly connected	2.00	4.40%	2.30	4.2%	4.30
driveways - drain to perv	2.00	4.40%	2.30	4.2%	4.30
sidewalk - directly connected	0.38	0.80%	0.97	1.8%	1.35
sidewalks - to perv	0.45	1.00%	1.13	2.1%	1.58
Parking lot/ Paved area - directly connected	1.40	3.1%	3.40	6.3%	4.80
Streets - directly connected	3.50	7.6%	7.30	13.4%	10.80
Landscaped area - pervious area	28.70	62.6%	30.00	55.1%	58.70
Total area	45.83	100.0%	54.40	100.0%	100.23

Table 32 summarizes the impervious areas that are directly connected or that flow to pervious areas, or are the pervious areas (landscaped areas). The breakdown of the directly and indirectly connected impervious areas was estimated based on the full area land use monitoring. The total impervious area for the area being treated is about 45%, while the total impervious area for the untreated area is about 37%. The calculations and modeling in the following section determine the maximum amount of control possible, and shows the sensitivity of the native soil conditions on biofilter performance.

**Table 32. Impervious and pervious areas in subareas receiving stormwater treatment and other areas**

Land component	Areas in subwatersheds with no stormwater control		Areas in subwatersheds with stormwater controls	
	Area (acres)	Percent of subarea	Area (acres)	Percent of subarea
Impervious, directly connected	8.09	17.7%	15.02	27.6%
Impervious, draining to pervious areas	9.04	19.7%	9.38	17.2%
Pervious areas	28.70	62.6%	30.00	55.2%
Total area:	45.83	100.0%	54.40	100.0%

## Designs and Service Areas for Stormwater Controls in the Test (Pilot) Area

Before the modeling of the area, it was necessary to determine the different types (and number) of each type of stormwater control, and their design attributes, along with the drainage area characteristics for each type of control practice.

Figure 69 shows the layout for the 100-acre pilot study area with the locations of all of the types of stormwater controls. There are 158 individual surface features, along with 21 supplemental underground storage pipe systems. A list of the different surface and subsurface structural components are summarized in Table 33. The schematic drawings of stormwater controls are also cross-referenced in Table 33 for each of the unique design plan component categories. Table 34 summarizes typical sizes for each type of stormwater control, based on reviewing several examples from the 100% design drawings.




Figure 69. Stormwater controls in the 100-acre test (pilot) study area (source: Tetra Tech).

Table 33. Summary of stormwater control design plan components

Design plan component	Structural description	Number of this type of stormwater control	Figure reference*
Bioretention	Bioretention without curb extension	24	Figure 70
	Curb extensions with bioretention	28	
	Shallow bioretention	5	
Bioswale	Vegetated swale infiltrates to background soil	1	Figure 71
Cascade	Terraced bioretention cells in series	5	Figures 72 and 73
Porous sidewalk or pavement	With underdrain	18	Figure 74
	With underground storage cubes	5	
Rain garden	Rain garden without curb extension	64	Figure 75
	Curb extensions with rain gardens	8	
Below grade storage	Retains stormwater control overflow and underdrain outflow from selected bioretention cells or porous pavement	21	Figure 76



Source: SUSTAIN report, 2011

\* Source: 100% design plans and near-street topographic info.

**Table 34. Typical sizes of different types of stormwater controls used in the test (pilot) area**

Stormwater control type	Examples	Top area (ft <sup>2</sup> )	Bottom area (ft <sup>2</sup> )	Ponding depth	Total depth to bottom of device	Material
Cascade	1	423.41	105.58	8"–12"	> 16"–20"	Topsoil planting mix on side slopes, engineered soil mix 8-in. min depth on bottom.
	2	316.96	106.73			
	3	290.73	48.16			
	4	283.1	74.12			
Bioswale	1	1,948.86		12"	> 20"	Native soil amended with 3-in. compost, rototilled 8-in. min
Porous Sidewalk	1	1,640.42		Figure 74	Figure 74	Figure 74
	2	650.1				
	3	277.62				
	4	362.86				
	5	544.15				
	6	391.02				
Bioretention	1	194.21	34.12	12"	> 20"	3-in. hardwood mulch on top, topsoil planting mix on side slopes, engineered soil mix 8-in. min depth on bottom.
	2	240.6	28.77			
	3	301.37	31.85			
	4	337.5	55.28			
	5	335.89	53.5			
Curb extension with bioretention	1	383.03	98	12"	24"	Engineering soil mix
	2	169.35	56.32			
	3	238.68	85.24			
Curb extension with rain garden	1	237.01	123.96	12"	24"	Engineering soil mix
	2	265.43	115.98			
	3	279.54	112.9			
	4	275.87	97.63			
Rain garden	1	468.93	247.07	6"	> 17"	3-in. hardwood mulch on top, native soil amended with 3-in. compose, rototilled 8-in. min depth
	2	743.55	463			
	3	514.74	219.77			
	4	282.43	71.3			
	5	422.9	240			

Figures 70 through 76 are example construction drawings from the 100% design plans representing the various stormwater control designs constructed in the test (pilot) area, referenced in Table 33.



**Figure 70. Shallow bioretention device typical details for residential streets.**




Figure 71. Bioswale typical details for residential streets.




Figure 72. Cascade rain garden typical details for residential streets.







Figure 73. Cascade rain garden typical details for residential streets (continued).





**Figure 74. Porous sidewalk typical details for residential streets.**





Figure 75. Rain garden typical details for residential streets.




Figure 76. Below grade storage system typical details for residential streets.


## Modeling of Test (Pilot) Watershed Area with Stormwater Controls Compared to Observed Flows

Table 35 lists the monitored events that occurred after the majority of the site construction was completed, including the observed and calculated runoff for the complete area. The model was set up assuming the native soil infiltration rate was 1 in/hr below the biofilters, which resulted in the best model predictions compared to observed conditions. Lower native infiltration rates significantly decreased the calculated discharges, resulting in poor fits of the monitored data, for example.

**Table 35. Events after construction of stormwater controls in pilot watershed**

Rain start date	Rain start time	Rain end date	Rain end time	Total rain (in)	Observed total pipe flow discharge volume (ft <sup>3</sup> )	Modeled with controls (1 in/hr)
4/4/2012	8:45:00 PM	4/5/2012	9:10:00 AM	0.18	1,818	3,204
4/12/2012	3:20:00 PM	4/13/2012	4:15:00 AM	0.12	2,546	2,034
4/27/2012	8:40:00 PM	4/28/2012	8:40:00 AM	0.12	1,249	2,034
4/28/2012	10:45:00 PM	4/30/2012	7:50:00 AM	0.75	20,505	21,820
5/1/2012	1:40:00 AM	5/1/2012	10:30:00 PM	0.43	6,626	10,260
5/6/2012	10:05:00 AM	5/7/2012	8:55:00 PM	1.85	34,962	95,046
5/24/2012	8:35:00 PM	5/25/2012	8:10:00 PM	0.40	43,119	9,283
6/11/2012	2:50:00 AM	6/11/2012	7:35:00 PM	1.22	15,514	44,473
6/21/2012	1:20:00 AM	6/21/2012	9:00:00 PM	0.91	30,410	27,777

Figure 77 compares the predicted with the observed total runoff volumes for the complete test (pilot) watershed for nine events after biofilter construction.




**Figure 77. Observed and calculated flows after biofilter construction.**

ANOVA analysis of the regression indicated a significant equation ( $p = 0.014$ ) and a significant slope term ( $p = 0.012$ ). The slope coefficient is 1.22, with a 95% confidence range of 0.36 to 2.1. Additional monitoring at the large scale will enable more precise fits of the data and confirm the expected performance of the stormwater controls.


### Sources of Flows and Particulates in Untreated Watershed

Before a stormwater management plan is selected for an area, knowing the sources of the flows and pollutants of concern is very helpful. One of the main features of WinSLAMM is its ability to calculate these source contributions for varying rain conditions. The plots shown in Figures 78 and 79 illustrate these source contributions for the test (pilot) area without (before) stormwater controls, for rains ranging from 0.01 to 4 in.



Event number on graphs	Rain depth (in)
1	0.01
2	0.05
3	0.10
4	0.25
5	0.50
6	0.75
7	1.00
8	1.50
9	2.00
10	2.50
11	3.00

**Figure 78. Sources of runoff volume during different rain events (no control practices).**



Event number on graphs	Rain depth (in)
1	0.01
2	0.05
3	0.10
4	0.25
5	0.50
6	0.75
7	1.00
8	1.50
9	2.00
10	2.50
11	3.00
12	4.00

**Figure 79. Sources of particulate solids during different rain events (no control practices).**

Table 36 summarizes the major flow and particulate flows for 0.5-, 1.0-, and 3.0-in rains. As expected, the directly connected impervious areas are responsible for most of these contributions, but landscaped areas become important flow and particulate solids contributions for the largest rains expected in Kansas City.

**Table 36. Major source areas contributing runoff and particulate solids**

Rain depth (in)	Runoff volume	Particulate solids
0.5	Street areas (36%) Driveways, directly connected (21%) Paved parking areas, directly connected (12%) Small landscaped areas (11%)	Street areas (83%)
1.0	Street areas (32%) Driveways, directly connected (19%) Small landscaped areas (18%) Paved parking areas, directly connected (12%)	Street areas (53%) Small landscaped areas (20%) Driveways, directly connected (14%)
3.0	Small landscaped areas (37%) Street areas (22%) Driveways, directly connected (13%)	Small landscaped areas (50%) Street areas (24%) Driveways, directly connected (12%)

**Use of Stormwater Controls in Test (Pilot) Area**

Table 37 summarizes the characteristics for each category of stormwater control used in the test (pilot) area, including the number of each device and the expected areas being treated by each unit. The device areas as a percentage of drainage area are also shown, and range from about 1.5% for the biofilters to 9% for the bioswale.

**Table 37. Sizes and drainage area characteristics of subareas treated by stormwater controls**

Design plan component	Structural description	Number of this type of stormwater control units in test (pilot) area	Drainage area to device area ratio	Device as a % of the drainage area	Drainage area for each unit (ac)	Total area treated by each device type (ac)
Bioretention	Bioretention without curb extension	24	61.8	1.6	0.40	9.6
	Curb extensions with bioretention	28	66.1	1.5	0.40	11.2
	Shallow bioretention	5	61.8	1.6	0.40	2.0
Bioswale	Vegetated swale infiltrates to background soil	1	11.2	8.9	0.50	0.5
Cascade	Terraced bioretention cells in series	5	53.0	1.9	0.40	2.0
Porous sidewalk or pavement	With underdrain	18	1.0	100.0	0.015	0.3
	With underground storage cubes	5	1.0	99.9	0.015	0.1
Rain garden	Rain garden without curb extension	64	35.8	2.8	0.40	25.6
	Curb extensions with rain gardens	8	66.0	1.5	0.40	3.2
<b>total number of control units (w/o porous pvt)</b>		135			<b>total area treated</b>	<b>54.4</b>
<b>total area treated (acres)</b>		54.4				
<b>area per unit</b>		0.40				

Tables 38 through 45 summarize the sizes and other design characteristics for each of these categories of stormwater controls that were used in modeling the total system. Tables are also shown indicating the surface areas being treated by each stormwater device. The percentage components for each category are the same as the entire area average.



**Table 38. Modeling characteristics for bioretention areas**

	Bioretention subareas		Top area (ft <sup>2</sup> )	Bottom area (ft <sup>2</sup> )	Total depth (ft)	Typical width (ft)	Native soil infiltr rate (in/hr)
res1	Bioretention	Bioretention without curb extension	282	41	5	10	1.0
res2	Bioretention	Curb extensions with bioretention	264	80	5	10	1.0
res3	Bioretention	Shallow bioretention	282	41	2	10	1.0
res4	Cascade	Terraced bioretention cells in series	329	84	2	10	1.0
res5	Rain garden	Rain garden without curb extension	487	248	3.5	10	1.0
res6	Rain garden	Curb extensions with rain gardens	264	113	3.5	10	1.0

**Table 38. Modeling characteristics for bioretention areas (cont.)**

	Bioretention subareas		Rate fraction for sides	Rock filled depth (ft)	Rock filled porosity	Satur. water content (porosity) %	Field capacity, %	Permanent wilting point, %	Infiltr rate (in/hr)
res1	Bioretention	Bioretention without curb extension	1	2.5	0.4	43.4	21.8	4.6	1.8
res2	Bioretention	Curb extensions with bioretention	1	2.5	0.4	43.4	21.8	4.6	1.8
res3	Bioretention	Shallow bioretention	1	0	n/a	43.4	21.8	4.6	1.8
res4	Cascade	Terraced bioretention cells in series	1	0	n/a	43.4	21.8	4.6	1.8
res5	Rain garden	Rain garden without curb extension	1	1	0.4	43.4	21.8	4.6	1.8
res6	Rain garden	Curb extensions with rain gardens	1	1	0.4	43.4	21.8	4.6	1.8

**Table 38. Modeling characteristics for bioretention areas (cont.)**

	Bioretention subareas		Eng. media depth (ft)	Inflow hydrograph peak to avg flow rate	Number of devices in source area of this type	Weir crest length (ft)	Weir crest width (ft)	Height from datum to bottom of weir opening (ft)	Prairie plants coverage	Annuals coverage
res1	Bioretention	Bioretention without curb extension	1.5	3.8	24	8	1	4.75	0.75	0.25
res2	Bioretention	Curb extensions with bioretention	1.5	3.8	28	8	1	4.75	0.75	0.25
res3	Bioretention	Shallow bioretention	1	3.8	5	8	1	1.75	0.75	0.25
res4	Cascade	Terraced bioretention cells in series	1	3.8	5	8	1	1.75	0.75	0.25
res5	Rain garden	Rain garden without curb extension	1.5	3.8	64	8	1	3.25	0.75	0.25
res6	Rain garden	Curb extensions with rain gardens	1.5	3.8	8	8	1	3.25	0.75	0.25

**Table 39. ET rates for Kansas City biofiltration devices (in/day)**

Bioretention subareas			Jan	Feb	Mar	Apr	May	Jun	Jly	Aug	Sept	Oct	Nov	Dec
res1	Bioretention	Bioretention without curb extension	0.05	0.1	0.1	0.15	0.2	0.2	0.25	0.25	0.2	0.1	0.05	0.05
res2	Bioretention	Curb extensions with bioretention	0.05	0.1	0.1	0.15	0.2	0.2	0.25	0.25	0.2	0.1	0.05	0.05
res3	Bioretention	Shallow bioretention	0.05	0.1	0.1	0.15	0.2	0.2	0.25	0.25	0.2	0.1	0.05	0.05
res4	Cascade	Terraced bioretention cells in series	0.05	0.1	0.1	0.15	0.2	0.2	0.25	0.25	0.2	0.1	0.05	0.05
res5	Rain garden	Rain garden without curb extension	0.05	0.1	0.1	0.15	0.2	0.2	0.25	0.25	0.2	0.1	0.05	0.05
res6	Rain garden	Curb extensions with rain gardens	0.05	0.1	0.1	0.15	0.2	0.2	0.25	0.25	0.2	0.1	0.05	0.05

**Table 40. Modeling characteristics for porous pavement areas**

Porous Pavement subareas			Porous pvt area (acres)	Inflow hydro peak/avg ratio	Pavement thickness (in)	Pavement porosity	Aggreg bedding thickness (in)	Aggreg bedding porosity	Aggreg base reser thickness (in)	Aggreg base porosity
res7	Porous sidewalk or pavement	With underdrain	0.015	3.8	3	0.4	3	0.4	12	0.45
res8	Porous sidewalk or pavement	With underground storage cubes	0.015	3.8	3	0.4	3	0.4	36	0.95

**Table 40. Modeling characteristics for porous pavement areas (cont.)**

Porous Pavement subareas			Perforated underdrain D (in)	Underdrain invert elev (in)	Number of underdrains	Subgrade seepage rate (in/hr)	Por pvt initial infilt rate (in/hr)	% after 3 yrs	% after 5 yrs	Total clogging (yrs)	% restored with cleaning	Cleaning frequency
res7	Porous sidewalk or pavement	With underdrain	3	8	1	1	40	80	50	10	75%	1/yr
res8	Porous sidewalk or pavement	With underground storage cubes	n/a	n/a	n/a	1	40	80	50	10	75%	1/yr

**Table 41. Modeling characteristics for swale drained areas**

Swale subareas	Fraction of area served by swales	Swale density (ft/ac)	Bottom width (ft)	Swale side slope H/1V	Long slope V/1H	Retardance factor	Grass height (in)	Dynamic infiltr rate (in/hr)	Swale depth (ft)	
res9 Bioswale	Vegetated swale infiltrates to background soil	100%	MDR land use value	3	3	0.02	D	4	0.5	3

**Table 42. Drainage areas to bioretention areas**

Bioretention subareas	Roofs1 (directly connected)	Roofs2 (to pervious areas)	Pvdpark1 (directly connected)	Drvy1 (directly connected)	Drvy2 (to pervious areas)	Sidwlks1 (directly connected)	Sidwlks (to pervious areas)	Streets1	Small landscp	Total Area (acres)	
res1 Bioretention	Bioretention without curb extension	0.182	1.046	0.605	0.403	0.403	0.173	0.202	1.286	5.299	9.6
res2 Bioretention	Curb extensions with bioretention	0.213	1.221	0.706	0.470	0.470	0.202	0.235	1.501	6.182	11.2
res3 Bioretention	Shallow bioretention	0.038	0.218	0.126	0.084	0.084	0.036	0.042	0.268	1.104	2.0
res4 Cascade	Terraced bioretention cells in series	0.038	0.218	0.126	0.084	0.084	0.036	0.042	0.268	1.104	2.0
res5 Rain garden	Rain garden without curb extension	0.486	2.790	1.613	1.075	1.075	0.461	0.538	3.430	14.131	25.6
res6 Rain garden	Curb extensions with rain gardens	0.061	0.349	0.202	0.134	0.134	0.058	0.067	0.429	1.766	3.2

**Table 43. Drainage areas to porous pavements**

Porous Pavement subareas	Roofs1 (directly connected)	Roofs2 (to pervious areas)	Pvdpark1 (directly connected)	Drvy1 (directly connected)	Drvy2 (to pervious areas)	Sidwlks1 (directly connected)	Sidwlks (to pervious areas)	Streets1	Small landscp	Total Area (acres)	
res7 Porous sidewalk or pavement	With underdrain	0.006	0.033	0.019	0.013	0.013	0.005	0.006	0.040	0.166	0.3
res8 Porous sidewalk or pavement	With underground storage cubes	0.002	0.011	0.006	0.004	0.004	0.002	0.002	0.013	0.055	0.1

**Table 44. Drainage areas to swales**

Swale subarea	Roofs1 (directly connected)	Roofs2 (to pervious areas)	Pvdpark1 (directly connected)	Drvy1 (directly connected)	Drvy2 (to pervious areas)	Sidwlks1 (directly connected)	Sidwlks (to pervious areas)	Streets1	Small landscp	Total Area (acres)
res9 Bioswale Vegetated swale infiltrates to background soil	0.010	0.055	0.032	0.021	0.021	0.009	0.011	0.067	0.276	0.5

**Table 45. Drainage areas not treated by stormwater controls**

	Roofs1 (directly connected)	Roofs2 (to pervious areas)	Pvdpark1 (directly connected)	Drvy1 (directly connected)	Drvy2 (to pervious areas)	Sidwlks1 (directly connected)	Sidwlks (to pervious areas)	Streets1	Small landscp	Total Area (acres)
res10 no controls	1.099	6.275	1.420	2.015	2.015	0.366	0.458	3.481	28.671	45.8

Tables 46 and 47 summarize the calculated runoff conditions entering the stormwater controls, along with the expected removals for each type of device. The runoff volume reductions range from 86 to 100% for a 4-year continuous simulation period (the same period and events included in the monitoring period). The predicted maximum water depths in the biofilters range from about 2 to 5 in, similar to the water depths observed. The maximum ponding times for the biofilters range from about 60 to 90 hours. Only a single event in the 4 years of simulation had a holding time longer than 3 days, the typical criterion for mosquito control. Only about one-third of the events might have any surface or underdrain discharges, and these amounts would be small compared to the treated volumes.

**Table 46. Calculated stormwater control performance**

Control practice no.	Control practice type	Control practice name or location	Total inflow volume (ft <sup>3</sup> )	Total outflow volume (ft <sup>3</sup> )	Percent volume reduction	Total influent load (lbs)	Total effluent load (lbs)	Percent load reduction	Flow weighted influent conc (mg/l)	Flow weighted effluent conc (mg/L)	Percent conc. reduction
1	Biofilter	DS Biofilters # 1	1,234,000	259,759	79%	16,138	2,248	86%	210	138.6	34%
2	Biofilter	DS Biofilters # 2	1,440,000	229,535	84%	18,844	1,943	90%	210	135.6	35%
3	Biofilter	DS Biofilters # 3	257,173	56,361	78%	3,358	488	85%	209	138.7	34%
4	Biofilter	DS Biofilters # 4	257,173	36,807	86%	3,493	314	91%	218	136.8	37%
5	Biofilter	DS Biofilters # 5	3,292,000	72,824	98%	43,059	602	99%	210	132.5	37%
6	Biofilter	DS Biofilters # 6	411,738	51,201	88%	5,384	429	92%	210	134.1	36%
7	Grass Swales	DS Grass Swales # 1	64,704	12,950	80%	845	74	91%	209	91.12	56%
8	Porous Pavement	SA Device, LU# 7 ,SA# 31	2,635	0	100%	12	0	100%	75	0	100%
9	Porous Pavement	SA Device, LU# 7 ,SA# 32	258	0	100%	1	0	100%	75	0	100%
10	Porous Pavement	SA Device, LU# 8 ,SA# 31	753	0	100%	4	0	100%	75	0	100%
11	Porous Pavement	SA Device, LU# 8 ,SA# 32	74	0	100%	0	0	100%	75	0	100%

**Table 46. Calculated stormwater control performance (cont.)**

Control practice no.	Control practice type	Control practice name or location	Influent median part. Size (microns)	Effluent (surface overflow) median part. Size (microns)	Maximum stage (ft)	Hydraulic volume out (cf)	Maximum surface ponding time (hrs)	Maximum subsurface ponding time (hrs)
1	Biofilter	DS Biofilters # 1	29.31	29.31	4.77	10,718	92	90
2	Biofilter	DS Biofilters # 2	29.31	29.31	4.77	8,091	87	87
3	Biofilter	DS Biofilters # 3	29.31	29.31	1.77	11,174	92	91
4	Biofilter	DS Biofilters # 4	29.31	29.31	1.77	7,292	86	87
5	Biofilter	DS Biofilters # 5	29.31	29.31	3.27	1,191	57	77
6	Biofilter	DS Biofilters # 6	29.31	29.31	3.27	6,284	83	85

**Table 46. Calculated stormwater control performance (cont.)**

Control practice no.	Control practice type	Control practice name or location	Volume infiltrated (cf)	Underdrain discharge Vol. (cf)	Evapo- transpir. vol. (cf)	Surface discharge bypass vol. (cf)	Surface ponding events >72 hrs (count)	Runoff producing events/ total rains
1	Biofilter	DS Biofilters # 1	40,152	0	350	10,666	1	68/190
2	Biofilter	DS Biofilters # 2	42,468	0	683	8,004	1	83/190
3	Biofilter	DS Biofilters # 3	39,781	0	341	11,123	1	56/190
4	Biofilter	DS Biofilters # 4	43,720	0	718	7,203	1	37/190
5	Biofilter	DS Biofilters # 5	47,937	0	2,116	1,038	0	88/190
6	Biofilter	DS Biofilters # 6	44,017	0	964	6,176	1	42/190
7	Grass Swales	DS Grass Swales # 1	0					0/190
8	Porous Pavement	SA Device, LU# 7 ,SA# 31	2,635	0				0/190
9	Porous Pavement	SA Device, LU# 7 ,SA# 32	258	0				0/190
10	Porous Pavement	SA Device, LU# 8 ,SA# 31	753	0				0/190
11	Porous Pavement	SA Device, LU# 8 ,SA# 32	74	0				0/190


**Table 47. Calculated stormwater conditions for treated and untreated areas**

	Area (acres)	Area as a % of total area	Runoff volume (ft <sup>3</sup> /year)	Rv	Partic solids (mg/L)	Part. solids yield (lb/yr)	Part. solids yield (lb/ac/yr)	% flow of total area	% part. solids of total area	% Flow reductions compared to untreated conditions	% Part.solid reductions compared to untreated conditions
Total Site Conditions, before controls	100.30		2,802,000	0.23	204	35,677	356	n/a	n/a	n/a	n/a
Untreated site area	45.80	45.7%	1,097,000	0.20	195	13,356	292	39.2%	37.4%	n/a	n/a
Area to be treated	54.50	54.3%	1,704,000	0.26	210	22,321	410	60.8%	62.6%	n/a	n/a
Total site conditions, after controls	100.30		1,284,000	0.11	187	14,998	150	n/a	n/a	54.2%	58.0%
Untreated site area	45.80		1,097,000	0.20	195	13,356	292	85.4%	89.1%	0.0	0.0
Treated area with controls	54.50		186,714	0.03	141	1,642	141	14.5%	10.9%	89.0%	92.6%

The following report sections are summaries of how these stormwater controls are modeled and how they can be sized to provide the desired benefits of a stormwater management program.

## Summary of Monitored and Modeled Performance of Stormwater Control Practices

The Kansas City GI demonstration project site is unique because a very large portion of the test (pilot) area receives direct treatment from many separate stormwater control devices, and the large area is being monitored to demonstrate the actual flow reductions. However, as in all retrofit installations, stormwater controls could not be placed to treat all the flows from the entire watershed area because of interferences from existing infrastructure, large trees, and surface drainage paths. The map in Figure 80 shows the subareas having stormwater control before being discharged into the combined sewer. The blanked-out areas drain into the combined sewers directly without any surface infiltration or retention control. Some areas are treated by multiple control units, with overflows from upgradient devices flowing into downgradient controls.




**Figure 80. Areas receiving surface stormwater control before being discharged into the combined sewer.**

The total impervious area for the area being treated is about 45%; the total impervious area for the untreated area is about 37%, indicating greater flows from the treated areas than indicated if based only on the total subareas. The calculations and modeling efforts determine the maximum amounts of stormwater control possible, reflecting the different land development characteristics in the treated and untreated subareas and showing the sensitivity of the native soil conditions on biofilter performance.

Figure 81 compares the modeled to the monitored events that occurred after the majority of the site construction was completed. The model used a native soil infiltration rate of 1 in/hr below the biofilters,




which results in reasonable predictions as shown in the figure. Lower native infiltration rates (as in the initial design calculations) resulted in significantly decreased calculated discharges, resulting in poor fits of the data.



**Figure 81. Modeled versus observed flows in the test (pilot) area after construction of stormwater controls.**

One of the main features of WinSLAMM is its ability to calculate these source contributions for varying rain conditions. Figure 82 illustrates the source contributions for the test (pilot) area without stormwater controls, for rains ranging from 0.01 to 4 in. The sources of flows (and pollutants) vary with the rain characteristics, but the directly connected areas are most important for the small- and intermediate-sized rains, with pervious contributions becoming more important as rains increase in size.



**Figure 82. Sources of runoff volume during different rain events (no control practices).**

Table 48 summarizes the characteristics for each category of stormwater control used in the test (pilot) area, including the number of each device type and the average areas being treated by each type of control. The device areas as a percentage of drainage area are also shown and range from about 1.5 to 2% for the biofilters to 9% for the bioswale. The porous pavement sidewalks treat 100% of the sidewalk areas because they do not receive runoff from adjacent areas.

**Table 48. Summary of the stormwater controls constructed in the test (pilot) watershed**

Design plan component	Structural description	Number of this type of stormwater control units in test (pilot) area	Drainage area to device area ratio	Device as a % of the drainage area	Drainage area for each unit (ac)	Total area treated by these devices (ac)
Bioretention	Bioretention without curb extension	24	61.8	1.6%	0.40	9.6
	Curb extensions with bioretention	28	66.1	1.5%	0.40	11.2
	Shallow bioretention	5	61.8	1.6%	0.40	2.0
Bioswale	Vegetated swale infiltrates to background soil	1	11.2	8.9%	0.50	0.5
Cascade	Terraced bioretention cells in series	5	53.0	1.9%	0.40	2.0
Porous sidewalk or pavement	With underdrain	18	1.0	100.0%	0.015	0.3
	With underground storage cubes	5	1.0	99.9%	0.015	0.1
Rain garden	Rain garden without curb extension	64	35.8	2.8%	0.40	25.6
	Curb extensions with rain gardens	8	66.0	1.5%	0.40	3.2
	Total number of control units (w/o porous pvt)	135			Total area treated	54.4
	Total area treated (acres)	54.4				
	Area per unit	0.40				

The calculated runoff volume reductions range from 86 to 100% for a 4-year continuous simulation period corresponding to the site total monitoring period (September 2008 through October 2012). The predicted maximum water depths in the biofilters ranged from about 2 to 5 in, similar to the water depths observed. The maximum ponding times for the biofilters ranged from about 60 to 90 hours. Only a single event in the 4 years of simulation had a holding time longer than 3 days, the typical criterion for mosquito control. Only about one-third of the events likely have any surface or underdrain discharges, and these amounts would be very small compared to the untreated volumes.

## 7. Stormwater Control Production Functions

WinSLAMM was used to examine a series of stormwater control practices, including rain barrels and water tanks for stormwater irrigation, pavement and roof disconnections, roof rain gardens, infiltration/biofiltration in parking lots and as curb-cut biofilters, street cleaning, grass swales, porous pavement, and selected combinations of these practices for the Kansas City regional land use conditions. The model evaluates the practices through engineering calculations of the unit processes on the basis of the actual design and size of the controls specified, and it determines how effectively the practices remove runoff volume and pollutants.

WinSLAMM does not use a percent imperviousness value or a curve number to generate runoff volume or pollutant loadings. The model applies runoff coefficients to each *source area* in a land use category. Each source area has a different runoff coefficient equation based on factors such as slope, type and condition of surface, soil properties, and such, and calculates the runoff expected for each rain. The runoff coefficients were developed using monitoring data from typical examples of each site type under a broad range of conditions. The runoff coefficients are continuously updated as new research data become available.

For each rain in a data set, WinSLAMM calculates the runoff volume and pollutant load (EMC x runoff volume) for each source area. The model then sums the loads from the source areas to generate a land use or drainage basin subtotal load. The model continues this process for the entire rain series included in the rain file. It is important to note that WinSLAMM does not apply a *unit load* to a land use. Each rainfall produces a unique load from a modeled area on the basis of the specific source areas in that modeled area.

The model replicates the physical processes occurring in the practice. For example, for a wet detention pond, the model incorporates the following information for each rain event:

1. Runoff hydrograph, pollution load, and sediment particle size distribution from the drainage basin to the pond
2. Pond geometry (depth, area)
3. Hydraulics of the outlet structure
4. Particle settling time and velocity in the pond based on retention time

Stokes Law and Newton's settling equations are used in conjunction with conventional surface overflow rate calculations and modified Puls-storage indication hydraulic routing methods to determine the sediment amounts and characteristics that are trapped in the pond. Again, it is important to note that the model does not apply *default* percent efficiency values to a control practice. Each rainfall is analyzed, and the pollutant control effectiveness varies according to each rainfall and the pond's antecedent condition.

The model's output is comprehensive and customizable, and typically includes

1. Runoff volume, pollutant loadings and EMCs for a period of record or for each event, or both
2. The above data pre- and post- for each stormwater management practice
3. Removal by particle size from stormwater management practices applying particle settling
4. Other results can be selected related to flow-duration relationships for the study area, impervious cover model expected biological receiving water conditions, and life-cycle costs of the controls

A full explanation of the model's capabilities, calibration, functions, and applications is at [www.winslamm.com](http://www.winslamm.com). For this project, the parameter files were calibrated using the local Kansas City monitoring data, supplemented by additional information from regional data from the NSQD, available at <http://www.unix.eng.ua.edu/~rpitt/Research/ms4/mainms4.shtml>.

## Pavement and Roof Disconnections

The first stormwater control that should be considered in an area is disconnecting the directly connected impervious areas, such as roofs and paved parking lots. WinSLAMM can evaluate disconnections in different ways. The most direct way to evaluate disconnections of impervious areas is by changing the source area parameter characteristic from directly connected (or draining to a directly connected area) to draining to a pervious area (partially connected impervious area), as shown in Figure 83. If the area has clayey soils, the building density is needed, and if it is a medium- or high-density area, the presence of alleys also needs to be known. This process is based on extensive monitoring of residential and commercial sites that ranged from completely connected to completely disconnected with varying density and soil conditions (Pitt 1987). Table 49 shows the results of these disconnections, showing excellent control when all areas are disconnected. For example, to obtain good receiving water habitat conditions, all the roofs and the parking areas must be disconnected in this example. As expected from observing the flow source area plot, disconnecting only a portion of these impervious areas has limited benefits. It is noted that the concentrations of the pollutants increase with increasing roof disconnections because the better quality roof runoff is being infiltrated and not diluting the runoff from the paved parking/storage area. However, the mass discharges all decrease with increased disconnections.

Source Area Parameters

Land Use: Residential 1      Total Area: 1.046 acres

Source Area: Roof 2

Roofs:  Flat Roof       Pitched Roof

Is the Source Area:

Directly Connected or Draining to a Directly Connected Area

Draining to a Pervious Area (partially connected impervious area)

Soil Type:       Sandy     Silty     Clayey

Building Density:     Low     Medium or High

Alleys present:     Yes     No

Continue

Figure 83. Disconnection of pitched roof to silty soil.

**Table 49. Effectiveness of disconnecting impervious areas in 2.25-acre commercial site over 10 years**

Description	Rv	Expected habitat conditions	TSS (mg/L)	solids yield (lbs/yr)	peak runoff rate (cfs)	TP (mg/L)	TP load (lbs)	Cu (µg/L)	Cu load (lbs)
Base conditions, no controls	0.55	Poor	100	1,040	4.6	0.28	29	17	1.7
Flat roof disconnections	0.47	Poor	112	990	3.8	0.29	26	18	1.6
Pitched roof disconnections	0.46	Poor	115	980	3.7	0.29	25	18	1.6
Both roof disconnections	0.38	Poor	132	930	3.0	0.31	22	20	1.4
Parking lot disconnections	0.25	Poor	66	309	1.9	0.36	17	12	0.56
All roofs and parking area disconnections	0.08	Good	140	200	0.72	0.67	9.8	15	0.21

Rain gardens, rain barrel/tanks, and disconnection of roof runoff are controls being used on private property in the residential areas in the Kansas City Marlborough GI test (pilot) area. Their maximum benefit is therefore dependent on the amount of runoff that is contributed from the source areas where they would be located. These controls receive runoff from the roofs. Table 50 shows that the directly connected roofs contribute only about 5.8%, but the much greater area of disconnected roofs contribute about 7.2% of the annual runoff from the entire 100-acre area. The current flow contributions of all roofs in the area total about 13%. If all the roofs were directly connected, the roofs would contribute about 31% of the total area runoff, and the runoff from the total area would increase by about 25%, a significant increase. In contrast, if the directly connected roofs were disconnected through a downspout disconnection program, the total roof contribution would decrease to about 9%, and the total area runoff would decrease by about 5%. Because about 85% of the existing roofs in the area are already disconnected, the benefits of controlling the remaining directly connected roofs are therefore limited.

**Table 50. Effectiveness of roof area disconnections.**

	Roof 1 areas (directly connected) (1.87 acres)	Roof 2 areas (disconnected) (10.57 acres)	Land use total (100 acres)	Whole area Rv
Base conditions (ft <sup>3</sup> /year)	257,200	319,200	4,449,000	0.30
% contributions	5.8%	7.2%		
% roof contributions	13.0%			
if all roofs connected (ft <sup>3</sup> /year)	257,200	1,458,000	5,588,000	0.38
% contributions	4.6%	26.1%		
% roof contributions	30.7%			
if all roofs disconnected (ft <sup>3</sup> /year)	56,340	319,200	4,248,000	0.29
% contributions	1.3%	7.5%		
% roof contributions	8.8%			

Table 51 shows that directly connected roofs in the study area contribute about 4.5 times the amount of runoff per unit area as the disconnected roofs. This indicates that about 78% of the annual runoff from the disconnected roofs is infiltrated as it passes over pervious areas on the way to the drainage system. Therefore, it is much less cost-effective to use roof runoff controls for the runoff from the disconnected roofs compared to runoff controls for the directly connected roofs. If an infiltration or beneficial use control is used to control runoff from disconnected roofs, they would have to be about 4.5 times larger than if used for runoff control from directly connected roofs, to have the same benefit on the overall discharge volume from the area.

**Table 51. Disconnected and directly connected roof runoff differences**

	Area (acres)	Annual runoff (ft <sup>3</sup> )	Runoff contributions to outfall per roof area (ft <sup>3</sup> /acre/year)
Roof 1 areas (directly connected)	1.87	257,200	137,500
Roof 2 areas (disconnected)	10.57	319,200	30,200
Ratio of disconnected to directed connected	5.65	1.24	0.220

The benefits of disconnecting connected paved parking or storage areas are similar to the benefits shown above for roofs. However, disconnecting these areas as part of a retrofit program is likely to be difficult because extensive re-grading would be needed, or at least a suitable adjacent undeveloped or landscaped area downgradient of the paved area would be needed. No such areas are available in the test area, for example, and are expected to be rare. In redevelopments and in new developments, this might be a more suitable option. However, the use of biofilters to infiltrate the runoff at directly connected paved areas is likely a much more suitable option.

### Roof Runoff Rain Gardens

Private rain gardens for controlling roof runoff are being used in the residential areas in the Kansas City CSO GI demonstration project test (pilot) area. The performance of these devices is affected by several unit processes, which are modeled in WinSLAMM. Modified puls hydraulic routing, with surface overflow calculations, are the basic processes modeled. However, several layers in the rain garden (or biofilter) must be considered. As runoff enters the device, water infiltrates through the engineered soil or media (or natural soil, in a rain garden). If the entering rain cannot all be infiltrated through the surface layer, the water ponds. If the ponding becomes deep, it can overflow through the broad-crested weir or other surface outlet. The percolating water moves down through the device until it reaches the bottom and intercepts the native soil. If the native soil infiltration rate is greater than the percolation water rate, no subsurface ponding occurs; if the native soil infiltration rate is slower than the percolation water rate, ponding occurs. This ponding can build up to the surface of the device and add to the surface ponding. If an underdrain is present (usually with a subsurface storage layer), the subsurface ponding will be intercepted by the drain which then discharges it to the surface water, but later in the event (or directly to the combined sewer system).

With the water percolating through the engineered soil or other fill, particulates and particulate-bound pollutants are trapped by the media through filtering actions. Therefore, the underdrain water usually has a lower particulate solids content than the surface waters entering the device. The calculations are sensitive to the amount of the different media used as fill (or the native soil) and its characteristics (especially its porosity and percolation rate; and if ET is used, the wilting point). The hydraulic routing uses the sum of the void volumes in the device to determine the effluent hydrograph, while the different infiltration/percolation rates affect the internal ponding. The stage-discharge relationships of the outlet devices are all modeled using conventional hydraulic processes. The ET loss calculations are based on the changing water content in the root zone at each time increment, and the ET adjustment factors for the mixture of plants in the device (Pitt et al. 2008a).

Figure 84 is the main WinSLAMM input screen used for rain gardens. This is a general format that is also used for other infiltration devices, including biofilters and bioinfiltration devices. This form includes the geometry of the device and material placed in the device. Most simple rain gardens do not have any special media, using only soils, nor do they have underdrains, so only some of the form is used. In this example, a loam soil is used in the rain garden, and the subsurface native soil is assumed to be a sandy loam having long-term infiltration rates of about 1.0 in/hr. As indicated, it is possible to also incorporate a Monte Carlo routine to better represent the variable infiltration rates that any individual unit has. All the devices using this input screen require a hydraulic overflow, described as a broad crested weir. For these

devices, evaporation of water from any pooled standing water above the soil and ET losses associated with plants installed in the rain garden, are also added as outlet devices. The engineered soil media characteristics screen is shown in Figure 85, as an example.




Figure 84. Rain garden input screen.






Figure 85. Detailed media characteristics for rain gardens.



The performance of a rain garden for controlling runoff from directly connected pitched roofs is summarized in Table 52 and Figure 86. As a rain garden increases in size in relationship to the roof area, less water is discharged to the storm or combined sewer. About 80% of the long-term runoff would be infiltrated for a rain garden that is about 20% of the roof area for these conditions. The concentrations all remain the same, because there is no underdrain or subsurface collection of filtered water; the water quality of the water discharged through the surface overflow weir is assumed to be the same as the incoming water. However, the mass discharges are decreased as the runoff volume decreases. The roof runoff has relatively low TSS concentrations, and the life of the rain gardens shown here would be very long, with very little clogging potential (clogging of biofilters occur with accumulative solids loadings of about 10 to 25 kg/m<sup>2</sup>). The peak flow rate reductions are also substantial; about 64% reductions of the uncontrolled peak flow rate for rain gardens that are about 20% of the roof area.

**Table 52. Rain garden performance for directly connected pitched roofs**

Rain garden as a % of contributing roof area	Estimated habitat conditions	TSS (mg/L)	Peak runoff rate (cfs)	Peak flow rate reduction (%)	TP (mg/L)	TP load (lbs)	Cu (µg/L)	Cu load (lbs)
	Poor	33	0.87	0	0.22	4.2	11	0.21
2%	Poor	33	0.78	10	0.22	3.4	11	0.17
5%	Poor	33	0.67	23	0.22	2.6	11	0.13
10%	Poor	33	0.47	46	0.22	1.6	11	0.08
15%	Poor	33	0.34	61	0.22	1	11	0.05
20%	Fair	33	0.31	64	0.22	0.59	11	0.029
25%	Good	33	0.28	68	0.22	0.35	11	0.017
30%	Good	33	0.22	75	0.22	0.19	11	0.0095
40%	Good	33	0.15	83	0.22	0.039	11	0.0019
50%	Good	33	0.079	91	0.22	0.01	11	0.00045



**Figure 86. Calculated roof runoff rain garden performance as a function of size.**





Figure 86. Calculated roof runoff rain garden performance as a function of size (cont.).

Another example is for rain gardens having a top surface area of 160 ft<sup>2</sup>, being about 10 by 16 ft in area. It is excavated to an overall depth of 3 ft, with 2 ft backfilled with a loam soil. The top 1 ft of surface is left open to provide surface storage 9 in deep (with a 3 inch overflow weir opening). A native soil infiltration rate of 0.2 in/hr was used in these calculations, while the loam soil fill had only a 0.15 in/hr infiltration rate. The only outlet used (besides the natural infiltration) is a surface overflow along one edge of the rain garden. One of these rain gardens per house represents about 17% of the typical roof area in the study area.

Table 53 and Figure 87 summarize the continuous modeling results for several different sizes and numbers of rain gardens, per house, according to the 1990 rain year (the year that was selected as being representative of the long-term rain record for Kansas City). As noted above, disconnected roofs already experience substantial runoff reductions (about 78%) in the study area, even when low infiltration rates are assumed. Rain gardens sized to be about 13% of the roof areas would be equivalent to the current benefits of disconnected roof drainage. This corresponds to a rain garden having about 120 ft<sup>2</sup> of surface area per house, with the rain garden overflow then flowing directly to the drainage system.

**Table 53. Numbers and sizes of rain gardens to provide specific roof runoff flow benefits**

# rain gardens per house	ft <sup>2</sup> of rain gardens per house	% of roof area as rain garden	% reduction in roof runoff	Total number of rain gardens if usage rate applied to all 576 homes	Total storage in rain gardens if applied to all 576 homes (ft <sup>3</sup> )	Total storage in rain gardens if all 576 homes used them (gal)	Total storage in rain gardens if only used for 86 directly connected roofs (gal)
0	0	0%	0%	0	0	0	0
0.035	5.6	1%	5%	20	2,460	18,400	2,760
0.1	16	2%	14%	58	7,030	52,600	7,890
0.25	40	4%	33%	144	17,600	131,500	19,700
0.5	80	8%	57%	288	35,140	263,000	39,400
1	160	17%	84%	576	70,300	526,000	78,900
2	320	34%	96%	1150	140,500	1,052,000	158,000
4	640	68%	100%	2300	281,100	2,104,000	316,000



**Figure 87. Production function for rain garden use for control of total annual roof runoff volume.**

The continuous simulations examined all 98 rain events that occurred in the typical 1990 rain year. The six rains closest to 1.4-in total depth (the critical event for the local CSO consent decree) for this year are shown in Tables 54 and 55. During this year, three rains were also larger than 1.4 in: 3.23, 3.11, and 2.18 in. The six rains close to 1.4 in ranged in depth from 1.21 to 1.76 in and had durations ranging from 8 to 28 hours. Antecedent dry periods ranged from 8 hours to about 4 days, and the total rain depth that occurred in the week before these rains ranged from 0.02 to 1.24 in.

**Table 54. Large rains close to 1.4-inch design storm *D***


Date	Rainfall (in)	Event duration (hrs)	Average rain intensity (in/hr)	Prior event interevent period (days)	Prior event rain depths for at least a week before (in, and its prior interevent periods in days)	Total rain fall in week before event (in)
3/14/1990	1.28	28	0.05	0.33	0.14 (0.67); 0.52 (1.1); 0.08 (0.25); 0.19 (3.0)	0.93
4/26/1990	1.76	26	0.07	0.92	0.03(5.0); 0.01 (5.0)	0.04
6/6/1990	1.22	8	0.15	3.8	0.01 (3.1); 0.01 (5.2)	0.02
6/8/1990	1.22	12	0.1	2.1	1.22 (3.8); 0.01 (3.1); 0.01 (5.2)	1.24
7/21/1990	1.67	13	0.13	0.58	0.39 (0.33); 0.08 (6.5)	0.47
10/2/1990	1.21	15	0.08	3	0.12 (8.5)	0.12
average	1.39	17	0.10			0.47
standard deviation	0.25	8.1	0.038			0.51
COV	0.18	0.48	0.38			1.1

The storage provided in the rain gardens is somewhat larger than the amount of runoff removed during the design storm *D* that is 1.4 in. Continuous simulations of this one year’s rains considers antecedent conditions in the rain garden, specifically, some of the storage capacity might not be available because some of the water from a prior event might not have completely drained. This is especially true in areas of poorly draining soils. The total drainage time in this general rain garden design is about 4 days, with about 1.5 to 2 days needed to drain the maximum ponding on the surface of the rain garden. Any rain that occurs before the rain garden can completely drain will increase the overall drainage time needed and reduce the amount of effective storage available for a subsequent event.

**Table 55. Roof runoff volumes for large rains close to 1.4-in design storm *D***

Date	Rainfall (in)	Base conditions, total runoff (ft <sup>3</sup> /100 ac)	Base conditions, Rv at outfall	Directly con. roof (ft <sup>3</sup> 86 of 576 homes)
3/14/1990	1.28	151,000	0.32	8,497
4/26/1990	1.76	227,000	0.35	11,739
6/6/1990	1.22	143,000	0.32	8,098
6/8/1990	1.22	143,000	0.32	8,098
7/21/1990	1.67	211,000	0.35	11,113
10/2/1990	1.21	141,000	0.32	8,032
average	1.39	169,000	0.33	9,260
standard deviation	0.25	38,800	0.015	1,700
COV	0.18	0.23	0.047	0.18

For up to one rain garden per house (17% of roof area), the storage provided is about 30 to 40% greater than the actual amount of runoff removed during storms that are close to the 1.4-in depth. This additional storage volume is related to the typical antecedent conditions before these rains, especially assuming the low infiltration rates used in this example. When the desired level of performance increases, this over-design volume also increases. When two rain gardens are used per house (totaling 34% of the roof area), the actual storage in the rain garden is about 2.3 times the volume removed, and when the rain garden usage is further increased to four per house (64% of roof area), the actual storage is about 4.6 times the roof runoff removed. This is evidenced by the non-linear plot shown below, which flattens out considerably for the largest removal rates. Using two rain gardens per house results in complete removal of the runoff from directly connected roofs from the drainage system during this 1.4-in site design storm, so that is the practical upper limit when considering only the design storm regulatory objectives. When the number of rain gardens is increased above one, the rain gardens do not always fill completely during all the rains in this size category. However, additional rain garden area could be used to increase the total amount of runoff reduction when the complete annual rain series is considered, as shown above. Using two rain gardens per house provides 100% control of the regulatory design storm, and it results in an expected 96% reduction in the total annual runoff from the directly connected roofs, as shown in Figure 88.



**Figure 88.** Performance function of roof runoff rain garden use and 1.4-in design storm *D* used for regulations.

A goal of reducing 90% of the runoff from directly connected roofs in the study area would require rain gardens that are about 20% of the roof areas, or a total area of slightly less than 200 ft<sup>2</sup> per house. This would also provide about 90% runoff reductions from the directly connected roofs during the 1.4-in regulatory design storm *D*. In most cases, this area would be made of two to four separate smaller rain gardens per house, depending on the locations of the roof gutter downspouts. With a peaked roof that all drains to one end of the house, two would be needed (each about 100 ft<sup>2</sup> of area), but for a more common peaked roof that drains to each corner separately, four separate smaller rain gardens would be needed (each about 50 ft<sup>2</sup> of area).

### **Curb-Cut Biofilters**

Biofilter performance is based on the characteristics of the flow entering the device, the infiltration rate into the native soil, the filtering capacity and infiltration rate of the engineered media fill if used, the amount of rock fill storage, the size of the device and the outlet structures for the device. Pollutant filtering by the engineered media (usually containing amendments) is based on the engineered media type and the particle size distribution of the inflowing water, or the user can directly enter the percent reduction from filtering that is directed by a regulatory agency. If the engineered media flow rate is lower than the flow rates entering the device, the engineered media will affect the device performance by forcing the excess water to bypass the device through surface discharges if the storage capacity above the engineered media is inadequate.

The device operation is modeled using the Modified Puls Storage-Indication method and is analyzed differently depending on whether a rock and engineered media layer is in the model. The model simulates the inflow and outflow hydrographs using a time interval selected by the user (typically 6 minutes), although this interval is reduced automatically by the program if the simulation approaches becoming unstable.

The complex triangular inflow hydrograph is divided into the selected time intervals, which are routed to the surface of the biofilter. The biofilter is evaluated in two basic sections: the aboveground section (or above the engineered media) and the belowground section (below the surface of the engineered media). If there is a rock and engineered media layer, the available surface outflow devices include broad (required) and sharp crested weirs, vertical stand pipe, evaporation/ET, and flow through the engineered media.

As water enters the device, all flow is routed to the belowground section of the device as long as the engineered media infiltration rate is greater than the inflowing water rate. As the inflow rate increases, the aboveground storage begins to fill once the inflow rate exceeds the engineered media infiltration rate. If the inflow rate is high enough and the excess runoff volume exceeds the available storage, the water begins to discharge from the device through the aboveground surface outflow devices. As water enters the belowground section of the device, it discharges through the native media and, as the bottom section fills, through the underdrain (if used). All water that flows through the underdrain is assumed to be filtered by the engineered media. The filtering performance changes based on the type of engineered media and varies by the particle size, which also affects the minimum effluent concentration. If the water level in the belowground section of the device reaches the top of the engineered media layer, infiltration from the surface layer into the belowground layer is not possible until the water level in the belowground section is below the top of the engineered media layer. If there are no rock and engineered media layers, flow into the native soil is considered to be an outflow: there is no belowground section, and all treatment by the device is assumed to be through volume loss by infiltration into the native soil.

Biofilters can be used as control devices in individual source areas or as a part of the drainage system. To model biofilters, the geometry and other characteristics of the biofilter are described, or of a typical biofilter if modeling a set of biofilters for, say, roofs or parking lot source areas. The number of biofilters to be modeled in the source area is also entered on the form. The model divides the total source area runoff volume by the number of biofilters in the source area, creates a complex triangular hydrograph for that representative flow fraction that is then routed through that biofilter. It then multiplies the resulting losses by the number of biofilters for the total source area.

### ***Biofilter Data Entry***

Figure 89 is the data entry form used for biofilters and related stormwater controls.

The screenshot shows the 'Biofiltration Control Device' software interface. It is divided into several sections:

- Drainage System Control Practice:** Includes 'Device Properties' for 'Biofilter Number 1' with fields for Top Area (400), Bottom Area (300), Total Depth (5.00), Typical Width (10.00), Native Soil Infiltration Rate (0.100), and various infiltration fractions. It also has checkboxes for 'Within Biofilter', 'Perforated', and 'Bottom Elevation'.
- Outlet Options:** 'Add Sharp Crested Weir' (Weir Length, Height from datum), 'Add Broad Crested Weir' (Weir crest length, Weir crest width, Height from datum), 'Add Vertical Stand Pipe' (Pipe diameter, Height above datum), and 'Add Surface Discharge Pipe' (Orifice Diameter, Invert elevation, Number of orifices).
- Evaporation and Evapotranspiration:** A table for monthly evaporation and evapotranspiration rates, and a 'Plant Types' table with columns 1-4 and rows for vegetation fraction, plant type (Prairie P), root depth, and ET crop adjustment factor.
- Soil Properties:** Fields for Soil porosity (0.390), Soil field moisture capacity (0.138), Permanent wilting point (0.045), and Supplemental irrigation used? (checkbox).
- Native Soil Infiltration Rate Selection:** Radio buttons for various soil types and their infiltration rates, plus a 'Rain Barrel/Cistern' option.
- Change Geometry:** Buttons for 'Copy Biofilter Data' and 'Paste Biofilter Data'.
- Biofilter Geometry Schematic:** A cross-sectional diagram showing a trapezoidal biofilter with a top width of 10.00', a bottom width of 3.00', and a total depth of 5.00'. It shows layers for 'Top of Engineered Media' (3.00' from bottom), 'Top of Rock Fill' (0.25' from media), and 'Bottom Elevation' (0.75' from rock fill).

Figure 89. Basis data entry screen for biofilters and bioinfiltration stormwater controls.

The bottom of the biofilter has a datum of zero. To describe the biofilter, the following information is entered.

### Device Geometry

- Top Area (square feet): Enter the top area of the biofilter
- Bottom Area (square feet): Enter the bottom area of the biofilter
- Total Depth (feet): Enter the depth of the biofilter.
- Typical Width (ft): If you intend to perform a cost analysis of the biofilter practices listed in the .mdb file, you must enter the typical biofilter width (ft) of a biofilter system you are modeling. This value is not used for a hydraulic or water quality analysis; it is relevant only for the cost analysis.
- Native Soil Infiltration Rate (in/hr): Enter the infiltration rate or select a typical infiltration rate based on soil type from the provided list in the lower left-hand corner of the window. The native soil infiltration rate value, based on a large number of tests performed by Pitt is supplied if you select the typical seepage rate provided by the model.
- Native Soil Infiltration Rate COV (Coefficient of Variation): If you want to consider the typical variabilities in the infiltration rates, select the “Use Random Number Generation to Account for Uncertainty in Infiltration Rate” checkbox and then accept or enter another seepage rate COV value in the cell below the native soil infiltration rate. This is optional and uses a Monte Carlo simulation




built into the model. If selected, the infiltration rates are randomly varied for each event based on a log-normal probability distribution of actual measured infiltration rate variabilities.

- Infiltration Rate Fraction - Bottom (0-1): Enter the seepage rate multiplier for bottom flow (from 0 to 1) to reduce the seepage rate through the bottom of the biofilter. This option can be useful if you want to evaluate the effects of clogging on the bottom of the device.
- Infiltration Rate Fraction - Side (0-1): Enter the seepage rate multiplier for side flow (from 0 to 1) to reduce the seepage rate through either the sides of the biofilter. This option can be useful if you want to evaluate the effects of clogging on the bottom of the device or ignore the benefits of seepage out of the sides of the device, as assumed by some regulatory agencies.
- Rock Filled Depth (ft): This is the depth of biofilter that is rock filled. This must be less than or equal to the biofilter depth, and may be zero if there is no rock fill. Water is assumed to flow through the rock storage layer very quickly.
- Rock Fill Porosity: Enter the fraction of rock fill that is voids as a value from zero to one. If you have both rock fill and engineered soil, the model calculates and uses the weighted average of the two porosity values to determine the benefits of this subsurface storage. If you are using an underdrain, a rock storage layer is usually required.
- Engineered Media Type. If the device has an engineered soil layer, the program enters an infiltration rate depending on the type of engineered media, based on extensive media tests in laboratory columns and in the field. Select the 'Media Data' button to enter media type information including the media porosity, infiltration rate, field moisture capacity and permanent wilting point.
- Engineered Media Infiltration Rate (in/hr): If you have selected a specific engineered media type, the program enters a measured infiltration rate for that media, or if you selected a user defined media type, you may enter your own engineered media infiltration rate.
- Engineered Media Depth (ft). This must be less than or equal to the biofilter depth, and may be zero if there is no engineered media fill.
- Engineered Media Porosity (0-1): This is the fraction of engineered media that is voids - enter the porosity of the engineered media as a value from zero to one. If you have both rock fill and engineered media, the model calculates and uses the weighted average of the two porosity values.
- Percent Solids Reduction Due to Engineered Media. If you want to enter a percent solids reduction value from engineered media if permitted to do so by the regulatory agency or because you have suitable data, select "User-Defined" as the engineered media type in the Detailed Soil Characteristics form. If you select any other engineered media type, the program calculates the percent reduction based on that media type.
- Inflow Hydrograph Peak Flow to Average Flow Ratio. This value is used to determine the shape of the complex triangular unit hydrograph that is routed through the device. A typical value of the peak to average flow ratio is 3.8, based on monitoring many urban areas (Pitt, et al. 2012). However, short duration events in small areas may have larger ratios and similarly, long duration events in large areas may have smaller ratios. WinDETPOND can evaluate any inflow hydrograph shape that you enter. In version 10, it is recommended that the option to use the hydrograph from upgradient areas and controls be used instead of resetting this value to 3.8.
- Number of Devices in the Source Area or Upstream Drainage System. The model divides the runoff volume by the number of biofilters in the source area or land use, creates a complex triangular hydrograph that it routes through that biofilter, and then multiplies the resulting losses by the number of biofilters to apply the results to the source area.

- Particle Size Distribution File. The particle size distribution of the particulates in the runoff affects the percent solids reduction of the engineered media layer. The program has pre-defined percent solids reductions for selected particle size distributions. If you have a user-defined engineered media type, then you do not need to enter a particle size distribution file. If you select the 'Route Hydrographs and Particle Sizes Between Control Devices' checkbox in Program Options/Default Model Options, the program uses the default particle size distribution file for all source areas. The particle size distribution entering the control device is modified by whatever practices are upstream of the control practice. If the practice is the most upstream practice, the default particle size distribution is used.
- Pipe or Box Storage is not activated.


Typical Kansas City curb-cut rain gardens along the street were assumed to be simple excavations 20 ft (6.1 m) long and 5 ft (1.5 m) wide in the terrace between the sidewalk and the street, but most of the curb-cut rain gardens installed in the test area are about 2 to 4 times this size. The following example calculations are still valid, as long as the *unit* rain gardens are 100 ft<sup>2</sup> of area and the actual components are sized accordingly. Their depth was limited to 1 ft (0.3 m) to decrease uneven steep slopes and other hazardous conditions. It is assumed that the subsoil would be loosened after the excavation, and a minimum amount of organic material would be added to the soil. There are less than 6 mi (9.6 km) of street side drainage systems in the 100 acre (40.5 ha) test watershed. Therefore, a maximum of 1,500 small street side rain gardens (150,000 ft<sup>2</sup> total rain garden area) was assumed to be possible in the area. However, a more reasonable maximum number would be 750 (75,000 ft<sup>2</sup> total rain garden area) because of the presence of large trees and other interferences.

Figure 90 is a plot of the percentage of the typical annual runoff amount that can be infiltrated by the curb-cut rain gardens on the basis of the number of units used and with no other controls in the area. With a maximum 1,500 units possible (total of 150,000 ft<sup>2</sup>, or 3.4% of the 100 acres being treated), up to 80% of the annual runoff can be infiltrated. With 400 units (total of 40,000 ft<sup>2</sup>, or less than 1% of the 100 acres being treated), 40% of the annual flows would be diverted from the combined sewers.



**Figure 90. Annual runoff volume reduction (%) for typical rain year (1990) for different numbers of simple curb-cut rain gardens (100 ft<sup>2</sup> each) per 100-acre watershed.**

Figure 91 shows the durations of flows at different rates for several different curb-cut rain garden applications. The maximum peak flow for the typical rain year is expected to be more than 25 ft<sup>3</sup> (708 L)/sec and less than 30 ft<sup>3</sup> (850 L)/sec for this area. The use of 600 rain gardens is likely to reduce the flow rates that occur for 0.1% of the annual hours (about 5 h/y to 10 h/y) to half the value if uncontrolled.




**Figure 91. Durations of flows (percentage of time) for different numbers of simple curb-cut rain gardens.**

## Use of Underdrains in Biofilters

The treatment of stormwater by biofilters is dependent on the hydraulic residence time in the device for some critical pollutants. The effective use of biofilters for controlling stormwater in combined sewer areas is also related to residence time because it is desired to retain the water before discharge to the drainage system to reduce the peak flows to the treatment plant. This section describes the results from a series of tests being conducted by Redahegn Sileshi, a Ph.D. student at UA, to determine the hydraulic characteristics of sand-based filter media (having a variety of particles sizes representing a range of median particle sizes and uniformity coefficients) during pilot-scale trench tests (Sileshi et al. 2012a, 2012b). The drainage rate in biofiltration devices is usually controlled using an underdrain that is restricted with a small orifice or other flow-moderating component. These frequently fail because the orifices are usually very small (less than 10 mm) and are prone to clogging. A series of tests are also being conducted using a newly developed foundation drain material (SmartDrain™), which offers promise as a low-flow control device with minimal clogging potential. A pilot-scale biofilter comprised of a trough 3 m long and having a cross section of 0.6 x 0.6 m is being used to test the variables affecting the drainage characteristics of the underdrain material (such as length, slope, hydraulic head, and type of sand media). Tests are also being conducted to determine the clogging potential of this drainage material. This report describes the initial tests that have investigated the basic hydraulic properties and the clogging potential of this drain material.

Figure 92 is an example showing the effects of a small bioretention facility and different underdrain options. Depending on the objectives (peak flow reduction, infiltration, or filtering of the water), different underdrain options can be selected. Sizing the controls can also be evaluated using the model based on both short-term and long-term rain records for the area.



**Figure 92. Initial design evaluation of alternative bioretention facility designs.**

A typical biofilter that is 1 m deep, 1.5 m wide and 5 m long would require about 8 hours to drain using the SmartDrain™ material as the underdrain. This is a substantial residence time in the media to optimize contaminant removal and provides significant retention of the stormwater before being discharged to a combined sewer system. In addition, this slow drainage time allows infiltration into the native underlying soil, with reduced short-circuiting to the underdrain.

The smart drain has many micro channels in an 8-in width, as shown in Figure 93. The micro channel inlet area composes over 20% of the active drainage surface of the belt/ribbon.




Figure 93. Close-up photograph of SmartDrain™ material showing the microchannels on the underside of the 8-in-wide strip.

The controlled tests investigated the drainage characteristics of the SmartDrain™ material under a range of typical biofilter conditions. A sand filter media purchased locally was used for the pilot-scale test setup to measure the hydraulic characteristics of the drainage material. The particle size distributions of the sand filter media, and the US Silica Sil-Co-Sil 250 ground silica material that is being used in the clogging tests, are shown in Figure 94.




Figure 94. Particle size distribution for medium-sized sand and SIL-CO-SIL250.



### **Underdrain Testing Procedure**

The experimental apparatus for the pilot-scale biofilter tests consisted of a fiberglass trough 3 m long having a 0.6 x 0.6 m cross section. The outlet end of the SmartDrain™ was inserted into a slit cut in the PVC collection pipe and secured with screws and silica sealant (Figures 95 and 96); the sealant is used only on the top smooth surface of the SmartDrain™ material and not on the bottom, which would clog the channels. The SmartDrain™ material is installed with the micro channels on the underside of the strip between two layers of coarse sand, each about 4 in thick. The SmartDrain™ directs the collected water into the PVC pipe, with a several inch drop to enhance siphoning action. The PVC collector pipe used was 2 in (5 cm) in diameter and was placed 1 in (2.5 cm) above the trough bottom. A hole was drilled through the side of the trough for an extension of this pipe outside the trough to allow sampling of the drainage water and to measure the flow rates. During the tests, the trough was initially filled with water to a maximum head of 22 in (56 cm) above the center of the pipe. A hydraulic jack and blocks were used to change the slope of the tank. Different lengths of the SmartDrain™ were tested for a range of slopes. Each test was also repeated several times, and regression analyses were conducted to obtain equation coefficients for the stage versus head relationships for these different conditions.



Figure 95. SmartDrain™ installation procedures in the trough.

The second testing phase examined the clogging potential of the SmartDrain™. Sil-Co-Sil 250, having a median particle size of about 45 µm, was mixed with the test water for the clogging tests. Figure 95 shows the tall, lined box that was used to verify the head versus discharge relationships for deeper water and was used for the clogging tests. This Formica-lined plywood box is 3 ft (90 cm) by 2.8 ft (85 cm) in cross-sectional area and 4 ft (120 cm) tall. The box was filled with tap water to produce a maximum head of 4 ft (120 cm) above the filter, and Sil-Co-Sil 250 was added to the water to provide a concentration of 1 g/L (1,000 mg/L). The box was then drained and flow measurements taken. These clogging tests were continually conducted to result in a high accumulation of the test particulates to measure degradation in performance with increasing loading.



Figure 96. SmartDrain™ installation for the clogging test in the tall box.

### ***Effects of Slope, Lengths, and Sediment Load on the Drainage Characteristics of the SmartDrain™***

Five replicates for each of five different lengths of the SmartDrain™ [9.4 ft (2.9 m), 7.1 ft (2.2 m), 5.1 ft (1.6 m), 3.1 ft (0.95 m) and 1.1 ft (0.34 m)] were tested. Two different lengths of the SmartDrain™ (9.4 and 7.1 ft) were tested for five different slopes (0, 3, 6, 9, and 12%) and the remaining three lengths of the SmartDrain™ (5.1, 3.1 and 1.1 ft) were tested for three different slopes (0, 3, and 12%). Flow rate measurements were manually obtained at 25- to 30-minute intervals until the water was completely drained from the pilot-scale biofilters. The flows were measured by timing how long it took to fill a 0.5-L graduated cylinder. Linear regression analyses were used to determine the intercept and slope terms of the head versus discharge relationships. The p values of the estimated coefficients were used to determine if the coefficients were significant ( $p < 0.05$ ). All five lengths tested for the given slopes showed statistically significant slope coefficients ( $p < 0.05$ ), while many of the intercept terms were not found to be significant. Stage-discharge relationships (Figure 98) reflects that the slope of the SmartDrain™ has no significant effect on the effluent flow rates.



Reductions in the outflow rate relationships of the filter media were not observed during the clogging tests (having a total load of more than 30 kg/m<sup>2</sup> onto the filter area). We would normally expect *complete* clogging (to less than about 1 m/day flow rates) after many repeated tests on the same media when a resulting total surface loading of about 10 to 20 kg/m<sup>2</sup> of sediment has been loaded to the filter area.

Influent and effluent turbidity measurements were also taken at 25- to 30-minute intervals at the same time as the flow rate measurements until the water completely drained from the tank. The turbidity (NTUs) values decreased with decreasing head of water in the tank (and effluent flow rate). The initial turbidity levels were about 1,000 NTU in the tank at the beginning of the test. The initial effluent water turbidity values were similar at the beginning of the tests, but significantly decreased as the tests progressed and with flow rates decreases.

Algal fouling of the SmartDrain<sup>TM</sup> material were also examined by allowing nutrient loaded test water to stagnate in the test tank for extended periods and then conducting flow rate measurements. The pilot-scale biofilter was used for these tests to verify the stage-discharge relationships under adverse algal conditions. During these biofouling tests, the tank was filled with tap water to produce a maximum head of 4 ft (1.2 m). The tank was left open to the sun for several weeks to promote algae growth. Two different algal species collected from a pond on the UA campus and from the Black Warrior River in Tuscaloosa, Alabama, were added to the test water. Miracle-Gro 12-4-8, an all-purpose liquid fertilizer, was also added to increase the algae growth rate in the biofilter tank (Figure 97). Seven biofouling trials were conducted at various algal growth stages in the device, with several weeks between each drainage test. The ponded depth of the test water in the tank for the first five trials was 4 ft (1.2 m), and was reduced to 1.4 ft (0.41 m) for the last two trials to encourage algal growths near the filter sand surface and along the drainage ribbon. At the end of each biofouling test period, the test water was drained, resulting in seven stage-discharge relationships.



**Figure 97. Algae in the test tank during the biofouling tests.**

Figure 98 summarizes the results of different SmartDrain™ tests under the test conditions. The SmartDrain™ functions similar to a very small orifice of 0.10 to 0.25 in. (2.5 to 6 mm) for all of the tests.




Figure 98. Stage-discharge relationships for various test conditions for the SmartDrain™.


### **Production Functions of Curb-Cut Biofilters Using WinSLAMM**

WinSLAMM was used with the calibration files prepared for the Kansas City demonstration project to examine alternative biofilter and bioinfiltration device designs for the residential test (pilot) area. Four infiltration rates for the native subsurface soil were examined: 0.2, 0.5, 1.0, and 2.5 in/hr (corresponding to sandy silt loam, loam, sandy loam, and loamy sand, respectively). The lowest rate (0.2 in/hr) was the assumed early infiltration rate used by the design consultants for the original designs. Site surface soil measurements in the test watershed indicated 1 in/hr, or greater, infiltration rates for rains lasting 2 hours or less. Site measurements of the biofilters during storms indicated infiltration rates of the media and device at 1.8 in/hr, and modeling indicated likely subsurface rates of about 1 in/hr to result in the observed performance during the rains (almost complete infiltration with very little overflow or subsurface underdrain discharges). Other features investigated included using alternative underdrain conditions (no underdrain, conventional 3-in perforated pipe underdrain, or a SmartDrain™), and with gravel storage for the underdrains and with and without the gravel for no underdrain.

The detailed summaries of the calculations are in Appendix E, and plots and shorter summaries are in this section. The main objectives were to identify how these alternative designs affected performance. Performance was indicated for various sizes of the devices (expressed as a percentage of the test area residential land use), ranging from 0.5 % of the drainage area as the biofilter size to maximum sizes that resulted in 100% runoff infiltration. The main performance measures summarized here are percentage of the annual flows infiltrated (or lost because of ET), number of events having 3 days or more of standing water (the typical stormwater criteria to prevent mosquito problems), the percentage of the annual flows being filtered by the media and then discharged to the combined sewer (and subjected to about a 4-hr delay because of the residence time in the media, benefiting the resultant peak flow rate in the combined sewer), and the potential useful life before clogging can occur. WinSLAMM calculates many other attributes for these devices, but these were selected as the most relevant for this project.

### Descriptions of Alternatives Examined

The model used locally measured rainfall starting in September 2008, through October 2012 to correspond to the time when sewer flow monitoring was conducted for this project. During this 4-year period, the average annual rain was about 33 in, and about 46 rains per year occurred (from 0.11 to 3.98 in. each). Figure 99 shows the pattern of these rains with time.



**Figure 99. September 2, 2008, to October 12, 2012, rains monitored in the Kansas City GI test area during the demonstration project monitoring period.**

Figures 100 through 104 are screenshots showing the four basic setups corresponding to the underdrain conditions for the various biofilters installed. The areas of the biofilter devices and the subsurface infiltration rates were changed for each tested condition. The top area was calculated according to the percentage of the residential drainage area (a unit acre was evaluated). The bottom areas were half of the top areas. The depths of the devices were 2.5 ft if no gravel storage was used, or 5 ft with gravel storage. The media layer was 1.5 ft thick, and its characteristics, shown below were from the analyzed site media used. The media infiltration rate was 1.8 in/hr with a porosity of 0.43. Gravel storage was 2.5 ft thick and had a porosity of 0.4. The ET monthly values are described in another section of this report and were obtained from the closest complete ET monitoring station. The broad crested weir provided a controlled surface discharge location, resulting in about 9 in. of surface pond storage before the overflow. The underdrains examined included a conventional 3-in. perforated pipe. The SmartDrain™ underdrain (with an equivalent orifice of 0.25 in.) was also placed at the same depth. The underdrains were placed 2 ft off the biofilter bottom to provide substantial storage during larger or intense rains.

Figure 100. Bioinfiltration device, no underdrain, and no gravel storage.

Soil Type Texture	Saturation Water Content % (Porosity)	Field Capacity (Percent)	Permanent Wilting Point (Percent)	Infiltration Rate (in/hr)	Fraction of Soil Type Texture in Engineered Soil (0-1)
<input checked="" type="checkbox"/> User-Defined Soil Type	43.4	21.8	4.6	1.800	1.000
Gravel	32	4	0	40	0.000
Sands	38	8	2.5	13	0.000
Loamy Sands	39	13.5	4.5	2.5	0.000
Sandy Loams	40	19.5	6.5	1	0.000
Fine Sandy Loams	42	26.5	10.5	0.5	0.000
Loams & Silt Loams	43	34	14	0.15	0.000
Clay Loams/Silty Clay Loams	50	34.5	17	0.1	0.000
Silty Clays & Clays	55	33.5	18	0.015	0.000
Peat as Amendment	78	59	5	3	0.000
Compost as Amendment	61	55	5	3	0.000
Composite Soil Mixture Properties	43.4	21.8	4.6	1.800	1.000

Apply Soil Mixture Values as a User Defined Soil Mixture  
 Apply Porosity  
 Apply Field Capacity  
 Apply Wilting Point  
 Apply Infiltration Rate  
 Apply All Values

Figure 101. Media characteristics used in the test (pilot) biofilters and bioinfiltration devices.






Figure 102. Bioinfiltration device with no underdrain but with gravel storage.





Figure 103. Biofilter with SmartDrain™ underdrain with gravel storage.




**Figure 104. Biofilter with conventional 3-in. underdrain and gravel storage.**


Figures 105 through 109 are the production function plots for the conditions examined, followed by summary Table 56. The first four plots compare the no underdrain condition, with and without gravel storage, for the three subsurface native soil infiltration rates. As noted, the use of the gravel storage is important for only the low infiltration rate conditions: once the infiltration rate is about 1 in/hr or larger, this additional storage is not needed, as far as benefiting the long-term infiltration performance.

The next four plots show the effects of the underdrains for the infiltration rates. For the low infiltration rates, using underdrains degrades the performance of the biofilters because the underdrains discharge subsurface ponding water before it can completely infiltrate. The use of a slow underdrain (as indicated here by the SmartDrain™), results in an intermediate effect on infiltration and with decreasing durations of surface ponding. As with the gravel storage, underdrains have very little effect on performance when the native subsurface native infiltration rate is about 1 in/hr or greater.







0.2 in/hr infiltr. rate



0.5 in/hr infiltr. rate



1.0 in/hr infiltr. rate



2.5 in/hr infiltr. rate

Figure 105. No underdrain alternatives, with varying native soil infiltration rates and with and without gravel storage.




Figure 106. Use of underdrains in soils having 0.2 in/hr native subsurface infiltration rates.




Figure 107. Use of underdrains in soils having 0.5 in/hr native subsurface infiltration rates.






Figure 108. Use of underdrains in soils having 1.0 in/hr native subsurface infiltration rates.



**Figure 109. Use of underdrains in soils having 2.5 in/hr native subsurface infiltration rates.**

Figure 110 is a plot indicating the clogging potential for the biofilters. Biofilter media is likely to fail resulting in very low infiltration rates with rapid and excessive particulate solids loadings. Generally, particulate loads of between 10 and 25 kg/m<sup>2</sup> could be indicative of significantly reduced infiltration. With a planted biofilter in good condition, and if this accumulative load occurs over at least 10 years, the biofilter is likely to be able to incorporate this additional material into the soil, and the plants can help retain the infiltration rate at a desired level (but with reduced surface storage volume). However, if this load occurs within just a few years, it is likely to overwhelm the system, resulting in premature clogging. This is more of a problem for small biofilters receiving runoff having high particulate solids concentrations, such as parking lots where space is limited for larger biofilters. Pretreatment using grass filters or swales can reduce these problems. For this study area, if the biofilters are at least 1 to 3% of the residential drainage area, the particulate loading is not likely to be a problem.



**Figure 110. Clogging potential for biofilters in test (pilot) area.**

Table 56 summarizes some of the features shown in Appendix E and from the above plots. Performance levels of 75, 90, and 95% reductions of surface runoff are indicated for the four infiltration rates and four underdrain options. The biofilters and bioinfiltration devices in the test (pilot) area are about 1.5 to 2% of the residential drainage areas. For the 1 in/hr subsurface infiltration rate, these sizes of the biofilters are expected to provide about a 90% reduction in the annual flows for the areas treated, with very little overflows. The SmartDrain<sup>TM</sup> installation is expected to have only about 1% of the annual flows being captured by this underdrain. These calculated conditions are all similar to the observed conditions during the brief monitoring period.

**Table 56. Summary of performance of biofilter size, use of underdrains, and subsurface soil infiltration rates on desired performance objectives**

Native soil subsurface infiltration rate (in/hr)	Annual flow removal goal (%)	No underdrain, no gravel storage				No underdrain, with gravel storage			
		Size as a % of residential drainage area	Days ponding $\geq 3$ days per 4 yrs	% of flows with extended retention time (4 hrs)	Potential years to clogging (10 to 25 kg/m <sup>2</sup> )	Size as a % of residential drainage area	Days ponding $\geq 3$ days per 4 yrs	% of flows with extended retention time (4 hrs)	Potential years to clogging (10 to 25 kg/m <sup>2</sup> )
0.2	75%	2.4%	12	0%	10 to 25	1.5%	10	0%	7 to 14
	90%	4.3%	6	0%	15 to 35	3%	5	0%	12 to 30
	95%	6%	2	0%	20 to 50	4.3%	2	0%	15 to 35
0.5	75%	1.6%	1	0%	6 to 16	1.2%	1	0%	5 to 12
	90%	2.7%	1	0%	9 to 25	2%	1	0%	8 to 19
	95%	3.6%	1	0%	14 to 35	3%	1	0%	10 to 25
1.0	75%	0.9%	1	0%	4 to 11	0.9%	1	0%	4 to 11
	90%	1.7%	1	0%	7 to 17	1.7%	1	0%	7 to 17
	95%	2.3%	1	0%	10 to 25	2.3%	1	0%	10 to 25
2.5	75%	0.7%	1	0%	3 to 8	0.7%	1	0%	3 to 8
	90%	1.3%	1	0%	5 to 15	1.3%	1	0%	5 to 15
	95%	2%	1	0%	7 to 17	2%	1	0%	7 to 17

**Table 56. Summary of performance of biofilter size, use of underdrains, and subsurface soil infiltration rates on desired performance objectives (cont.)**

Native soil subsurface infiltration rate (in/hr)	Annual flow removal goal (%)	Size as a % of residential drainage area	SmartDrain			Conventional 3-in. drain pipe			
			Days ponding ≥ 3 days per 4 yrs	% of flows with extended retention time (4 hrs)	Potential years to clogging (10 to 25 kg/m <sup>2</sup> )	Days ponding ≥ 3 days per 4 yrs	% of flows with extended retention time (4 hrs)	Potential years to clogging (10 to 25 kg/m <sup>2</sup> )	
0.2	75%	2.6%	0	10%	9 to 22	4.2%	0	25%	13 to 32
	90%	4.5%	0	6%	15 to 40	7.8%	0	7%	26 to 66
	95%	6.5%	0	2%	25 to 60	10%	0	4%	35 to 85
0.5	75%	1.4%	1	7%	6 to 14	2.2%	1	17%	8 to 20
	90%	2.4%	1	4%	9 to 22	4.2%	1	10%	15 to 35
	95%	3%	1	3%	15 to 35	6%	1	5%	25 to 60
1.0	75%	0.8%	1	1%	4 to 9	0.8%	1	2%	4 to 9
	90%	2%	1	1%	7 to 16	2%	1	3%	7 to 16
	95%	2.3%	1	0.5%	9 to 24	2.3%	1	2%	9 to 24
2.5	75%	0.6%	1	0%	3 to 7	0.6%	1	0%	3 to 7
	90%	1.4%	1	0%	4 to 12	1.4%	1	0%	4 to 12
	95%	2%	1	0%	7 to 17	2%	1	0%	7 to 17

## Porous Pavement

The WinSLAMM porous pavement control in version 10 has full routing calculations associated with subsurface pond storage, and it allows runoff from adjacent paved areas that do not have porous pavement. The *outlet* options for porous pavements include subgrade seepage and an optional underdrain, which is modeled as an orifice. The porous pavement control device has a surface seepage rate that limits the amount of runoff that can enter the storage system. The seepage rate is usually much larger than the rain intensity, so this would be unusual, except if it is significantly reduced by clogging or if substantial runoff occurs from adjacent paved areas. This surface seepage rate is reduced to account for clogging with time, while the surface seepage rate can be partially restored with cleaning at a stated cleaning frequency. The runoff volume reaching the porous pavement surface is equal to the rainfall volume directly falling on the porous pavement, plus runoff volume from any runoff from the adjacent paved areas. The porous pavement surface can be paver blocks, porous concrete, porous asphalt, or any other porous surface, including reinforced turf. Porous pavements are usually installed over a subsurface storage layer that can dramatically increase the infiltration performance of the device, while reinforced turf does not have subsurface storage.

Porous pavements are typically used at paved parking and storage areas, paved playgrounds, paved driveways, or paved walkways. They should be used in relatively clean areas (walkways or driveways or other surfaces that receive little traffic, for example), to minimize groundwater contamination potential and premature clogging and failure. Porous pavements direct the infiltrating water to subsurface soil layers, usually at a depth where the soils have little organic matter that tend to sorb pollutants. Salts used for ice control in northern areas are also problematic when considering infiltrating stormwater. Consider biofiltration devices to infiltrate water from more contaminated sites because they can use amended soils to help trap contaminants before infiltration, or use other appropriate pre-treatment before infiltration, and are easier to restore. No common pretreatment device is suitable for removing salts, however, so minimal use of deicing chemicals is the preferred control option.

It is necessary to describe the geometry and other characteristics of a typical porous pavement surface, as shown in Figure 111. The model computes the runoff volume, equal to the rainfall volume plus any runoff, and then creates a complex triangular hydrograph (the flow duration equals the rain duration) that it routes through that porous pavement system.



**Poros Pavement Control Device**

**First Source Area Control Practice**      **Poros Pavement Number 1**

**Land Use: Residential 7**

**Source Area: Sidewalks 1**

**Total Area: 0.007**

**Poros pavement area (acres):**

**Inflow Hydrograph Peak to Average Flow Ratio**

**Pavement Geometry and Properties**

1 - Pavement Thickness (in)	3.0
Pavement Porosity (>0 and <1)	0.40
2 - Aggregate Bedding Thickness (in)	3.0
Aggregate Bedding Porosity (>0 and <1)	0.40
3 - Aggregate Base Reservoir Thickness (in)	12.0
Aggregate Base Reservoir Porosity (>0 and <1)	0.40

**Outlet/Discharge Options**

Perforated Pipe Underdrain Diameter, if used (inches)	3.00
4 - Perforated Pipe Underdrain Outlet Invert Elevation (inches above Datum)	8.0
Number of Perforated Pipe Underdrains (<250)	1
Subgrade Seepage Rate (in/hr) - select below or enter	1.000
Use Random Number Generation to Account for Uncertainty in Seepage Rate	<input type="checkbox"/>
Subgrade Seepage Rate COV	

**Select Subgrade Seepage Rate**

Sand - 8 in/hr       Clay loam - 0.1 in/hr  
 Loamy sand - 2.5 in/hr       Silty clay loam - 0.05 in/hr  
 Sandy loam - 1.0 in/hr       Sandy clay - 0.05 in/hr  
 Loam - 0.5 in/hr       Silty clay - 0.04 in/hr  
 Silt loam - 0.3 in/hr       Clay - 0.02 in/hr  
 Sandy silt loam - 0.2 in/hr

**Surface Pavement Layer Infiltration Rate Data**

Initial Infiltration Rate (in/hr)	40.00
Percent of Original Infiltration Rate Upon Cleaning (0-100)	75.0
Percent of Infiltration Rate After 3 Years (0-100)	
Percent of Infiltration Rate After 5 Years (0-100)	
Time Period Until Complete Clogging Occurs (yrs)	
Surface Clogging Load (lb/sf)	5.00

**Restorative Cleaning Frequency**

Never Cleaned  
 Three Times per Year  
 Semi-Annually  
 Annually  
 Every Two Years  
 Every Three Years  
 Every Four Years  
 Every Five Years  
 Every Seven Years  
 Every Ten Years

Control Practice #: 8    Land Use #: 7    Source Area #: 31

**Figure 111. Poros pavement main input screen.**

Table 57 summarizes the calculated performance of porous pavements located at paved parking/storage areas. The given underlying soil is a loam soil. A conventional 3-in. perforated pipe underdrain was also used. As indicated, even the smallest area examined (25% of the area as porous pavement) had very good runoff volume reductions for this example. The porous pavement was cleaned every year, restoring much of the lost surface infiltration rate capacity in this example. If the area was not cleaned, clogging would be expected in about 8 years, based on field experience.

**Table 57. Poros pavement performance (paved parking and storage area; loam soil; 3-in underdrains placed 20 ft apart)**

Poros pvt as a % of paved parking area	Rv	Volume reduction (%)	Expected habitat conditions	TSS (mg/L)	Solids discharged (lbs/yr)	TP (mg/L)	TP load (lbs)	Cu (µg/L)	Cu load (lbs)
none	0.75	n/a	Poor	130	812	0.21	13	21	1.3
25%	0.06	92%	Good	130	60	0.21	0.98	21	0.098
50%	0.05	93%	Good	130	58	0.32	0.94	12	0.093
100%	0.05	93%	Good	130	58	0.21	0.94	21	0.093

## Grass Filters

Grass filters have broad, shallow flows. WinSLAMM calculations for grass filters are based on extensive pilot-scale and field measurements of grass swales and filters conducted for the Alabama Department of Transportation. This model determines the flow conditions for every calculation increment, including flow velocity and depth. Special shallow Manning's n values are used according to shallow sheetflow measurements. Sediment transport is calculated for each narrow particle size range using their sedimentation rate, depth of flow, and length of flow. Scour is also considered, along with equilibrium concentrations. The pilot-scale tests were confirmed during full-scale tests during actual rains.

The grass filter and grass swale controls calculate pollutant and runoff volume reductions. The model determines the runoff volume reduction by calculating the infiltration loss for each time step. The particulate reduction is based on the settling frequency of the particles entering the grassed area and the height of the grass relative to the flow depth. The grass "filters" the runoff using the settling frequency and the length of the flow path. The algorithms used to determine the Manning's n values were developed from the master's thesis by Jason Kirby Kirby, et al. 2005) as part of a WERF-supported research project (Johnson, et al. 2003). The particle trapping algorithms were based on the master's thesis research conducted by Yukio Nara (Nara, et al. 2006), supported by the University Transportation Center for Alabama (Nara and Pitt 2005)..

Runoff volume is reduced by the dynamic infiltration rate of the swales for each 6-minute time step of the hydrograph. The flow and the geometry are used to determine Manning's n to iteratively determine the depth of flow in the swale for each time step, using traditional VR-n curves that were extended by Kirby (Kirby, et al. 2005) to address the smaller flows found in roadside grass swales and filters. Using the calculated depth of flow for each time increment, the model calculates the wetted perimeter (using the swale cross-sectional shape), which is then multiplied by the total flow length to determine the area used to infiltrate the runoff. Details for these calculations are available by selecting the "Hydraulics Detailed Output File" checkbox from the "Detailed Output Options" listing under "Program Options." The event-by-event summary detailed output is available by selecting the "Hydraulics and Concentration by Event" checkbox from the Detailed Output Options listing. These comma-separated tabular files are created when the model is executed and can be reviewed using a spreadsheet after importing the files.

Figure 112 is the WinSLAMM basic input screen used for grass filters. Table 58 summarizes the performance of the grass filters for controlling the runoff from 2 acres of impervious areas. As the grass filters become steep, they lose some of their performance because of the faster flowing has a greater equilibrium capacity associated with its carry capacity and the faster flowing water has reduced effective infiltration rates compared to ponded water. Version 10 uses a direct calculation of the hydraulics for grass filter strips as for grass swales, but with modified turbulent induced length restrictions. An upcoming model release will use Muskingum channel routing to more effectively calculate the flowing water conditions in the filters (and swales).

Figure 112. Grass filter strip form in Version 10.

Table 58. Grass filter performance for different soils and slopes

Description	Rv	% runoff volume reduction	TSS (mg/L)	Solids yield (lbs/yr)	% solids yield reduction	Peak runoff rate (cfs)	% peak runoff rate reduction	TP (mg/L)	TP load (lbs)	Cu (µg/L)	Cu load (lbs)
Base conditions, no controls	0.55		100	1,040		4.6		0.28	29	17	1.7
Grass filter 0.5% slope	0.17	69%	91	300	71%	2.6	43%	0.27	8.7	16	0.52
Grass filter 2 to 25% slopes	0.22	60%	90	376	64%	3.5	24%	0.26	11	16	0.67

## Grass Swales

Grass swales are evaluated using the same general process as described previously for grass filters. As summarized, these procedures are based on extensive laboratory and field tests and calculate swale performance through infiltration mechanisms and sedimentation of many discrete particles sizes. The data entry form is shown in Figure 113. Table 59 summarizes the performance of a swale for two soil

conditions. As expected, the swale water volume and pollutant reduction performance is better for the loam soil than for the silty soil.

Figure 113. Grass swale input screen.

Table 59. Grass swale performance

Descrption	Rv	% runoff volume reduc.	Expected habitat conditions	TSS (mg/L)	solids yield (lbs/yr)	% solids yield reduc.	peak runoff rate (cfs)	% peak runoff rate reduc.	TP (mg/L)	TP load (lbs)	Cu (µg/L)	Cu load (lbs)
base conditions, no controls	0.55		Poor	100	1,040		4.6		0.28	29	17	1.7
silty soil	0.33	40%	Poor	86	535	92%	4.4	4%	0.25	16	16	0.98
loam soil	0.16	71%	Fair	87	263	92%	2.9	37%	0.26	7.8	16	0.47

## Cisterns and Water Storage Tanks


This section describes a method to evaluate or size water storage tanks needed to optimize the beneficial uses of stormwater. Much of this material was previously summarized in the recent WERF report on nonpotable beneficial uses of stormwater (Pitt, et al. 2011b). Irrigation of land on the homeowner's property was considered the beneficial use of most interest. Production function curves were prepared showing the relationship between water tank size and roof runoff beneficial use for the Kansas City study area.

### ***Calculating the Benefits of Rainwater Harvesting Systems***

Benefits associated with stormwater use for irrigation and other on-site uses can be calculated using site-specific information. Specifically, source area characteristics describing where the flows will originate and how the water will be used, are needed. In the most direct case, this information is used in conjunction with the local rainfall information and storage tank sizes to determine how much of the water needs can be satisfied with the stormwater, and how the stormwater discharges can be reduced. The following section describes how WinSLAMM can be used to calculate production functions that can be used to size storage water tanks to maximize irrigation use for residential locations in Kansas City, Missouri.

### ***Regional Rainfall and Runoff Distributions Affecting Roof Runoff Harvesting***

The model can use any length of rainfall record as determined by the user, from single rainfall events to several decades of rains. The rainfall file used in these calculations for Kansas City were developed from hourly data obtained from EarthInfo CD ROMs, using the 27 years from 1972 through 1999, as shown in Figure 114. This period contains 2,537 rains, with an average depth of 0.40 in. and a maximum of 6.19 in.



**Figure 114. Long-term rain depths for individual Kansas City, Missouri, rains (1972–1999).**

Figure 115 shows that the regional stormwater runoff is heavily influenced by the small to intermediate rains (data for the region shown for St. Louis, Missouri). Almost all of the runoff is associated with rains between about 0.3 to 2 in., the events for which WinSLAMM is optimized. The rare drainage design events generally comprise a very small portion of the typical year's runoff. The 1.4-in. event used in Kansas City for the original sizing of distributed storage systems is close to the rain depth associated with the median runoff depth.




Figure 115. St. Louis, Missouri, rain and runoff distributions (1984–1992 rains).

The land development characteristics and the evaluation of flow and pollutant sources in the area determine the maximum effectiveness of different types of controls. The land survey found that most of the homes in the test watershed already have disconnected roofs (85% of all roof areas) and that the total roof areas compose about 13% of the total area. The land survey also found that about 65% of the area is landscaped, with most being in turf grass in poor to good condition. This information was used in conjunction with regional ET data to calculate the amount of supplemental irrigation needed to meet the ET requirements of typical turf grass, considering the long-term rainfall patterns. Most of the supplemental irrigation would be needed in July and August, whereas excess rainfall occurs in October through December (compared to ET requirements during these relatively dormant months). Soil infiltration monitoring in the area, along with soil profile surveys, has indicated relatively poorly draining soil in the test area for the larger rains. Surface infiltration rates during several-hour rains can have infiltration rates of about 1 in/hr or greater, but these rates continue to decrease with increasing rain depths. For conservative modeling calculations, a soil infiltration rate of 0.2 in/hr was used.

The expected major sources of runoff from the test area vary for different rain depth categories. Directly connected impervious areas are the major runoff sources only for rains that are less than about 0.25 in. The large landscaped areas contribute about half of the runoff for rains larger than about 0.5 in. The directly connected roofs, which make up only about 2% of the study area, contribute about 6% of the total annual flows. The disconnected roofs, which compose about 11 percent of the area, contribute about 7% of the total flows. If all roofs were directly connected, they would compose about 31 percent of the annual total runoff flows, most of which could be eliminated through the use of cisterns/water tanks and irrigation.

Rain barrel/water cistern effectiveness is related to the need for supplemental irrigation and how that matches the rains for each season. The continuous simulations used a typical one-year rain series and average monthly ET values for varying amounts of roof runoff storage. One 35-gallon rain barrel is expected to reduce the total annual directly connected roof runoff by about 24%, if the water use could be closely regulated to match the irrigation requirements, such as with an automated irrigation system with soil moisture sensors (not likely to be used in conjunction with a few rain barrels, but more likely with a

large tank than can be pressurized). If four rain barrels were used (such as one at each corner of a house receiving runoff from separate roof downspouts), the total annual roof runoff volume reductions from the roofs could be as high as about 40%. Larger storage quantities result in increased beneficial use but likely require larger water tanks instead of large numbers of rain barrels. Water use from one water tank is also easier to control through soil moisture sensors and can be integrated with landscaping irrigation systems for almost automatic operation. A small water storage tank about 5 ft in diameter and 6 ft high is expected to result in about 75% total annual runoff reductions from directly connected roofs; a larger, 10-ft diameter and 6-ft tall tank could approach complete roof runoff control for this area. The 5-ft diameter tank is also expected to provide almost complete control of runoff from the regulatory design storm *D*.

The use of rain barrels and rain gardens together at a home is more robust than using either method alone: the rain barrels would overflow into the rain gardens, so their irrigation use is not quite as critical. In order to obtain reductions of about 90% in the total annual roof runoff, it is necessary to have at least one rain garden per house, unless the number of rain barrels exceeds about 25 (or 1 small water tank) per house.

Simple disconnections of the currently directly connected roofs can provide significant reductions in the annual flows from the roofs for low cost. A reduction of about 80% is expected in the total flows with disconnections, even with the site's clayey soils, with most occurring during small rains, and the benefits decreasing as the rains increase in depth. This flow volume reduction is enhanced because of the relatively small roof areas and large landscaped areas, which provide long flow paths. With steep slopes and poor grass, this reduction will be less.

Caution is needed when comparing the amount of site runoff storage provided by these upland controls to the total storage goals to meet the objectives of the CSO control program (288,000 gallons storage required). For example, storage provided at directly connected roofs need to be discounted by factor of 1.3 to 1.4 because not all of the storage is available during all rains, and their drainage is controlled by low infiltration rates through the native soils, compared to flow controls directly connected to the combined sewers. In contrast, curb-cut biofilters have access to almost all the flows in the area, so their storage volumes are more effectively used. More significantly, if storage was provided at roofs that are already disconnected, their storage volumes would need to be discounted by about 4.5 times when compared to the total site storage goals because of the existing infiltration occurring with the disconnected roof runoff.

### **Water Harvesting Potential in Kansas City**

The water harvesting potential for water tank use was calculated on the basis of supplemental irrigation requirements for the basic landscaped areas. The irrigation needs were determined to be the amount of water needed to satisfy the ET requirements of typical turf grasses, after the normal rainfall (a conservative calculation because only a portion of the rainfall contributes to soil moisture).

Table 60 summarizes the monthly average rainfall for the 1973 through 1999 period at the Kansas City airport, a 26-year continuous rain record. The average total annual rainfall is typically about 37.5 in., with most falling in the spring to early fall. A much smaller fraction of the annual rain occurs in December through February.

**Table 60. 1973 through 1999 Kansas City Airport monthly rain depth totals (inches)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Average	1.13	1.24	2.54	3.48	5.41	4.27	4.15	3.63	4.63	3.32	2.08	1.60	37.49
COV	0.68	0.57	0.66	0.61	0.54	0.48	0.85	0.67	0.75	0.81	0.59	0.83	0.25
Minimum	0.02	0.20	0.32	0.34	1.18	1.73	0.25	0.65	0.57	0.00	0.00	0.00	21.60
Maximum	2.81	2.72	9.08	8.43	12.41	8.67	15.47	9.58	11.11	10.16	5.12	5.42	55.26



The total landscaped area in the 100-acre residential land use area is 65.1 acres, and with 576 homes, each has about 4,925 ft<sup>2</sup> of landscaped area that might be irrigated.

Tables 61 and 62 along with Figures 116 through 118 show the monthly ET requirements of typical turf grasses for a monitoring station near Kansas City (Ottawa, Kansas, at a University of Kansas field station). The total annual ET is about 52 in. a year, and the annual total rainfall is about 37 in. a year, resulting in a rainfall deficit of about 15 in. per year.

**Table 61. Monthly irrigation requirements**

	In/day ET*	ET (in/month)	Rainfall (in/month)	Irrigation deficit (in/month)	Irrigation deficit (gal/day/house)
Jan	0.05	1.55	1.13	0.42	42
Feb	0.10	2.83	1.24	1.59	172
Mar	0.10	3.10	2.54	0.56	55
Apr	0.15	4.50	3.48	1.02	104
May	0.20	6.20	5.41	0.79	78
Jun	0.20	6.00	4.27	1.73	177
Jul	0.25	7.75	4.15	3.60	357
Aug	0.25	7.75	3.63	4.12	408
Sep	0.20	6.00	4.63	1.37	140
Oct	0.10	3.10	3.32	excess rain	0
Nov	0.05	1.50	2.08	excess rain	0
Dec	0.05	1.55	1.60	excess rain	0

\* These ET values are for eastern Kansas (Ottawa, Kansas) and are for typical turf grasses.

**Table 62. Monthly irrigation per household**

Month	Irrigation needs per month (gal/house)	Irrigation needs per month (ft <sup>3</sup> /house)	Irrigation needs per month (ft depth/house)	Supplemental irrigation needs per month (inches depth/month)	Supplemental irrigation needs per month (inches depth/week)
Jan	1,302	174	0.04	0.42	0.10
Feb	4,859	650	0.13	1.58	0.39
Mar	1,705	228	0.05	0.56	0.13
Apr	3,120	417	0.08	1.02	0.24
May	2,418	323	0.07	0.79	0.18
Jun	5,310	710	0.14	1.73	0.40
Jul	11,067	1,480	0.30	3.60	0.81
Aug	12,648	1,691	0.34	4.12	0.93
Sep	4,200	561	0.11	1.37	0.32
Oct	0	0	0.00	0.00	0.00
Nov	0	0	0.00	0.00	0.00
Dec	0	0	0.00	0.00	0.00
Totals:	46,629	6,234	1.27	15.19	

Figures 116 through 118 plot the monthly ET, rainfall, and supplemental irrigation needs. Most of the supplemental irrigation is needed in July and August, whereas there is an excess of rainfall in October through December, and therefore no supplemental irrigation is needed in those months.




Figure 116. ET by month.




Figure 117. Monthly rainfall.




Figure 118. Monthly supplemental irrigation requirements to meet ET.

The total amount of rainfall harvesting potential for irrigation (to match the ET) is about 46,600 gallons (6,230 ft<sup>3</sup>) per household per year. With 4,925 ft<sup>2</sup> of landscaped area per household, the annual irrigation requirement is about 1.3 ft, or 15 in., or an average of about one-half inch of water applied per week during the 9 months when there is an irrigation need. With 576 homes in the watershed, this totals about 27 million gallons (3.6 million ft<sup>3</sup>) per year for the 100-acre project area. Continuous simulations are used to see how much of this can actually be used according to the interevent conditions and rain patterns compared to the water need patterns and water storage volumes. It is also possible to use a greater amount of this water for irrigation for certain plants. These irrigation values are for typical turf grasses. Any additional irrigation would not be used by the plants but would be infiltrated into the soil. As noted, the long-term infiltration rates available through the soils at the project site are low.

### **Rain Barrels and Water Tanks for Roof Runoff Harvesting**

Rain barrels are a very simple method for collecting roof runoff for beneficial uses. In these analyses, irrigation of typical turf grass landscaping around the homes in the study area is the use being examined. This irrigation requirement was described previously and is the additional water needed to supplement the long-term monthly average rainfall to match the ET requirements for the area. As shown in these analyses, small rain barrels provide limited direct benefits, so larger water tanks were also considered. Also, to be most beneficial, these calculations assume that the irrigation rates are controlled by soil moisture conditions to match the ET requirements closely. This level of control is usually most effectively achieved with one large storage tank connected to an automatic irrigation system. Numerous smaller rain barrels are more difficult to control optimally.

For these calculations, each rain barrel is assumed to have 35 gallons of storage capacity (4.7 ft<sup>3</sup>). Each roof has an average area of 945 ft<sup>2</sup> and receives a total of 3,100 ft<sup>3</sup> of rainfall. As noted above, these analyses are for the directly connected roofs in the area, which are only about 15% of the total roof area in the study watershed.

Figures 119 and 120 are input screens used for rain barrels or cisterns in WinSLAMM version 10. This is the same form used for the biofilters, but only conditions relevant to rain barrels and water beneficial use are selected (top and bottom area the same, no native soil infiltration and no fill material needed). The two discharges include the required overflow (just the tank upper rim) and the monthly water use requirements (the irrigation demands). The current release of WinSLAMM now has a separate and stream-lined form for cisterns and rain barrels.

**Land Use: Residential**  
**Source Area: Roofs 1**  
**Total Area: 1.866 acres**  
**Biofilter Number 1**

**Device Properties**

Top Area (sf)	2
Bottom Area (sf)	2
Total Depth (ft)	2.50
Typical Width (ft) (Cost est. only)	1.50
Native Soil Infiltration Rate (in/hr)	0.000
Native Soil Infiltration Rate CDV	N/A
Infil. Rate Fraction-Bottom (0-1)	1.00
Infil. Rate Fraction-Sides (0-1)	1.00
Rock Filled Depth (ft)	0.00
Rock Fill Porosity (0-1)	0.00
Engineered Soil Type	
Engineered Soil Infiltration Rate (in/hr)	0.00
Engineered Soil Depth (ft)	0.00
Engineered Soil Porosity (0-1)	0.00
Percent solids reduction due to Engineered Soil (0 -100)	N/A
Inflow Hydrograph Peak to Average Flow Ratio	3.80
Number of Devices in Source Area or Land Use	86

**Add Outlet/ Discharge**

**Outlet/Discharge Options**

- 1. Sharp Crested Weir
- 2. Broad Crested Weir
- 3. Vertical Stand Pipe
- 4. Evaporation
- 5. Rain Barrel/Cistern
- 6. Underdrain Outlet
- 7. Evapotranspiration
- 8. Other Outlet

**Edit Existing Outlet**

**Selected Outlets**

- 1 - Broad Crested Weir
- 2 - Rain Barrel/Cistern

**Change Geometry**

**Source Areas from Land Use that Contribute Runoff to Biofiltration Control Device(s)**

- Rooftop 1
- Rooftop 2
- Rooftop 3
- Rooftop 4
- Rooftop 5
- Paved Parking/Storage 1
- Paved Parking/Storage 2
- Paved Parking/Storage 3
- Unpaved Prkng/Storage 1
- Unpaved Prkng/Storage 2
- Playground 1
- Playground 2
- Driveways 1
- Driveways 2
- Driveways 3
- Sidewalks/Walks 1
- Sidewalks/Walks 2
- Street Area 1
- Street Area 2
- Street Area 3
- Large Landscaped Area 1
- Undeveloped Area
- Small Landscaped Area 1
- Small Landscaped Area 2
- Small Landscaped Area 3
- Other Pervious Area
- Other Dir Cnctd Imp Area
- Other Part Cnctd Imp Area
- Paved Land and Shoulder 1
- Paved Land and Shoulder 2
- Paved Land and Shoulder 3
- Paved Land and Shoulder 4
- Paved Land and Shoulder 5
- Large Turf Areas
- Undeveloped Areas
- Other Pervious Areas
- Other Directly Cnctd Imp
- Other Partially Cnctd Imp

**Biofilter Geometry Schematic**

**Refresh Schematic** **Delete** **Cancel** **Continue**

**Select Native Soil Infiltration Rate**

- Sand - 8 in/hr
- Loamy sand - 2.5 in/hr
- Sandy loam - 1.0 in/hr
- Loam - 0.5 in/hr
- Silt loam - 0.3 in/hr
- Sandy silt loam - 0.2 in/hr
- Clay loam - 0.1 in/hr
- Silty clay loam - 0.05 in/hr
- Sandy clay - 0.05 in/hr
- Silty clay - 0.04 in/hr
- Clay - 0.02 in/hr
- Rain Barrel/Cistern - 0.00 in/hr

**Route Through Wet Detention Pond First**

Use Random Number Generation to Account for Infiltration Rate Uncertainty

Select Particle Size File: Does not need a particle size distribution

Figure 119. Cistern/water tank WinSLAMM input screen.

**Biofilter Cistern/Rain Barrel**

**Land Use: Residential**  
**Source Area: Roofs 1**  
**Biofiltration Device Number 1**  
**Outlet Number 2**

Month	Water Use Rate (gal/day)
January	42.00
February	172.00
March	55.00
April	104.00
May	78.00
June	177.00
July	357.00
August	408.00
September	140.00
October	0.00
November	0.00
December	0.00

**Cancel** **Continue** **Delete**


Figure 120. Water use WinSLAMM input screen.

Tables 63 and 64 and Figure 121 summarize the benefits of storage and irrigation use of runoff collected from directly connected roofs. The use of one rain barrel is expected to provide about a 24% reduction in roof runoff through irrigation to match ET. To match the benefits of disconnection of connected downspouts (about 78% reductions), about 25 rain barrels would be needed. Twenty-five rain barrels correspond to a total storage quantity about equal to 0.12 ft (1.4 in.). The level of maximum performance for roof runoff storage in Kansas City is relatively high compared to other US locations because the excess rainfall occurs during times of the greatest ET needs (with some winter months not having ET needs). More importantly, the landscaped areas that can be irrigated are relatively large when compared to the small roof areas. Together, these result in substantial maximum potential benefits associated with irrigation beneficial uses.

**Table 63. Roof runoff storage needs for beneficial use objectives**

# of rain 35 gal. barrels per house	Rain barrel storage per house (ft <sup>3</sup> )	Rain barrel storage per house (ft <sup>3</sup> ) per roof area (ft <sup>2</sup> , or ft depth over the roof)	Total annual roof runoff for 86 houses (ft <sup>3</sup> )	Total annual roof runoff per house (ft <sup>3</sup> )	Rv for roof area	% reduction in roof runoff
0	0	0	257,200	2,990	0.97	0
1	4.7	0.0050	196,700	2,290	0.74	24
4	19	0.020	155,800	1,810	0.58	39
10	47	0.050	112,400	1,310	0.42	56
100	470	0.50	3,160	37	0.01	99

1 ft<sup>3</sup> = 28 liters



**Figure 121. Irrigation storage requirements production function.**

As the storage volume increases, it likely becomes impractical to meet the total storage volume with small rain barrels. Table 64 shows the equivalent size of larger water tanks or cisterns when the number of rain barrels is more than four. As an example, a moderately sized water tank 5 ft in diameter and 6 ft tall has a similar storage capacity as 25 rain barrels, and if the 6-ft tall tank was expanded to 10 ft in diameter, this larger tank would have a similar capacity as 100 rain barrels.

The use of about 25 rain barrels, or a small tank 5 ft in diameter and 6 ft tall, is the recommended amount of storage for the directly connected roofs in the study area. This would provide about 74% reductions in the total annual runoff discharges, and almost complete control for the 1.4-in. regulatory design storm *D*.

**Table 64. Rain barrels and water tank equivalents**

Storage per house (ft depth over the roof)	Storage per house having 945 ft <sup>2</sup> roof area (ft <sup>3</sup> and gallons)	Reduction in roof runoff for 1.4-in. rain (%)	Reduction in annual roof runoff (%)	# of 35-gallon rain barrels	Tank height size required if 5 ft diameter (ft)	Tank height size required if 10 ft diameter (ft)
0	0 (0)	0	0	0	0	0
0.0050	4.7 (35)	16	24	1*	0.24	0.060
0.010	9.4 (70)	19	29	2	0.45	0.12
0.020	19 (140)	27	39	4	0.96	0.24
0.050	47 (350)	46	56	10	2.4	0.60
0.12	118 (880)	96	74	25	6.0	1.5
0.50	470 (3,500)	100	99	100	24	6.0

\*the yellow high-lighted cells are the most reasonable alternatives for these performance levels


### **Example Alternative Irrigation Water Use Calculations**

Tables 65 and 66 and Figures 122 and 123 are calculated supplemental irrigation requirements for residential areas in Millburn, New Jersey, an area having very challenging conditions for using stormwater to match local ET requirements (Pitt and Talebi 2012). These areas have roofs that are about 325 m<sup>2</sup> in area (3,500 ft<sup>2</sup>) corresponding to about 13.5% of the land use, and landscaped areas about 1,440 m<sup>2</sup> (15,500 ft<sup>2</sup>) corresponding to about 61% of the land use, with a relatively high roof to landscaped area ratio of about 0.23 (large homes and small lots). Table 65 and Figure 122 show the irrigation needs that can be considered the minimum amount by barely meeting the landscaped area ET requirements (assuming all rainfall contributes to soil moisture, which is true for rains less than about 25 mm (1 in.) in depth, but some of the rain flows to the storm drainage system for larger rains. The monthly rainfall compared to the monthly ET is shown in Figure 122 and illustrates how supplemental irrigation would be needed in the summer months, as expected. Table 65 shows the monthly irrigation needs in gallons per day per house. This rate would be used for barely meeting the ET needs with excessive irrigation. Excessive irrigation water would result in runoff (if applied at a rate greater than the infiltration rate of the surface soils) and recharge of the shallow groundwater. For a water conservation program, this irrigation amount is usually the target. However, for a stormwater management goal, maximum use of the roof runoff is desired.

**Table 65. Irrigation needs to satisfy ET requirements for Essex County, New Jersey**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total Annual
Average monthly rain (in/mo)	3.42	3.11	4.16	3.71	3.99	2.88	4.21	4.04	3.61	3.06	3.70	3.47	43.37
Average monthly ET (in/mo)	0.47	0.85	3.26	3.90	4.81	4.65	4.81	4.19	3.60	3.57	3.00	1.40	38.47
deficit for ET needs (in/mo)	0.00	0.00	0.00	0.19	0.81	1.77	0.60	0.15	0.00	0.51	0.00	0.00	4.03
Deficit ET needed (gal/day/house) 0.36 acre	0	0	0	63	256	577	188	47	0	160	0	0	39,200 gal/year

Source: Pitt and Talebi 2012  
(1 in/mo = 25 mm/mo)



**Figure 122. Plot of supplemental irrigation needs to match ET deficit for Essex County, New Jersey. (1 in/mo = 25 mm/mo).**

For maximum use of the roof runoff to decrease runoff volume discharges, it is desired to irrigate at the highest rate possible, without causing harm to the plants. Therefore, Table 66 and Figure 123 show an alternative calculation corresponding to a possible maximum use of the roof runoff. For a *healthy* lawn, total water applied (including rain) is generally about 25 mm (1 in.) of water per week, or 100 mm (4 in.) per month. Excessive watering is harmful to plants, so indiscriminate over-watering is to be avoided. Some plants can accommodate additional water. As an example, Kentucky bluegrass, the most common lawn plant in the United States, needs about 64 mm/week (2.5 in./week), or more, during the heat of the summer and should also receive some moisture during the winter. Table 66 therefore calculates supplemental irrigation for 12 mm (0.5 in.) per week in the dormant season and up to 64 mm/week (2.5 in./week) in the hot months. Natural rains are expected to meet the cold season moisture requirements. The total irrigation needs for this moisture series is about 318,000 gallons (1,200 m<sup>3</sup>) per year per home. This is about eight times the amount needed to barely satisfy the ET requirements noted before. However, the roofs in the Millburn study area are expected to produce about 90,000 gallons




(340 m<sup>3</sup>) of roof runoff per year, or less than a third of the bluegrass needs but more than twice the needs for the ET deficit. Therefore, it is possible to use runoff from other areas, besides the roofs, for supplemental irrigation.

**Table 66. Irrigation needs to satisfy heavily irrigated lawn for Essex County, New Jersey**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total annual
Average monthly rain (in/mo)	3.42	3.11	4.16	3.71	3.99	2.88	4.21	4.04	3.61	3.06	3.70	3.47	43.37
Lawn moisture needs (in/mo)	2.00	2.00	4.00	4.00	8.00	8.00	10.00	10.00	10.00	8.00	4.00	2.00	72.00
Deficit irrigation need (in/mo)	0.00	0.00	0.00	0.29	4.01	5.12	5.79	5.96	6.39	4.94	0.30	0.00	32.80
Deficit irrigation needed (gallons/day/house) 0.36 acre	0	0	0	96	1,263	1,669	1,826	1,880	2,081	1,558	96	0	318,000 gal/year

Source: Pitt and Talebi 2012



**Figure 123. Plot of supplemental irrigation needs to match heavily watered lawn (0.5 to 2.5 in./week) deficit for Essex County, New Jersey (1 in/mo = 25 mm/mo).**

## Green Roofs

As noted above for the description of the biofilter calculations, the biofilter device can be configured to represent green roofs, as illustrated in Figure 124. In an upcoming WinSLAMM version, a separate screen will be provided for these devices. Basically, the green roof area is used as the area of the biofilter, and no natural infiltration is allowed. The only outlets include the required broad crested weir for surface overflows, underdrains, and ET. Partial roof coverage can be modeled by using a smaller area for the “biofilter” to represent the area dedicated to green roof processes.

Figure 124. Green roof main input screen.

Table 67 summarizes the calculated performance of the specified green roof system, for different roof coverages. The concentrations are similar for all scenarios because almost all of the water is filtered by the roof media, with little being discharged to the surface overflows. The available ET resulted in about 25% reductions in runoff volume discharges. If more surface storage was provided in the green roof design and if more efficient plants were used, it is likely that these runoff volume reductions could be about double the reductions shown in this example.


**Table 67. Calculated green roof performance**

Green roof as a % of flat roof area (3-in conventional underdrains every 20 ft)	Rv	Volume reductions (%)	TSS (mg/L)	Solids discharged (lbs/yr)	Peak runoff rate (cfs)	Peak rate reductions (%)	TP (mg/L)	TP load (lbs)	Cu (µg/L)	Cu load (lbs)
none	0.8	n/a	33	55	0.76	n/a	0.22	3.6	11	0.18
25%	0.71	11	24	35	0.57	25	0.17	2.4	9.8	0.14
50%	0.66	18	24	33	0.45	41	0.16	2.2	9.7	0.13
100%	0.6	25	24	29	0.38	50	0.16	2	9.7	0.12

## Summary of Performance Production Functions for the Design and Analysis of Stormwater Management Controls

The first stormwater control that should be considered in an area is disconnecting the directly connected impervious areas, such as roofs and paved parking lots. The directly connected roofs in the test area contribute about 5.8% of the total area flows, whereas the much greater area of disconnected roofs contribute about 7.2% of the annual runoff from the entire 100-acre area. The current flow contributions of all roofs in the area total about 13%. If all the roofs were directly connected, the roofs would contribute about 31% of the total area runoff, and the runoff from the total area would increase by about 25%, a significant increase. In contrast, if the directly connected roofs were disconnected through a downspout disconnection program, the total roof contribution would decrease to about 9%, and the total area runoff would decrease by about 5%. Because about 85% of the roofs in the area are already disconnected, the benefits of controlling the remaining directly connected roofs are limited. Directly connected roofs in the study area contribute about 4.5 times the amount of runoff per unit area as the disconnected roofs. This indicates that about 78% of the annual runoff from the disconnected roofs is infiltrated as it passes over previous areas on the way to the drainage system. Therefore, it is much less cost-effective to use roof runoff controls for the runoff from the disconnected roofs compared to runoff controls for the directly connected roofs. The benefits of disconnecting connected paved parking or storage areas are similar to the benefits shown above for roofs.


Private rain gardens for controlling roof runoff are being used in the residential areas in the test (pilot) area. As runoff enters the device, water infiltrates through the engineered soil or media (or natural soil, as in a rain garden). If the entering rain cannot all be infiltrated through the surface layer, the water ponds. If the ponding becomes deep, it can overflow through the broad-crested weir or other surface outlet. The percolating water moves down through the device until it reaches the bottom and intercepts the native soil. If the native soil infiltration rate is greater than the percolation water rate, no subsurface ponding occurs; if the native soil infiltration rate is slower than the percolation water rate, ponding occurs. As shown in Figure 125, as the rain garden size increases in relation to the roof area, less water is discharged to the collection system. About 90% of the long-term runoff would be infiltrated for a rain garden that is about 20% of the roof area (similar to the monitored roof runoff rain gardens in this study):



**Figure 125. Percentage reduction in annual roof runoff with rain gardens.**

Rain gardens 20% of the roof area would also provide about 90% runoff reductions from the directly connected roofs during the 1.4-in. regulatory design storm *D*.

Biofilter performance is based on the characteristics of the flow entering the device, the infiltration rate into the native soil, the filtering capacity and infiltration rate of the engineered media fill if used, the amount of rock fill storage, the size of the device, and the outlet structures for the device. WinSLAMM was used with the calibration files prepared for the Kansas City demonstration project to examine alternative biofilter and bioinfiltration device designs for the residential test (pilot) area. Four infiltration rates for the native subsurface soil were examined: 0.2, 0.5, 1.0, and 2.5 in/hr (corresponding to sandy silt loam, loam, sandy loam, and loamy sand soils, respectively). The lowest rate (0.2 in/hr) was the assumed early infiltration rate used by the design consultants for the original designs. Site surface soil measurements in the test watershed indicated 1 in/hr, or greater, infiltration rates for rains lasting 2 hours or less. Site measurements of the biofilters during storms indicated infiltration rates of the media and device at 1.8 in/hr, and modeling indicated likely subsurface rates of about 1 in/hr (or greater) to result in the observed performance during the rains (almost complete infiltration with very little overflow or subsurface underdrain discharges). The use of gravel storage is important for only the low infiltration rate conditions: once the infiltration rate is about 1 in/hr, or more, this additional storage is not needed, as far as benefiting the long-term infiltration conditions. As shown in Figure 126, for the low infiltration rates, the use of underdrains degrades the performance of the biofilters because the underdrains discharge subsurface ponding water before it can completely infiltrate (but underdrains decrease surface ponding, a desired objective). The use of a slow underdrain (as indicated here by the SmartDrain<sup>TM</sup>), results in an intermediate effect, while also decreasing long periods of surface ponding. As with the gravel storage, underdrains have very little effect on performance when the native subsurface native infiltration rate is about 1 in/hr, or greater.



**Figure 126. Effects of underdrains in biofilters on annual runoff reductions for subsurface native soil infiltration rate of 0.5 in/hr.**

Biofilter media is likely to fail resulting in very low infiltration rates with rapid and excessive particulate solids loadings. Generally, particulate loads of between 10 and 25 kg/m<sup>2</sup> might lead to significantly reduced infiltration. A planted biofilter is likely to be able to incorporate this additional material into the soil as healthy plants can keep the infiltration rates at a desired level, if this accumulative load occurs over at least 10 years. However, if this load occurs within just a few years, it is likely to overwhelm the system, resulting in premature clogging. This is more of a problem for small biofilters receiving runoff having high particulate solids concentrations, such as parking lots where space is limited. Pretreatment using grass filters or swales can reduce these problems. For this study area, if the biofilters are at least 1 to 3% of the residential drainage area, the particulate loading is not likely to be a problem. The biofilters and bioinfiltration devices in the test (pilot) area are about 1.5 to 2% of the residential drainage areas. For the 1 in/hr subsurface infiltration rate, this size of treatment device is expected to provide about a 90% reduction in the annual flows for the areas treated, with very little overflows. The SmartDrain<sup>TM</sup> installation is expected to have only about 1% of the annual flows being captured by this underdrain. These calculated conditions are all similar to the observed conditions during the brief monitoring period.

The WinSLAMM porous pavement control in version 10 has full routing calculations associated with subsurface porous media storage and allows runoff from adjacent areas. Table 68 summarizes the calculated performance of porous pavement located at paved parking/storage areas. The given underlying soil is a loam soil. A conventional 3-in. perforated pipe underdrain was also assumed. As indicated, even the smallest area examined (25% of the area as porous pavement) had very good runoff volume reductions. The porous pavement was cleaned every year, restoring much of the lost surface infiltration rate capacity in this example. If the area is not cleaned, clogging would be expected in about 8 years, based on field experience. Care needs to be taken to prevent runoff of stormwater having high particulate solids loads, or excessive leaf debris on the porous pavement, as both conditions can result in premature failure. Porous pavements are also not recommended for areas having substantial traffic or receiving other

more highly contaminated runoff (especially snowmelt in areas using deicing chemicals) to reduce groundwater contamination potential. Sidewalks and walkways, along with residential driveways are the most suitable areas for porous pavement installations.

**Table 68. Porous pavement performance (paved parking and storage area; loam soil; 3-in underdrains every 20 ft.)**

Porous pvt as a % of paved parking area	Rv	Volume reduction (%)	Expected habitat conditions	TSS (mg/L)	Solids discharged (lbs/yr)	TP (mg/L)	TP load (lbs)	Cu (µg/L)	Cu load (lbs)
none	0.75	n/a	Poor	130	812	0.21	13	21	1.3
25%	0.06	92%	Good	130	60	0.21	0.98	21	0.098
50%	0.05	93%	Good	130	58	0.32	0.94	12	0.093
100%	0.05	93%	Good	130	58	0.21	0.94	21	0.093

Grass filters have broad, shallow flows. WinSLAMM calculations for grass filters are based on extensive pilot-scale and field measurements of grass swales and filters. Table 69 summarizes the performance of grass filters for controlling runoff from 2 acres of impervious area. As the grass filters become steep, they lose some of their performance because of the faster flowing water reducing the effective infiltration rates.

**Table 69. Grass filter performance for different soils and slopes**

Description	Rv	% runoff volume reduction	TSS (mg/L)	Solids yield (lbs/yr)	% solids yield reduction	Peak runoff rate (cfs)	% peak runoff rate reduction	TP (mg/L)	TP load (lbs)	Cu (µg/L)	Cu load (lbs)
base conditions, no controls	0.55		100	1040		4.6		0.28	29	17	1.7
grass filter 0.5% slope	0.17	69%	91	300	71%	2.6	43%	0.27	8.7	16	0.52
grass filter 2 to 25% slopes	0.22	60%	90	376	64%	3.5	24%	0.26	11	16	0.67

Grass swales are evaluated in WinSLAMM with the same general processes as for grass filters, except that concentration flows occur. Table 70 summarizes the performance of a swale for two soil conditions. As expected, the swale water volume and pollutant reduction performance is better for the loam soil than for the silty soil.

**Table 70. Grass swale performance**

Description	Rv	% runoff volume reduc.	Expected habitat conditions	TSS (mg/L)	% solids yield reduc.	Solids yield (lbs/yr)	Peak runoff rate (cfs)	% peak runoff rate reduc.	TP (mg/L)	TP load (lbs)	Cu (µg/L)	Cu load (lbs)
base conditions, no controls	0.55		poor	100		1040	4.6		0.28	29	17	1.7
silty soil	0.33	40%	poor	86	92%	535	4.4	4%	0.25	16	16	0.98
loam soil	0.16	71%	fair	87	92%	263	2.9	37%	0.26	7.8	16	0.47

Benefits associated with stormwater use for irrigation and other on-site uses can be calculated on the basis of site-specific information. Irrigation of land on the homeowner's property was considered the beneficial use of most interest. Rain barrel/water cistern effectiveness is related to supplemental irrigation and how that matches the rainfall deficit (ET minus rainfall) for each season. The continuous simulations used a typical one-year rain series and average monthly ET values for varying amounts of roof runoff storage. Figure 127 shows the expected roof runoff reductions for different storage tank volumes. One 35-gallon rain barrel is expected to reduce the total annual directly connected roof runoff by about 24%, if the water use could be closely regulated to match the irrigation requirements, such as with an automated irrigation system with soil moisture sensors (not likely to be used in conjunction with a few rain barrels, but more likely with a large tank than can be pressurized). If four rain barrels were used for each house, such as one at each corner of a house receiving runoff from separate roof downspouts, the total annual roof runoff volume reductions from the roofs could be as high as about 40%. A small water storage tank about 5 ft in diameter and 6 ft in height could result in about 75% total annual runoff reductions from directly connected roofs; a larger, 10-ft-diameter tank that is 6 ft tall could approach complete roof runoff control. The 5-ft-diameter tank is also expected to provide almost complete control of runoff from the regulatory design storm *D*. These calculations are very sensitive to location as the rainfall deficit varies greatly throughout the country. The central part of the United States (including Kansas City) has a relatively large rainfall deficit with rainfall occurring at relatively optimal times for enhanced beneficial uses of roof runoff. Other areas of the county are not as suitable for this control.




Figure 127. Percentage reduction in roof runoff with irrigation of landscaped areas in Kansas City.



For maximum use of the roof runoff to decrease runoff volumes, it is desired to irrigate at the highest rate possible, without causing harm to the plants. For a *healthy* lawn, total water applied (including rain) is generally about 25 mm (1 in.) of water per week, or 100 mm (4 in.) per month. Excessive watering is harmful to plants, so indiscriminate over-watering is to be avoided. Some plants can accommodate additional water. As an example, Kentucky Bluegrass, the most common lawn plant in the United States, needs about 64 mm/week (2.5 in/week), or more, during the heat of the summer and should receive some moisture during the winter.

The biofilter option in WinSLAMM can be configured to represent green roofs. Basically, the green roof area is used as the area of the biofilter and no natural infiltration allowed. The only outlets include the required broad crested weir for surface overflows, underdrains, and ET. Partial roof coverage can be modeled by using a smaller area for the *biofilter* to represent the area dedicated to green roof processes. Table 71 summarizes the calculated performance of a green roof system for different roof coverages. The concentrations are similar for all scenarios because almost all of the water is filtered by the roof media, with little being discharged to the surface overflows. The available ET resulted in about 25% reductions in runoff volume reductions. If more surface storage was provided in the green roof design and if more efficient plants were used, it is likely that these runoff volume reductions could be about double the reductions shown here.

**Table 71. Calculated green roof performance**

Green roof as a % of flat roof area (3-in conventional underdrains every 20 ft)	Rv	Volume reductions (%)	TSS (mg/L)	Solids discharged (lbs/yr)	Peak runoff rate (cfs)	Peak rate reductions (%)	TP (mg/L)	TP load (lbs)	Cu (µg/L)	Cu load (lbs)
none	0.8	n/a	33	55	0.76	n/a	0.22	3.6	11	0.18
25%	0.71	11%	24	35	0.57	25%	0.17	2.4	9.8	0.14
50%	0.66	18%	24	33	0.45	41%	0.16	2.2	9.7	0.13
100%	0.6	25%	24	29	0.38	50%	0.16	2	9.7	0.12

## 8. Economic and Decision Analyses using WinSLAMM

The cost analyses in WinSLAMM can be used to automatically calculate the capital, maintenance and operation, and financing costs for stormwater control programs being examined. This information can be used with the model batch processor to develop cost-benefit curves for the different control options. The cost information is entered in the model using the set of forms as shown in Figure 128. Figure 129 shows the cities that have inflation data already in the model (including Kansas City). Besides the unit cost rates that are already available, it is possible to enter more specific local cost data, based on site costs.




Figure 128. Basic economic analyses input screen






Figure 129. U.S. cities already in the economic model


An example of a performance production function that can be used in conjunction with the economic analyses is illustrated in Figure 130 which is a plot of the percentage of the typical annual runoff amount that can be infiltrated by curb-cut rain gardens, based on the number of units used. With 1,500 units possible in this area, up to about 80% of the annual runoff could be infiltrated. With 400 units, about 40% of the annual flows would be diverted from the combined sewers. Figure 131 plots some preliminary cost estimates for these devices (this estimate does not consider aesthetic landscaping, only basic excavation and simple curb cuts). The basic total capital cost for these very small devices is expected to be about \$1,000 each, and the annualized total cost to be about \$150 each. Again, the actual costs are likely to be greater because of the planting and plant maintenance. Figure 132 shows the durations of flows at different rates for several different curb-cut rain garden applications. The maximum peak flow for the typical rain year is expected to be between 25 and 30 cfs for this area. The use of 600 rain gardens is also likely to reduce the peak flow rates that occur about 5 to 10 hours a year to about half of the flow rates that would occur if uncontrolled.




**Figure 130.** Annual runoff volume reduction (%) for typical rain year (1990) for different numbers of simple curb-cut rain gardens per 100-acre watershed.



**Figure 131.** Total capital costs and total annualized costs for different numbers of simple curb-cut rain gardens per 100-acre watershed.



**Figure 132.** Durations of flows (% of time) for different numbers of simple curb-cut rain gardens.



**Figure 133.** Percentage reduction of annual flows with 10 ft diameter x 5 ft tall cisterns (numbers per 100 acres)

Figure 133 is a plot of the annual roof runoff removals that would occur for different numbers of large cisterns in the area. The maximum control that is expected is about 35%, as that is the fraction of the annual flow that is expected to originate from the roofs. This level of control would occur with about 200 large cisterns in the 100-acre area. Very small rain barrels would have very little benefits in reducing the annual discharges to the combined sewer.

Table 72 shows the expected level of control for various combinations of large cisterns and curb-side rain gardens. The largest level of control expected is about 90% of the annual runoff, but that would require a

maximum application of these controls. However, levels of runoff reduction of about 75% could be achieved with a more reasonable effort (about 500 rain gardens and 250 cisterns, or 1,000 rain gardens and 50 cisterns). The expected cost of this high level of control is likely to be more than \$1million for the 100 acres, just for these components. Controls established at the time of development can be much less and, in many cases, can be less than conventional development options.

**Table 72. Approximate annual flow reductions (%) for combinations of large cisterns and simple curb-side rain gardens, per 100 acres**

	0 rain gardens	100 rain gardens	500 rain gardens	1,000 rain gardens	1,500 rain gardens
0 cisterns	0%	12%	47%	70%	81%
25 cisterns	12%	23%	52%	73%	82%
50 cisterns	20%	32%	58%	76%	83%
100 cisterns	29%	40%	66%	80%	85%
250 cisterns	36%	47%	73%	86%	90%
600 cisterns	37%	48%	74%	87%	91%

## Using WinSLAMM Decision Analyses to Select an Urban Runoff Control Program

Decision analysis techniques can be used to guide the selection of an urban runoff control program. Decision analysis is a systematic procedure that enables one to study the tradeoffs among multiple and usually conflicting program objectives. An alternative procedure is to separately determine the programs necessary to meet each objective and to use the least costly program that satisfies all the identified critical objectives. This is an acceptable procedure some of the time, but it might not result in the most cost-effective program, especially when multiple objectives need to be considered.

Decision analysis optimizes the partial fulfillment of all the objectives. It translates these into their relative worth to the decision maker or other interested parties. This section describes the types of output information calculated by WinSLAMM and how it can be used in decision analysis procedures of varying complexities.

As in most models, there is a great deal of information calculated by WinSLAMM during an analysis of stormwater management alternatives. In most cases, values presented on the main WinSLAMM summary screen are sufficient for most comparisons. These include the overall percent runoff and particulate solids reductions, the final Rv and runoff volume, and the resulting particulate solids and pollutant yields and concentrations. In addition, life cycle costs (including lost opportunity, capital, land, operation, and maintenance costs) and the expected habitat conditions of the receiving waters is also available for evaluation, in addition to flow-duration information. Cost data included in the model were obtained from several studies, including those by APWA 1992; Brown and Schueler 1997; Frank 1989; Heaney et al. 2002; Muthukrishnan et al. 2006; Sample, et al. 2003; SEWRPC 1991; Wiegand et al. 1986; and Wossink and Hunt 2003. The batch processor in WinSLAMM is frequently used to automatically examine all the land use and stormwater control options for a relatively large area, such as for citywide analysis, especially when used in conjunction with GIS data.

Figure 134 is a screenshot of the main batch processor screen that is used to select the standard land use files for an area being examined, along with the areas, and soils. This screen is also used to select a set of files that can be run in batch mode to compare multiple stormwater controls for the same site, as described later. In that configuration, the first file listed is the base condition that is compared to the other files. Alternative analyses are also usually conducted to examine different stormwater control practices.




Figure 134. WinSLAMM Batch Editor setup screen.

Recent enhancements to WinSLAMM allow the batch processor to be used to enable comparisons of different stormwater control programs for a single site. As noted above, many stormwater factors are calculated for each analysis, and a stormwater manager might have difficulty comparing the different alternatives. Tables 73 and 74 are summarized from the expanded csv output file (showing only a few of the calculated factors, as an example), comparing eight alternative stormwater management programs to a base condition that was calculated with the WinSLAMM batch processor. The alternatives and the full analyses for this example are shown later in this section. The different stormwater management programs considered in this example are: grass swales, two wet detention ponds, biofilters, plus combinations of these controls. WinSLAMM can evaluate many other alternative controls, and combinations, but this is shown as only a short example of the output table.

**Table 73. Attributes of several different stormwater management programs**

Stormwater treatment option	Part. phos yield (lbs/yr)	Volum. runoff coeff. (Rv) (est. bio. cond.)	% of time flow > 1 cfs	% of time flow > 10 cfs	SS conc. (mg/L)	Part. P conc. (mg/L)	Zn conc. (µg/L)
Base, No Controls	174	0.29 (poor)	4.5	0.3	204	0.50	359
Option 1 Pond	25	0.29 (poor)	4	0.05	30	0.073	128
Option 2 Grass Swale	79	0.15 (fair)	2	0.1	178	0.43	390
Option 3 Site Biofilter	172	0.14 (fair)	2	0.2	408	1.0	696
Option 4 Small pond	41	0.29 (poor)	4	0.2	48	0.12	151
Option 5 Pond and grass swale	10	0.15 (fair)	2	0	23	0.057	203
Option 6 Pond, swale, biofilter	5.5	0.06 (good)	0.5	0	29	0.073	386
Option 7 Small pond and swale	17	0.15 (fair)	2	0.05	39	0.095	220
Option 8 Small pond, swale and biofilter	10	0.07 (good)	0.8	0	53	0.13	390

**Table 74. Additional attributes of several different stormwater management programs**

Stormwater treatment option	Annual total sw treat. cost (\$/yr)	Annual addit. drain. system cost (\$/yr)	Total annual cost (\$/yr)	Land needs for SW mgt (acres)	Runoff volume (cf/yr)	Part. solids yield (lbs/yr)	Reduc. in SS yield (%)
Base, No Controls	0	64,230	64,230	0	5,600,000	71,375	n/a
Option 1 Pond	19,134	64,230	83,364	4.5	5,507,000	10,192	86
Option 2 Grass Swale	3,158	26,850	30,008	0	2,926,000	32,231	55
Option 3 Site Biofilter	32,330	37,380	69,710	0	2,705,000	68,890	1
Option 4 Small pond	10,209	64,230	74,439	2.3	5,557,000	19,552	73
Option 5 Pond and grass swale	22,292	26,850	49,142	4.5	2,844,000	4,133	94
Option 6 Pond, swale, biofilter	54,622	0	54,622	4.5	1,203,000	2,183	97
Option 7 Small pond and swale	13,367	26,850	40,217	2.3	2,887,000	6,937	90
Option 8 Small pond, swale and biofilter	45,698	0	45,698	2.3	1,253,000	4,125	94

Table 74 also shows the additional conventional drainage system costs for each option, including the costs associated with a conventional storm drainage system from external calculations. If at least

80% particulate solids reductions are needed (a typical goal for some programs, including those in Massachusetts and Wisconsin for new developments), several options would meet this goal, as shown in the last column. Option 7, the use of grass swales plus a small wet detention pond, is the least costly of these acceptable options. This option also has the benefit of significant runoff volume reductions, compared to the base condition, although the options adding the biofilters with the swales produce even less runoff.

The above example illustrates a relatively straightforward approach in selecting the *best* stormwater control program. However, it might be desirable to also consider other attributes associated with the different options. The following discussion is based on material originally presented by Pitt (1979) and is a hypothetical example application of a decision analysis procedure that considers conflicting and multiple objectives applied to selecting a street cleaning program as part of a stormwater management plan.

### **Decision Analysis with Multiple Conflicting Objectives**

The following is a hypothetical example with fictional values that illustrates the basic elements of decision analysis to select a preferred street cleaning program from a list of alternatives (updated from an earlier discussion presentation by Pitt 1979). The objectives of such a program might include maximizing air, water, and aesthetic quality and minimizing the noise and cost of street cleaning operations. Unfortunately, some objectives (such as cost and environmental quality) tend to conflict with each other. The decision makers must choose the alternative that makes the best tradeoffs among the competing objectives.

The techniques of decision analysis, as described by Keeney and Raiffa (1976), are used to aid in the selection process. This historical reference contains detailed discussions on decision analysis theory and should be consulted for further information. This method uses utility curves and tradeoff values between the different attributes. The utility curves should be based on data and not reflect personal attitudes or objectives, while the tradeoffs between the attributes reflect different viewpoints. This decision analysis method is therefore a powerful tool that can be used to compare the rankings of alternative stormwater management programs for different groups. In many cases, final rankings might be similar among the interested parties, although their specific reasons vary. Most importantly, this tool also completely documents the decision-making process, enabling full disclosure. This feature is probably more important for site selection projects for power plants than for small public works projects, but this level of documentation is still critical when public policy and taxes are concerned.

The detail and depth of understanding needed to fully use this decision analysis methodology forces the user to acquire a deeper understanding of the problem being solved. Multiple experts are usually needed to develop the utility curves, but they can be used for similar projects in the same region sharing similar problems and objectives. The tradeoffs are dependent on the mix of decision makers and stakeholders involved in the process and are expected to change with time. The depth of knowledge obtained and full documentation always is a positive aspect of these methods, but the required resources to fully implement the system can be an insurmountable obstacle to smaller communities. However, sensitivity analyses can be used to focus resources only on those aspects of greatest importance.

The first step in applying decision analysis techniques consists of defining the alternatives and quantitative measures (attributes) for the objectives. How well each alternative achieves the objective is also determined. In this hypothetical example, five example attributes were chosen to reflect widely different considerations in deciding which street cleaning program to select. These attributes, their units of measurement, and the associated ranges are shown in Table 75.



**Table 75. Decision analysis attributes, measures, and ranges of values**

	Attribute description	Units of measurement	Range of values	
			Best	Worst
1.	Aesthetics (residual loading)	lb/curb-mile	68	525
2.	Annual cost	\$/curb-mile/year	350	3,600
3.	Air quality (particulates)	µg/m <sup>3</sup>	100	200
4.	Water quality (suspended solids)	mg/L	200	1,500
5.	Noise Level	dB <sub>A</sub>	65	82

The second step consists in describing each alternative in terms of the attributes defined in step one. The value of each attribute for each of the alternatives must be determined. The attribute levels may be described either in terms of probabilistic forecasts, where uncertainties are quantified, or by point estimates representing the level expected for each attribute. In this example, five alternative street cleaning programs are considered, and point estimates are made for each attribute. The street cleaning programs consist of combinations of equipment types and their frequencies of use. These alternatives are defined in Table 76. Point estimates, for illustrative purposes, are used for this example and summarized in Table 77, which shows that all attributes, except cost, are better than, or equal for alternative two.

**Table 76. Definition of alternatives**


Alternative description
1 Conventional mechanical street cleaner, one pass every week
2 Conventional mechanical street cleaner, one pass every weekday
3 Vacuum street cleaner, one pass every week
4 Street flusher, one pass every week
5 Conventional mechanical street cleaner followed by a flusher, one pass every week

**Table 77. Estimated attribute levels for each alternative (fictional)**

Alternative	Aesthetics (lb total solids/curb-mile)	Annual cost (\$/curb-mile/year)	Air quality (µg susp partic/m <sup>3</sup> )	Water quality (mg TSS/L)	Noise level (dB <sub>A</sub> /pass)
1	340	700	200	1,000	65
2	68	3,600	120	200	65
3	470	700	150	1,400	70
4	525	350	200	1,500	80
5	150	1,000	150	400	82

The third step consists of quantifying the preference and tradeoffs for the various attribute levels. The concepts of utility theory provide a consistent scale to quantify how much one gives up when choosing one attribute over another. Utility curves are first assessed for the individual attributes. These curves quantify the preferences that exist for the total range of each attribute. They also quantify attitudes toward risk. This is important when alternatives yield uncertain consequences. The curves are theoretically defined from a series of questions that determine points on each of the utility curves. The most preferred point is defined as having a utility value of 1.00 and the least preferred point a utility value of 0.00. The utility assessments establish where the intermediate points fall on the utility scale. An example of a utility

function for a water quality attribute is shown in Figure 135. Each of the other attributes can be assessed on a similar curve.



Source: Pitt 1979

**Figure 135. Example utility function for a water quality attribute (TSS, mg/L).**

The formal development of a utility curve can be determined through a series of questions. In many cases, the shape of the utility curve can be reasonably determined through direct knowledge of the attribute. In other cases, it is suitable to assume a linear relationship between the maximum and minimum attribute levels. The utility curves are technology-based and reflect how different levels of an attribute relate to other levels of the same attribute. As an example, further degradation of a receiving water is unlikely after the dissolved oxygen levels reach anaerobic conditions, but increasing stress occurs as that level is approached. This information can be used to determine the shape of the utility curve. In the example of cost, spending twice as much is probably twice as bad reflecting a straight-line relationship between cost and utility.

The questions that can be used to define the individual attribute utility curves consist of asking the decision maker to choose one of two possible situations. In this example, one situation is uncertain and describes a 50-50 chance for a successful outcome of one of the two possible levels of the attribute; the second situation occurs with certainty and consists of achieving a specified level of the attribute. The level of the attribute in the second situation is somewhere between the two equally possible levels of the first situation. The utility assessment for each point on the curve is determined by the attribute level in the second situation, where the decision maker is indifferent to the choice of the two situations. Because, at the point of indifference, each choice is equally acceptable, the expected utility values of the two situations must be equal, and a point of the utility curve can be established.

Consider for example a situation with a 50-50 chance of achieving water quality at either 1,500 or 200 mg TSS/L. What level of water quality (if known with certainty) would be equally preferable to the uncertain situation above? After a series of trial choices, it was determined that a water quality level of 650 mg TSS/L would be indifferent to the uncertain situation. Again, this would be based on knowledge of the attribute, such as how the risk varies for different concentrations, such as how the toxicity response varied for different conditions during controlled toxicity tests. Thus, the utility of a water quality level of 650 mg/L TSS must equal the expected utility of the uncertain situation with a 50-50 chance of achieving either 1,500 or 200 mg/L TSS. Because the utility values of 1,500 and 200 mg/L are known to be 0.00 and 1.00, respectively, the expected utility of the first situation can be calculated as  $0.5 (0) + 0.5 (1.00) = 0.5$ .

Therefore, the utility value of 650 mg/L must equal 0.5. This point is plotted in Figure 135. Similar questions can be used to define the other points shown in Figure 135.

The tradeoffs that exist among the attributes are established next. While the utility curves should be based on scientific knowledge, the tradeoffs should reflect the different attitudes of the different interested parties. Different tradeoffs will result in possibly different final rankings for the different street cleaning programs for the different groups. Determining the tradeoffs is done by first ranking the attributes in order of importance. The tradeoffs result in values given to each attribute, such that the sums of the values equal one. The simplest approach is to request the decision makers to rank the attributes and arbitrarily assign tradeoffs such that the tradeoff values equal one.

The rank order and tradeoff values can be theoretically established by answering questions like the following: “Given that all attributes are at their worst levels, which attribute would one first move to its best level?” The question is repeated to determine which attribute would next be moved to its best level. This process is continued until the complete rank order of the attributes is established. In this example, the following rank order of the attributes was established:

- Water Quality
- Annual Cost
- Air Quality
- Aesthetics
- Noise Level

The tradeoffs among attributes are addressed next. This can be done by considering the choice between two possible situations for a pair of attributes. Both situations are certain but consist of different levels for the pair of attributes. The levels for the pair of attributes are in the form of *worst*, *best* compared with *?*, *worst*. The unknown attribute level is established after repeated trials until the decision maker is indifferent to the two situations. Considering the water quality/annual cost attribute pair, the two situations would be “1500 mg/L, \$350” and “?, \$3600.” In this situation, we are determining how much people would expect the water quality to improve with an increase in cost. In this hypothetical example, if the water quality were 650 mg/L, the second situation would be indifferent to the first situation. Similar questions were asked for other pairs of attributes, determining how much the attribute level was expected to improve with increasing cost. These hypothetical results are summarized below, using the notation ( $\cong$ ) to indicate indifference.

- (Water quality, annual cost) = (1500 mg/L, \$350)  $\cong$  (650 mg/L, \$3600)
- (Annual cost, noise level) = (\$3600, 65 dbA/pass)  $\cong$  (\$3000, 82 dbA/pass)
- (Annual cost, aesthetics) = (\$3600, 68 lb/mile)  $\cong$  (\$3000, 525 lb/mile)
- (Annual cost, air quality) = (\$3600, 100  $\mu\text{g}/\text{m}^3$ )  $\cong$  (\$1500, 200  $\mu\text{g}/\text{m}^3$ )

The above information concerning the preferences for achieving levels for the attributes can be used to establish a multiattribute utility function. A multiattribute utility function is a mathematical expression that summarizes attribute utility functions and the tradeoffs between the attributes. The mathematical form of the multiattribute utility function is established by verifying several reasonable assumptions regarding preferences. To illustrate, an additive multiattribute utility function is represented as follows:

$$u(x_1, x_2, x_3, x_4, x_5) = \sum_{i=1}^5 k_i v_i(x_i) \quad (8.1)$$

where

$$\begin{aligned}
 x_i &= \text{the level of the } i\text{th (i-1,5) attributes} \\
 u_i(x_i) &= \text{the utility of the } i\text{th individual attribute} \\
 v &= \text{the multiattribute utility} \\
 k_i &= \text{tradeoff constant for } i\text{th attribute, and}
 \end{aligned}$$

$$\sum_{i=1}^5 k_i = 1$$

The tradeoff constants in Equation 8.1,  $k_i$ , are calculated on the basis of the individual attribute utility functions and indifference points for pairs of attributes. These individual tradeoff constants can be calculated as shown below, on the basis of the equivalent pairings from the preceding questions. Although the utility functions actually assessed would normally be used to illustrate this example, it is assumed that each of the individual attribute utility functions is linear in this example. Keeney and Raiffa (1976) illustrate many other examples for these calculations for other conditions.

The multiattribute utility values for assessed points of indifference between pairs of attributes must be equal because they are equally preferable. Holding all attributes not considered in the pair tradeoffs at their worst level so that their utility value is zero, the  $k_i$  values (where the subscript  $i$  is for each attribute) in Equation 8.1 can be calculated. The ratio between the tradeoff constants for any two attributes (such as  $k_2/k_4$ , the ratio of the cost and water quality tradeoff constants) is therefore equal to the utility value of the attributes that is the denominator for this worst-case comparison.

As an example, the water quality attribute value of 650 mg/L TSS relates to the worst case cost attribute value of \$3,600. The corresponding utility value for this water quality attribute value is 0.65, the ratio between the cost and water quality tradeoff constant ( $k_2/k_4$ ). The following relationships show the ratios of the other tradeoff values:

$$\frac{k_2}{k_4} = u_4(650 \text{ mg/L}) = 0.65 \quad (8.2)$$

$$\frac{k_5}{k_2} = u_2(\$3000) = 0.23 \quad (8.3)$$

$$\frac{k_1}{k_2} = u_2(\$3000) = 0.23 \quad (8.4)$$

$$\frac{k_3}{k_2} = u_2(\$1500) = 0.46 \quad (8.5)$$

Using Equation 8.2,

$$\sum_{i=1}^5 k_i = (0.23 + 1.00 + 0.46 + 1.54 + 0.23)k_2 = 1 \quad (8.6)$$

$$k_2 = 0.29 \quad \text{for the annual cost attribute} \quad (8.7)$$

Therefore,

$$k_1 = 0.07 \quad \text{the aesthetics attribute} \quad (8.8)$$

$$k_3 = 0.13 \quad \text{for the air quality attribute} \quad (8.9)$$

$$k_4 = 0.42 \quad \text{for the water quality attribute} \quad (8.10)$$

$$k_5 = 0.07 \quad \text{for the noise level attribute} \quad (8.11)$$

The above tradeoff constant values, the individual attribute utility functions, and the original equation completely define the multiattribute utility function.

The fourth step consists of synthesizing the information. The multiattribute preferences, when combined with the attribute levels associated with each alternative, allow a ranking of the five alternative street cleaning program alternatives. The estimated attribute levels for each alternative shown in Table 78 and the individual attribute utility functions are used to determine  $u_i(x_i)$  for each alternative.

**Table 78. Individual attribute utility values for each alternative**

Alternatives	Aesthetics	Annual cost	Air quality	Water quality	Noise level
1	0.40	0.90	0	0.38	1.00
2	1.00	0	0.80	1.00	1.00
3	0.12	0.90	0.50	0.08	0.71
4	0	1.00	0	0	0.12
5	0.82	0.80	0.50	0.85	0

The information given in Table 78 is then substituted into Equation 8.1 to define the multiattribute utility associated with each alternative. These utility values provide the basis for determining the rank order of the alternatives and the degree to which one alternative is preferred over another. The utility values associated with each alternative are shown in Table 79.

**Table 79. Utility of each alternative**

Alternative	Utility
1	0.52
2	0.66
3	0.42
4	0.30
5	0.72

The most preferred alternative is that with the highest utility value. For this example, Table 79 reveals that alternative five (conventional mechanical street cleaner followed by a flusher, every five days) is the most preferred alternative. This is followed closely by alternative two (conventional mechanical street cleaner, one pass every day). The least desirable was alternative four (flusher, one pass every five days). Again, this is a hypothetical example used to illustrate a procedure that can be used for this type of decision analysis approach; the values used are fictional as are the results of this hypothetical analysis.

Obviously, changes in preferences for the attributes or estimated attribute levels associated with each alternative could alter the order of preference for the alternatives. The decision analysis methodology summarized here would allow such changes to be rapidly investigated by a sensitivity analysis of the rank

order of alternatives. For example, if the tradeoff between annual cost and water quality were changed so that the annual cost is somewhat more important than in the previous tradeoff, alternatives one and two can become equally preferred, but alternative five is still the most preferred. Also, new attributes may be added to the analysis and the alternatives ranked again.

## **Example Decision Analysis Application with Extended WinSLAMM Data Output**

The above example was prepared some time ago when stormwater modeling techniques were still in their infancy, and environmental regulations, especially for stormwater, were not well developed (and when we were very optimistic concerning the benefits of street cleaning). It is now possible, such as with the recent enhancements made to WinSLAMM, to more completely evaluate different stormwater management options that consider a wide variety of conflicting objectives. The following example is based on a recent project and illustrates the procedure from the above discussions (Pitt and Voorhees 2007).

### **Attribute Levels Associated with Different Stormwater Management Programs**

WinSLAMM generates a great deal of information when stormwater management options are evaluated, as previously described. New revisions to the batch processor option in the model make it possible to summarize many of the important attributes in a simple spreadsheet format. The site and corresponding stormwater management options for this example are described below. All costs are in U.S. dollars.

### **Descriptions of Site and Alternative Stormwater Controls**

This example site is a new industrial park in northern Alabama that is about 98 acres (40 ha) in area, comprising about 33.8 acres (13.7 ha) of industrial land, 60.2 acres (24.5 ha) of open space land, and 4.6 acres (1.9 ha) of buffers surrounding sinkholes. There are 13 industrial lots in this subarea, each about 2.6 acres (1.1 ha) in area. The following list shows the estimated total surface covers for these 98 acres:

- Roofs: 18.4 acres (7.5 ha)
- Paved parking: 2.3 acres (0.9 ha)
- Streets (1.27 curb-miles): 3.1 acres (1.3 ha)
- Small landscaped areas (B, or sandy-loam soils, but assumed silty soils because of compaction): 10.0 acres (4.1 ha)
- Large undeveloped area (B or sandy-loam soils, but assumed silty soils because of compaction): 60.2 acres
- Isolated areas (sinkholes): 4.6 acres

The stormwater control options examined in this subarea included the following:

#### *Conventional storm drainage system elements:*

The base conditions (associated with the *Base Conditions, No Controls* option) have conventional curb and gutters with concrete storm drainage pipes, and the roofs and paved parking areas are directly connected to the storm drainage system. The conventional drainage system for base conditions were sized using conventional stormwater drainage system methods (SWMM), and were composed of: 5,200 ft (1,585 m) of 18 in. (460 mm) and 3,360 ft (1,024 m) of 36 in. (910 mm) storm drainage pipe, plus 39 on-site and 45 public street inlets. The estimated costs for these conventional storm drainage elements are from RS Means (2006 publication, 2005 basis) and are \$19 per ft (304 mm) for 18 in. and \$72 per ft for 36-in. reinforced concrete pipe. Excavation and backfilling costs add \$6/yd<sup>3</sup>. The inlets are \$3,000 each.

The on-site drainage elements are needed whenever the site biofilter-swale option is not being used:  
5,200 ft of 18-in. concrete pipe (buried in a 5-ft [1.5 m] deep trench) at \$25/ft = \$130,000  
39 inlets = \$117,000

Total on-site drainage costs: \$247,000 (1996 costs) x 1.2 = \$296,400 (2005 costs, based on ENR index).  
In addition, it is assumed that annual maintenance costs for these drainage elements will be 1% of the total capital costs for each year = \$2,960/y (2005 costs)

The roadside drainage elements are needed whenever the regional swale option is not being used:  
3,360 ft of 36-in. concrete pipe (buried in an 8-ft [2.4 m] deep trench) at \$80/ft = \$268,800  
25 inlets = \$75,000

Total roadside drainage costs: \$343,800 (1996 costs) x 1.2 = \$412,560 (2005 costs, based on ENR index).  
In addition, it is assumed that annual maintenance costs for these drainage elements will be 1% of the total capital costs for each year = \$4,130/y (2005 costs)

These initial costs must be converted to annualized costs. The following is based on the procedures outlined by Narayanan and Pitt (2005) and is the same procedure used in WinSLAMM for calculating the costs of the stormwater controls.

Annual on-site drainage costs:

Interest rate on debt capital = 5%  
Project financing period = 20 years  
Capital cost of project = \$296,400 (2005)  
Annual maintenance cost = \$2,960/year (2005)

$$\text{Annual value of present amount} = \frac{i(1+i)^N}{(1+i)^N - 1}$$

$$\text{Annual value of present amount (or) annual value multiplier} = \frac{0.05(1+0.05)^{20}}{(1+0.05)^{20} - 1} = 0.0806$$

Annualized value of all costs = Annualized value of (total capital cost of project) + annual maintenance and operation cost.

$$= 0.0806 * (\$296,400) + \$2,960 = \$26,850 \text{ per year}$$

Annual roadside drainage costs:

Interest rate on debt capital = 5%  
Project financing period = 20 years  
Capital cost of project = \$412,560 (2005)  
Annual maintenance cost = \$4,130/year (2005)  
Annualized value of all costs = Annualized value of (total capital cost of project) + annual maintenance and operation cost.

$$= 0.0806 * (\$412,560) + \$4,130 = \$37,380 \text{ per year}$$

*On-site biofilter swales:*

These small drainage swales, included in options 3, 6, and 8, collect the on-site water from the roofs and paved areas and direct it to the large natural swales. These have the following general characteristics: 200 ft (61 m) long, with 10 ft (3.1 m) bottom widths, 3 to 1 (H to V) side slopes (or less), and 2 inches (51 mm) per hour infiltration rates. One of these will be used at each of the 13 sites on the site. These



swales will end at the back property lines with level spreaders (broad-crested weirs) to create sheetflow toward the large drainage swale.

When modeling the site biofilters, the following dimensions were used:

- Top area: 4,400 ft<sup>2</sup>
- Bottom area: 2,000 ft<sup>2</sup>
- Depth: 2 ft
- Seepage rate: 2 in/hr
- Peak to average flow ratio: 3.8
- Typical width for cost purposes: 10 ft
- Number of biofilters: 13 (one per site)
- All roofs and all paved parking/storage areas drained to the biofilters

The level spreader at the end of the biofilter was modeled assuming a broad-crested weir having a crest length of 12 ft , a crest width of 10 ft, and the height from the datum to bottom of opening was 1 ft. Table 80 shows the evaporation rates used for this example analyses.

**Table 80. Example monthly average evaporation rates (in/day)**

January	0.01
February	0.03
March	0.06
April	0.08
May	0.12
June	0.25
July	0.25
August	0.15
September	0.08
October	0.06
November	0.03
December	0.01

*Large regional drainage swale:*

Options 2, 5, 6, 7, and 8 include a natural drainage swale in this subarea that will collect the sheetflows from the bioretention swales from each site and direct the excess water to the ponds. This swale is about 1,700 feet long, on about a 2.6% slope, and is 50 ft wide. It has 3 to 1 (H to V) side slopes, or less, and 1 in/hr infiltration rates. The bottom of the swale will be deep vibratory cultivated during proper moisture conditions to increase the infiltration rate, if compacted. This swale also has limestone check dams every 100 ft to add alkalinity to the water and to encourage infiltration. The vegetation in the drainage will be native grasses having deep roots and be mowed to about 6 in., or higher. Any cut grass will be left in place to act as a mulch that will help preserve infiltration rates. The swale will also have a natural buffer on each side at least 50 ft wide.

When modeling this large, regional swale, the model used a swale density of 29 ft/ac with 57 acres served by the swales, resulting in a total swale length of 1,653 ft. The drainage system is composed of 58% grass swales and 42% undeveloped roadside. The infiltration rate in the swale was 1 in/hr. The swale bottom width was 50 ft, with 3H:1V side slopes. The longitudinal slope was 0.026 ft/ft, and Manning’s n roughness coefficient was 0.024. For the cost analysis, the typical swale depth was assumed to be 1 ft.

*Wet detention pond:*

Options 1, 4, 5, 6, 7 and 8 include a wet detention pond across the main road next to the southern property boundary. The regional swale will direct excess water into the pond far from the discharge point. The pond is a wet pond having the approximate dimensions and depths shown in Table 81.

**Table 81. Wet detention pond size and elevation characteristics**

Pond elevation (ft)	Pond area (acres)
1	0.15
2	0.25
3	0.5
4	0.75
5	1.0 (normal pool elevation, and invert elevation of 30° v-notch weir)
6	1.5
7	2
8	2.5 (invert elevation of flood flow broad-crested weir). Normal maximum elevation during one and two year rains.
9	3.0 (approximate maximum pond elevation, or as determined based on flood flow analysis). Additional storage and emergency spillway may be needed to accommodate flows in excess of the design flood flow.

The pond storage between 5 and 9 feet is about 8 acre-ft. If additional storage is needed for flood control, either the pond can be enlarged, or an additional dry pond can be located immediately north of the road crossing of the drainageway upstream of the wet pond.

The normal pool elevation of the pond is at 5 ft, about 4 ft below the ground elevation, with an overall pond excavation of 9 ft. The pond is created by a combination of excavation and a downstream embankment. Accessible forebays are located near each of the flow entrance locations to encourage pre-settling of larger sediment in restricted areas. A safety ledge 6–12 in. underwater also extends out 3–10 ft around the pond perimeter and is planted with a thick stand of emerging vegetation to restrict access to deep water. The edge of the pond along the water is also planted with appropriate vegetation as a barrier. Perimeter plantings also discourage nuisance geese populations. A boardwalk extends through this perimeter vegetation at selected locations for access for demonstration purposes. This boardwalk is also connected with the path system through the industrial park that connects other points of interest for recreational use by site workers.

When modeling the pond, the particle size distribution was assumed to have a median particle size of about 20 µm, with 90% of the particles (by mass) less than 250 µm in diameter. A 4-ft-high 30° v-notch weir 5 ft off the pond bottom was used for water quality control. The emergency spillway was a 50-ft-long broad-crested weir, having a 3 ft width, with 1 ft of freeboard. The same evaporation rates used for the biofilters were also used for the ponds.

**Calculated Performance of Stormwater Control Options**

A typical Huntsville rain year (1976) was used in this analysis. This year had 102 recorded rains ranging from 0.01 to 3.70 in. The total rain recorded was 53.4 in and the average rain depth was 0.52 in.

**Utility Functions for and Tradeoffs between the Different Attributes**

The utility functions and tradeoffs between the different attributes are highly dependent on the local goals and regulations that need to be addressed in a stormwater management program. The following discussion

describes several alternative goals for a hypothetical situation and how the attributes for each option can be evaluated.

*Single Absolute Goal/Limit at Least Cost*

In some cases, a watershed analysis might have been completed that recognizes the critical pollutants and set removal goals. This would especially be relevant for areas attempting to address retrofitting stormwater controls in areas already developed. For new developments, some areas might require an 80% reduction in suspended solids, compared to traditional development. If this was the case, the utility functions for particulate solids would be easily defined as being zero for outcomes that do not meet the reduction goal, and one for outcomes that do meet the reduction goal. The ranking of the options would simply be based on examining only those options that meet this simple goal, possibly by cost of implementation. In this example, outcomes for eight stormwater control programs made up of combinations of the different stormwater controls are shown on Table 82.

**Table 82. Suspended solids reduction goals and costs  
(values in italics meet the numeric criterion of 80% TSS goals)**

Stormwater treatment option	Total annual cost (\$/y)	Reduction in SS Yield (%)	Meet 80% particulate solids reduction goal?	Rank based on annual cost
Option 1 Pond	83,364	86	Yes	5
Option 2 Regional Swale	30,008	55	No	n/a
Option 3 Site Biofilter	69,710	1	No	n/a
Option 4 Half-sized pond	74,439	73	No	n/a
Option 5 Pond and reg. swale	49,142	<i>94</i>	Yes	3
Option 6 Pond, reg. swale and biofilter	54,622	<i>97</i>	Yes	4
Option 7 Small pond and reg. swale	40,217	<i>90</i>	Yes	1
Option 8 Small pond, reg. swale and biofilter	45,698	<i>94</i>	Yes	2

Therefore, using a small pond in conjunction with a regional swale would be the cheapest option to meet the reduction goal of 80% particulate solids removal. The most costly option to meet the particulate solids removal goal is to use a pond with a conventional storm drainage system, at about twice the expected annual cost. In this example, no other attributes of the different stormwater management options are considered. This solution simply meets the single goal at the least cost. In fact, it exceeds the goal (90% TSS removals exceeding the 80% minimum goal). It would therefore be worthwhile to examine slightly smaller ponds that will more closely meet the single target, with some additional cost savings for the pond construction. The simple ranking method shown in this example would also apply for any other situation where there is a single goal that must be met at the least total cost.

*Several Absolute Goals/Limits*

When more than one absolute goal is required to be met, the analysis becomes only slightly more complex. It is still relatively simple with absolute goals; the first step is to filter out the options that do not

meet all the required goals. This situation can occur when water quality numeric standards must be met. As an example, assume that the hypothetical effluent concentration limits shown in Table 83 must be met. The attribute table shows only the flow-weighted concentrations. If standards need to be met for all rains with a specific recurrence probability, those concentrations can be summarized from the probability distributions of outfall concentrations that WinSLAMM can calculate.

**Table 83. Options and specific criteria (values in italics meet numeric criteria)**

	Total annual cost (\$/y)	SS conc. (mg/L)	Part. P conc. (mg/L)	Zn conc. (µg/L)	Meets all numeric standards?	Rank based on annual cost
Hypothetical Numeric Limits:		< 50 mg/L	< 0.2 mg/L	< 400 µg/L		
Option 1-Pond	83,364	<i>30</i>	<i>0.073</i>	<i>128</i>	Yes	6
Option 2 Regional Swale	30,008	178	0.43	390	No	n/a
Option 3 Site Biofilter	69,710	408	1.0	696	No	n/a
Option 4 Half-sized pond	74,439	<i>48</i>	<i>0.12</i>	<i>151</i>	Yes	5
Option 5 Pond and reg. swale	49,142	23	<i>0.057</i>	203	Yes	3
Option 6 Pond, reg. swale and biofilter	54,622	29	<i>0.073</i>	386	Yes	4
Option 7 Small pond and reg. swale	40,217	39	<i>0.095</i>	220	Yes	1
Option 8 Small pond, reg. swale and biofilter	45,698	53	<i>0.13</i>	390	Yes	2

Again, simple filtering enables the suitable options to be identified, and these can be ranked on the basis of their annual cost to identify the least costly option that meets the applicable numeric standards (option 7 again is the least costly option that meets all three hypothetical goals).

#### *Combinations of Goals/Limits*

Things get more complicated as the goals become more involved. In such situations, a more formal decision analysis approach might be worthwhile, possibly as described previously following the Keeney and Raiffa (1976) methods. The goals can be separated into classes:

(i) Specific criteria or limits that must be met. As in the above examples, it is possible to simply filter out (remove) the options that do not meet all the absolutely required criteria. If the options remaining are too few, or otherwise not very satisfying, it might be desirable to continue to explore additional options. The above examples considered combinations of only three types of stormwater control devices, for example. Many others could also be explored. If the options that meet the absolute criteria look interesting and encouraging, it is possible to continue to the next steps. Options 1, 5, 6, 7, and 8 are the five remaining options, after the specific criteria listed above are met.

(ii) Goals that are not absolute. In such a case, utility curves and tradeoffs can be developed for the remaining attributes. The above example includes attributes of several types:

- Costs
- Land requirements

- Runoff volume (volumes, habitat responses, and rates)
- Particulate solids (reductions, yields and concentrations)
- Particulate phosphorus (concentrations)
- Total zinc (concentrations)

In this example, the particulate solids reductions, suspended solids concentrations, particulate phosphorus concentrations, and total zinc concentrations are assumed to have absolute criteria, and only those options that meet them will be further considered. This leaves the attributes, shown in Table 84, that need tradeoffs and utility curves. The rankings and tradeoffs shown on Table 84 were selected for the attributes on the basis of their assumed importance for this project site. These tradeoffs could be expected to vary for different decision makers and other interested parties. Separate analyses can therefore be conducted for each different set of tradeoffs, resulting in slightly different, but hopefully similar, rankings of the options. As noted above, these tradeoffs can be mathematically determined, basically by determining the expected improvements in each attribute for a specific increase in expenditures, and then by solving the set of simultaneous equations. They can also be rather arbitrarily selected, as in this example, by assigning the rankings and values to each attribute so the resultant tradeoff values are summed to equal 1.0.

**Table 84. Ranges of attributes for pre-screened options**

Attribute	Range of attribute value for acceptable options	Attribute ranks for selection (after absolute goals are met)	Tradeoffs between remaining attributes
Total annual cost (\$/year)	\$40,217 to \$83,364	2	0.20
Land needs (acres)	2.3 to 4.5	5	0.08
Rv	0.06 to 0.29	1	0.30
% of time flow > 1 cfs	0.5% to 4 %	7	0.05
% of time flow > 10 cfs	0% to 0.05 %	3	0.18
Particulate solids yield (lbs/y)	2,183 to 10,192	6	0.07
Part. Phosphorus yield (lbs/y)	5.5 to 25	4	0.12
			Sum = 1.0

The utility curve values for these attributes are shown below. For the flow rates and volumetric runoff coefficients, site conditions and local receiving waters enabled groupings of the attribute values into categories having specific utility values. The best categories were intended to protect the receiving water aquatic habitat by minimizing sediment scour and stream enlargement, whereas the poorest categories would be associated with conventional development practices that frequently are associated with severe receiving water problems. The flow rate groupings are very specific to the site, based on local hydrology and hydrologic calculations; the Rv groupings might be more generally applicable. The other utility curves (for cost, phosphorus yield, land needs, and particulate solids yields) are simple straight line relationships, with the best attribute values obtained for the different options assigned a value of 1.0, and the worst attribute values obtained assigned a value of 0.0. Intermediate values are simply interpolated between these extreme values.

- Volumetric runoff coefficient ( $R_v$ ) as an indicator of habitat quality and aquatic biology stress:

Attribute value	Expected habitat condition	Utility value
< 0.1	Good	1.0
0.1–0.25	Fair	0.75
0.26–0.50	Poor	0.25
0.51–1.0	Very poor	0

- Total annual cost: straight line, with \$83,364 = 0 and \$40,217 = 1.0.

- % of time flow > 10 cfs:

% of time flow > 10 cfs	Utility value
< 0.05	1.0
0.05–1	0.75
1.1–2.5	0.25
> 2.5	0

- Part. phosphorus yield (lbs/y): straight line, with 25 lbs/y = 0 and 5.5 lbs/y = 1.0

- Land needs (acres): straight line, with 4.5 acres = 0 and 2.3 acres = 1.0

- Particulate solids yield (lbs/y): straight line, with 10,192 lbs/y = 0 and 2,183 lbs/y = 1.0

- % of time flow > 1 cfs:

% of time flow > 1 cfs	Utility value
< 1	1.0
1–3	0.75
3.1–10	0.25
> 10	0

### Calculation of Utilities and Ranking of Alternative Stormwater Management Programs

At this site, most of the particulate solids originate from the undeveloped areas, so the site biofilters have minimal benefits on reducing the overall particulate solids discharges. Also, the site biofilters infiltrate water having much lower particulate concentrations compared to the undeveloped areas (to minimize clogging), so the resulting outfall concentrations actually increase. The regional swale and detention ponds treat all the site water, so they have a much larger benefit on the particulate solids.

Tables 85 and 86 show the calculated utility factors for each option, along with the sums of the factors and the overall ranking of the options. Option 8, the small pond with the regional swale and the on-site biofilter swale was ranked significantly ahead of the other options. Options 5 (large pond and regional swale) and 7 (small pond and regional swale) ranked next and were basically tied. Option 1, the large pond alone, ranked far below the other options. The factors are calculated by multiplying the utilities by the tradeoff values. As an example, for Option 5, the cost tradeoff was 0.20 and the cost utility was 0.79, and the calculated cost factor is therefore  $0.20 \times 0.79 = 0.158$ . The sum of factors is the sum of the individual factors for all attributes for each option. The ranks are based on the sum of factors, with the largest sum of factors ranked 1.

**Table 85. Utility and tradeoffs for different options**

Stormwater control option	Volumetric runoff coefficient (Rv)	Rv utility	% of time flow > 1 cfs	Mod flow utility	% of time flow > 10 cfs	High flow utility
Tradeoff Value	0.30	0.30	0.05	0.05	0.18	0.18
Option 1 Pond	0.29	0.25	4	0.25	0.05	0.75
Option 5 Pond and reg. swale	0.15	0.75	2	0.75	0	1.0
Option 6 Pond, reg. swale and biofilter	0.06	1.0	0.5	1.0	0	1.0
Option 7 Small pond and reg. swale	0.15	0.75	2	0.75	0.05	0.75
Option 8 Small pond, reg. swale and biofilter	0.07	1.0	0.8	1.0	0	1.0

**Table 85. Utility and tradeoffs for different options (continued)**

Stormwater control option	Total annual cost (\$/yr)	Cost utility	Land needs for SW mgt (acres)	Land utility	Part. solids yield (lbs/yr)	Part. solids utility	Part. phos. yield (lbs/yr)	Phos. utility
Tradeoff value	0.20	0.20	0.08	0.08	0.07	0.07	0.12	0.12
Option 1 Pond	83,364	0	4.5	0	10,192	0	25	0
Option 5 Pond and reg. swale	49,142	0.79	4.5	0	4,133	0.76	10	0.77
Option 6 Pond, reg. swale and biofilter	54,622	0.67	4.5	0	2,183	1.0	5.5	1.0
Option 7 Small pond and reg. swale	40,217	1	2.3	1	6,937	0.41	17	0.41
Option 8 Small pond, reg. swale and biofilter	45,698	0.87	2.3	1	4,125	0.76	10	0.77



**Table 86. Calculations of ranks for different stormwater management options**

Stormwater control option	Rv utility	Rv factor	Mod flow utility	Mod flow factor	High flow utility	High flow factor	Sum of factors	Overall rank
Tradeoff value	0.30		0.05		0.18			
Option 1 Pond	0.25	0.075	0.25	0.0125	0.75	0.135	0.2225	5
Option 5 Pond and reg. swale	0.75	0.225	0.75	0.0375	1.0	0.18	0.7455	4
Option 6 Pond, reg. swale and biofilter	1.0	0.30	1.0	0.05	1.0	0.18	0.8540	2
Option 7 Small pond and reg. swale	0.75	0.225	0.75	0.0375	0.75	0.135	0.7555	3
Option 8 Small pond, reg. swale and biofilter	1.0	0.30	1.0	0.05	1.0	0.18	0.9290	1

**Table 86. Calculations of ranks for different stormwater management options (continued)**

Stormwater Control Option	Cost utility	Cost factor	Land utility	Land factor	Part. utility	Part. factor	Phos. utility	Phos factor
Tradeoff value	0.20		0.08		0.07		0.12	
Option 1 Pond	0	0	0	0	0	0	0	0
Option 5 Pond and reg. swale	0.79	0.158	0	0	0.76	0.053	0.77	0.092
Option 6 Pond, reg. swale and biofilter	0.67	0.134	0	0	1.0	0.07	1.0	0.12
Option 7 Small pond and reg. swale	1	0.20	1	0.08	0.41	0.029	0.41	0.049
Option 8 Small pond, reg. swale and biofilter	0.87	0.174	1	0.08	0.76	0.053	0.77	0.092

## **Summary of Decision Analysis Methods to Assist in the Selection of Stormwater Control Programs**

Stormwater quality models can produce copious amounts of information for large numbers of alternative management programs that contain a wide variety of individual stormwater control practices, as described by Pitt and Clark (2008). In most cases, just a few of the values are sufficient for quick comparisons. These include the overall percent runoff and particulate solids reductions, the final Rv and runoff volume, and the resulting particulate solids yields and concentrations. WinSLAMM also calculates the life-cycle costs and the expected habitat conditions of the receiving waters to be compared, in addition to flow-duration information. The use of decision analysis procedures, based on methods developed by Keeney and Raiffa (1976) with the WinSLAMM batch processor allows semi-automatic formal evaluations of alternative stormwater control programs considering multiple conflicting objectives.

This decision analysis approach has the flexibility of allowing for variable levels of analytical depth, depending on the problem requirements. The preliminary level of defining the problem explicitly in terms of attributes often serves to make the most preferred alternatives clear. The next level of analysis might consist of a first-cut assessment and ranking. Several different utility function curve types can be used with a simple additive model. Spreadsheet calculations with such a model are easily performed, making it possible to conduct several decision analysis evaluations using different tradeoffs, representing different viewpoints. It is possible there will be a small set of options that everyone agrees are the best choices. Also, this procedure documents the process for later discussion and review. Sensitivity analyses can also be conducted to identify the most significant factors that affect the decisions. The deepest level of analysis can use all the analytical information one collects, such as probabilistic forecasts for each of the alternatives and the preferences of experts over the range of individual attributes. Monte Carlo options available in WinSLAMM can also be used that consider the uncertainties in the calculated attributes for each option.

Therefore, decision analysis has several important advantages. It is very explicit in specifying tradeoffs, objectives, alternatives, and sensitivity of changes to the results. It is theoretically sound in its treatment of tradeoffs and uncertainty. Other methods ignore uncertainty and often rank attributes in importance without regard to their ranges in the problem. This decision analysis procedure can be implemented flexibly with varying degrees of analytical depth, depending on the requirements of the problem and the available resources.

## 9. Conclusions

WinSLAMM has been undergoing development and changes since the mid-1970s and now includes a wide range of options. Over the years, periodic major upgrades have occurred to take advantage of advancing computer capabilities and knowledge gained through stormwater research, and to respond to requests by users.

The expected major sources of runoff from the test area vary for different rain depth categories. A detailed land survey found that most of the homes in the test watershed already have disconnected roofs (85% of all roof areas) and that the total roof areas account for 13% of the total study area. The directly connected roofs, which make up only 2% of the study area, contribute 6% of the total annual flows. The disconnected roofs, which constitute 11% of the area, contribute 7% of the total flows. Thus, complete control of the runoff from the directly connected roofs would reduce the total area runoff by only a very small amount, less than can be reliably detected by monitoring the total runoff from the area. The modeling calculations illustrate the different effects of using rain gardens, rain barrels or tanks, or simple disconnections of the directly connected roofs. The results are presented on the basis of the effects for the directly connected roofs alone; if calculated for the whole drainage area, the contribution would be less than 5%. If all the roofs were directly connected, they would then contribute 30% of the annual flows, and the outfall consequences for the entire area from these roof controls would be substantially larger.

Performance plots were prepared comparing the size of rain gardens to the roof areas to result in expected roof runoff flow reductions. Rain gardens that are 20% of the roof areas are expected to result in about 90% reductions of the total annual flow compared to directly connected roofs. This rain garden size is about 200 ft<sup>2</sup>/house (about 20 m<sup>2</sup>/house) which could, for example, be composed of several smaller rain gardens each located at a downspout. Reductions of 50% in the total annual flows could be obtained if the total rain garden area per house was 7% of the roof area.

Rain barrel effectiveness is related to the need for supplemental irrigation and how that matches the rains for each season, or the use of water-resistant plants. The continuous simulations used a typical 1-year rain series and average monthly ET values for varying amounts of roof runoff storage. One 35-gal (133 L) rain barrel is expected to reduce the total annual runoff by 24% from the directly connected roofs, if the water use can be closely regulated to match the irrigation requirements. If four rain barrels were used (such as one on each corner of a house and receiving runoff from separate roof downspouts), the total annual roof volume reductions could be as high as 40%. Larger storage quantities result in increased usage but likely require larger water tanks. A small tank 5 ft (1.5 m) diameter and 6 ft (1.8 m) high is expected to result in 75% total annual runoff reductions, while a larger 10 ft (3 m) diameter tank 6 ft (1.8 m) tall would approach complete roof runoff control.

Using rain barrels and rain gardens together at a home is more effective than using either method alone: the rain barrels would overflow into the rain gardens, so their irrigation use is not quite as critical. To obtain reductions of 90% in the total annual runoff, it is necessary to have at least one rain garden/house, unless the number of rain barrels more than 25 (or one small water tank)/house. In such a case, the rain gardens can be reduced to 80 ft<sup>2</sup>/house (7 m<sup>2</sup>/house).

The best combination of control options is not necessarily obvious. The CSO control program must meet permit requirements, which specify certain amounts of upland storage in the watershed. Other elements, including costs, aesthetics, improvements to streetside infrastructure, and other potential benefits, must also need to be considered in a decision analysis framework. Caution is needed when comparing the amount of site runoff storage provided by these upland controls to the total storage goals to meet the objective of the CSO control program (288,000 gal). As an example, storage provided at directly connected roofs needs to be discounted by a factor of about 1.4 because not all the storage is available

during all rains, and because their drainage is influenced by low infiltration rates through the native soils, compared to flow controls directly connected to the combined sewers. In addition, the curb-cut biofilters also have access to almost all the flows in the area, so their storage volumes are more effectively used. More significantly, if storage was provided at roofs that are already disconnected, their storage volumes would need to be discounted by a factor of 4.5 when compared to the total site storage goals because of the existing infiltration already occurring from the disconnected roofs.

Cost-effective designs of biofilters for the area can be identified by examining the production functions provided in this report. For slowly infiltrating native subsoils (less than 1 in/hr), the use of additional subsurface storage and restricted underdrains can be very beneficial. For higher rate soils, these features have minimal benefit on performance. The biofilters being about 1.5 to 2% of the drainage area in the residential area are expected to provide about 90% long-term reductions in stormwater runoff to the combined sewer for the areas treated. However, only about half of the test (pilot) watershed received runoff control, so the overall runoff volume reduction benefit is expected to be about 40 to 50%. Subsurface drainage water from the biofilters undergo substantial retention (several hours) which would benefit peak combined sewer flows, but the volume affected is relatively small.

## Considerations That Affect Use of Different Stormwater Controls

Certain site conditions could restrict the applicability of some of these controls. The following comments are mostly summarized from Pitt et al. (2008a) and from preliminary research reported by others at recent technical conferences.

### **Sodium Adsorption Ratio (SAR)**

The SAR can radically degrade the performance of an infiltration device, especially when clays are in the media or underlying soils. Media or soils with an excess of sodium ions, compared to calcium and magnesium ions, remain in a dispersed condition, and are almost impermeable to rain or applied water. A *dispersed* soil is extremely sticky when wet, tends to crust, and becomes very hard and cloddy when dry. Water infiltration is therefore severely restricted. Dispersion caused by sodium can result in poor physical soil conditions and water and air do not readily move through the soil. An SAR value of 15 or greater indicates that an excess of sodium will be adsorbed by the soil clay particles. This can cause the soil to be hard and cloddy when dry, to crust badly, and to take water very slowly. SAR values near 5 can also cause problems, depending on the type of clay present. Montmorillonite, vermiculite, illite, and mica-derived clays are more sensitive to sodium than other clays. Additions of gypsum (calcium sulfate) to the soil can be used to free the sodium and allow it to be leached from the soil in some situations, but recent laboratory tests with biofilter media at UA indicate minimal improvement.

The SAR is calculated by using the concentrations of sodium, calcium, and magnesium (in meq) in the following formula:

$$SAR = \frac{Na^+}{\sqrt{\frac{(Ca^{+2} + Mg^{+2})}{2}}}$$

SAR has been documented to be causing premature failures of biofiltration devices in northern communities, such as several in the Madison, Wisconsin, area documented by University of Wisconsin soil science student projects. These failures occur when snowmelt water is allowed to enter a biofilter that has clay in the soil mixture. To minimize this failure potential, the following are recommended:

1. Do not allow snowmelt water to enter a biofilter unit. As an example, roof runoff likely has little salt and SAR problems seldom occur for roof runoff rain gardens, even in areas having large

amounts of clay in the soil. However, if driveway or walkway runoff waters affected by saline deicing chemicals are discharged to these devices, problems can occur. The largest problem is associated with curb-cut biofilters or parking lot biofilters in areas with snowmelt entering these devices, especially if clay is in the engineered backfill soil/media.

2. The biofilter media should not have any clay. It appears that even a small percent of clay in the media can cause a problem, but little information is available on the tolerable clay content of biofilter soils. Some biofilter guidance documents recommend an appreciable clay content to slow the water infiltration rate (and therefore increase the hydraulic detention time in the system) to improve pollutant capture. Instead of clay used to control the infiltration rates, restrictive underdrains, such as the SmartDrain™, should be used. Guidance documents recommending fines in the biofilter mixture are usually from areas having mild climates with little or no snowmelt (and deicing chemical use).
3. The most robust engineered soil mixtures used in biofilters tend to be mixtures of sand and an organic material (such as compost, if nutrient leaching is not a concern, or Canadian peat for a more stable material having little nutrient leaching potential). Other mixtures of biofilter media can be used targeting specific pollutants, but these are usually expensive and likely only appropriate for special applications.
4. If a suitable soil mixture not having clay (should be less than 3% based on preliminary information), and if snowmelt water will affect the system, biofilters should not be used in the area. As noted above, rain gardens receiving only roof runoff might be suitable in most situations because of the absence of excessive sodium in the runoff water.

The Kansas City biofilter media is being further tested, but it appears to have minimal amounts of clays. It is expected that system monitoring during the winter and spring will enable decreased performance to be detected, if present.

### ***Clogging of Infiltration Devices***

The designs of infiltration devices need to be checked on the basis of their clogging potential. For example, a relatively small and highly efficient biofilter (especially in an area having a high native infiltrating rate) could capture a large amount of sediment. Having a small surface area, this sediment would accumulate rapidly over the area, possibly reaching a critical clogging load early in its design lifetime. Therefore, the clogging potential can be calculated according to the predicted annual discharge of suspended solids to the biofiltration device and the desired media replacement interval. Infiltration and bioretention devices might show significantly reduced infiltration rates after about 2 to 5 lb/ft<sup>2</sup> (10 to 25 kg/m<sup>2</sup>) of particulate solids have been loaded (Clark 1996, 2000; Urbonas 1999). Deeply rooted vegetation and a healthy soil structure can extend the actual life much longer. However, abuse (especially compaction and excessive siltation) can significantly reduce the life of the system. If this critical load accumulates relatively slowly (taking about 10 or more years to reach this total load) and if healthy vegetation with deep roots are present, the infiltration rate might not significantly degrade because of the plant's activities in incorporating the imported sediment into the soil column. If this critical load accumulates in just a few years, or if healthy vegetation is not present, the premature failure from clogging can occur. Therefore, relatively large surface areas might be necessary in areas having large sediment content in the runoff, or suitable pretreatment to reduce the sediment load before entering the biofilter or infiltration device would be necessary.

For some of the calculated Kansas City biofilter size options, the sediment loading rates are high (mostly because of treatment of relatively large areas compared to the size of the biofilters), which could result in premature failure if the minimum sizes were used according to infiltration goals alone. Therefore, a larger area might actually be needed to prevent premature failure from clogging. The following considerations apply to infiltration/biofiltration devices to minimize clogging failure:

1. Use a sufficient infiltration area to enable at least 10 years before the critical sediment loading (10 to 25 kg/m<sup>2</sup>) occurs, and maintain a healthy, deep-rooted plant community to incorporate the sediment into the soil horizon.
2. Use pretreatment to reduce the sediment load entering a biofilter to reduce the TSS concentrations to match the desired maintenance or clogging interval. Using a grass filter/grass swale before a biofilter can significantly reduce the loading to the device, extending the operational life.

The characteristics for the Kansas City biofilters in the test area indicate that most are likely sufficiently sized to result in minimal clogging potential. However, there might be a desire to reduce the sizes appreciably during future construction to reduce costs, which could result in early failure.

### ***Groundwater Contamination Potential and Over-Irrigation***

The potential for infiltrating stormwater to contaminate groundwater is dependent on the concentrations of the contaminants in the infiltrating stormwater and how effective those contaminants might travel through the soils and vadose zone to the groundwater. Source stormwater from residential areas are not likely to be contaminated with compounds having significant groundwater contaminating potential (with the exception of high-salinity snowmelt). In contrast, commercial and industrial areas are likely to have greater concentrations of contaminants of concern that might adversely affect the groundwater. Therefore, pretreatment of the stormwater before infiltration might be necessary, or treatment media can be used in a biofilter or as a soil amendment to hinder the migration of the stormwater contaminants of concern to the groundwater. Again, these concerns are usually more of a problem in industrial and commercial areas than in residential areas.

Pitt et al. (2010a) summarized prior research on potential groundwater contamination. Table 87 can be used for initial estimates of contamination potential of stormwater affecting groundwater. This table includes likely worst-case mobility conditions using sandy soils having low organic content. If the soil is clayey or has a high organic content, or both, most of the organic compounds would have less mobility than shown. The abundance and filterable fraction information is generally applicable for warm-weather stormwater runoff at residential and commercial area outfalls. The concentrations and detection frequencies would likely be greater for critical source areas (especially vehicle service areas) and critical land uses (especially manufacturing industrial areas), with greater groundwater contamination potential.

**Table 87. Groundwater contamination potential for stormwater pollutants post-treatment**

Compound class	Compounds	Subsurface injection with minimal pretreatment	Surface infiltration with sedimentation*	Surface infiltration and no pretreatment*
Nutrients	Nitrates	Low/moderate	Low/moderate	Low/moderate
Pesticides	2,4-D	Low	Low	Low
	γ-BHC (lindane)	Moderate	Low	Moderate
	Atrazine	Low	Low	Low
	Chlordane	Moderate	Low	Moderate
	Diazinon	Low	Low	Low
Other organics	VOCs	Low	Low	Low
	1,3-dichlorobenzene	Low	Low	<b>High</b>
	Benzo(a) anthracene	Moderate	Low	Moderate
	Bis (2-ethyl-hexyl) phthalate	Moderate	Low?	Moderate
	Fluoranthene	Moderate	Moderate	<b>High</b>
	Naphthalene	Low	Low	Low
	Phenanthrene	Moderate	Low	Moderate
	Pyrene	Moderate	Moderate	<b>High</b>
Pathogens	Enteroviruses	<b>High</b>	<b>High</b>	<b>High</b>
	<i>Shigella</i>	Low/moderate	Low/moderate	<b>High</b>
	<i>P. aeruginosa</i>	Low/moderate	Low/moderate	<b>High</b>
	Protozoa	Low	Low	<b>High</b>
Heavy metals	Cadmium	Low	Low	Low
	Chromium	Low/moderate	Low	Moderate
	Lead	Low	Low	Moderate
	Zinc	Low	Low	<b>High</b>
Salts	Chloride	<b>High</b>	<b>High</b>	<b>High</b>

Source: modified from Pitt et al. 1994

Notes: Overall contamination potential (the combination of the subfactors of mobility, abundance, and filterable fraction) is the critical influencing factor in determining whether to use infiltration at a site. The ranking of these three subfactors in assessing contamination potential depends of the type of treatment planned, if any, before infiltration.

\* Even for those compounds with low contamination potential from surface infiltration, the depth to the groundwater must be considered if it is shallow (1 m or less in a sandy soil). Infiltration might be appropriate in an area with a shallow groundwater table if maintenance is sufficiently frequent to replace contaminated vadose zone soils.

Therefore, groundwater contamination potential of infiltrating stormwater can be reduced by

1. Careful placement of the infiltrating devices and selection of the source waters. Most residential stormwater is not highly contaminated with the problematic contaminants, except for chlorides associated with snowmelt.
2. Commercial and industrial area stormwater would likely need pretreatment of reduce the potential of groundwater contamination associated with stormwater. The use of specialized media in the biofilter, or external pretreatment might be needed in these other areas.

The Kansas City test area is expected to have minimal groundwater contamination potential because it has relatively uncontaminated stormwater, and the soil has appreciable clay. However, snowmelt salts could be a problem if deicing salt use is not restricted in the area.



### **Retrofitting and Availability of Land**

Most of the control options being used in GI approaches to minimize combined sewer problems are retrofitted in existing urban areas. Their increased costs and availability of land can be detrimental in developing highly effective control programs. The selection and construction of stormwater controls at the time of development (rather than retrofits) is usually much more cost-effective and can provide a higher level of control. However, many controls can be retrofitted into existing areas. Practices that can usually be easily retrofitted get the most attention in stormwater management program in existing areas. Table 88 summarizes some of the problems associated with different stormwater retrofitting options in combined sewer areas.

**Table 88. Retrofitting problems for different stormwater management options**

<b>Controls</b>	<b>Ability to retrofit</b>	<b>Land requirements</b>
<b>Roof Runoff Controls</b>		
Rain Gardens	Easy in areas having landscaping	Part of landscaping area
Disconnections	Suitable only if the adjacent pervious area is adequate (mild slope and long travel path)	Part of landscaping area
Rain Barrels and Water Tanks	Easy if placed close to a building or underground large tanks	Supplements landscaping irrigation, no land requirements
<b>Pavement Controls</b>		
Disconnections	Suitable only if the adjacent pervious area is adequate (mild slope and long travel path)	Most large paved areas are not adjacent to suitable large turf areas, except for schools; no additional land requirements, but land is needed.
Biofiltration/bioinfiltration	Easy if one can rebuild parking lot islands as bioinfiltration areas; perimeter areas also possible (especially good if existing stormwater drainage system can be used to easily collect overflows)	Part of landscaped islands in parking areas, along parking area perimeters, or sacrifice some existing parking areas.
Porous Pavement	Difficult as a retrofit; must replace complete pavement system; possible if during rebuilding effort	Uses parking area
<b>Street Side Drainage Controls</b>		
Grass Swales	Difficult to retrofit. Suitable if existing swales are to be rebuilt.	Part of street right of way
Curb-Cut Biofilters	Difficult to retrofit, but much easier than simple swales. Usually build to work with existing drainage system. Can do extensions into parking lanes/shoulders to increase areas.	Part of street right of way, but can be major nuisance during construction and can consume street side parking. Can be used to rebuild street edge and improve aesthetics.

The range of difficulties and land requirements varies, mostly depending on available opportunities. In some communities, extensive retrofitting is occurring, including installing curb-cut biofilters, during scheduled street improvement projects. These can also be installed during scheduled repaving and sidewalk repairs that usually occur in many areas every few decades. Rain gardens are usually installed by the homeowners with no cost to the city. Many areas have organized efforts encouraging these, for example. Redevelopment and new construction periods are the most suitable times for installing many of these controls to have the least interferences with residents and for the least costs.

## 10. References

- APWA (American Public Works Association). 1992. *A Study of Nationwide Costs to Implement Municipal Storm Water Best Management Practices*. American Public Works Association, Southern California Chapter, Water Resource Committee.
- Bannerman, R., K. Baun, M. Bohn, P.E. Hughes, and D.A. Graczyk. 1983. *Evaluation of Urban Nonpoint Source Pollution Management in Milwaukee County, Wisconsin*, Vol. I. PB 84-114164. U.S. Environmental Protection Agency, Water Planning Division, Washington, DC.
- Bochis, C., R. Pitt, and P. Johnson. 2008. Land development characteristics in Jefferson County, Alabama. In *Stormwater and Urban Water Systems Modeling*, Monograph 16, ed. W. James, E.A. McBean, R.E. Pitt, and S.J. Wright. CHI. Guelph, Ontario, pp. 249–282.
- Brown, W., and T. Schueler. 1997. *The Economics of Storm Water BMPs in the Mid-Atlantic Region*. Center for Watershed Protection, Ellicott City, MD.
- Clark, S.E. 1996. *Evaluation of Filtration Media for Stormwater Runoff Treatment*. Master's thesis. University of Alabama at Birmingham, Birmingham, AL.
- Clark, S.E. 2000. *Urban Stormwater Filtration: Optimization of Design Parameters and a Pilot-Scale Evaluation*. Ph.D. Dissertation, University of Alabama at Birmingham, Birmingham, AL.
- Clark, S.E., and R. Pitt. 2008. Comparison of stormwater solids analytical methods for performance evaluation of manufactured treatment devices. *Journal of Environmental Engineering*.
- Clark, S.E., and C.S. Siu. 2008. Measuring solids concentration in Stormwater runoff: comparison of analytical methods. *Environmental Science and Technology* 42:511–516.
- Clark, S.E., C.Y.S. Siu, R. Pitt, C.D. Roennings, and D.P. Treese. 2008. Peristaltic pump autosamplers for solids measurement in stormwater runoff. *Water Environment Research* 80.
- Frank, J. 1989. *The Costs of Alternative Development Patterns: A Review of the Literature*. Urban Land Institute, Washington, DC.
- Gregory, J.H., M.D. Dukes, P.H. Jones, and G.L. Miller. 2006. Effect of urban soil compaction on infiltration rate. *Journal of Soil and Water Conservation* 61(3):117–123.
- Heaney, J.P., D. Sample, and L. Wright. 2002. *Costs of Urban Stormwater Control*. EPA Contract No. 68-C7-0011. U.S. Environmental Protection Agency, National Risk Management Research Laboratory Office of Research and Development, Cincinnati, OH.
- Johnson, P.D., R. Pitt, S.R. Durrans, M. Urrutia, and S. Clark. 2003. Metals Removal Technologies for Urban Stormwater. *Water Environment Research Foundation*. WERF 97-IRM-2. ISBN: 1-94339-682-3. Alexandria, VA.
- Keeney, R.L., and H. Raiffa. 1976. *Decision Analysis with Multiple Conflicting Objectives*. John Wiley & Sons, New York.
- Kirby, J.T., S.R. Durrans, R. Pitt, and P.D. Johnson. 2005. Hydraulic resistance in grass swales designed for small flow conveyance. *Journal of Hydraulic Engineering* 131(1).
- Means, R.S. 2006. *RS Means Building Construction Cost Data*, 64th ed. Reed Publications.

- Muthukrishnan, S., B. Madge, A. Selvakumar, R. Field, and D. Sullivan. 2006. *The Use of Best Management Practices (BMPs) in Urban Watersheds*. ISBN No. 1-932078-46-0. U.S. Environmental Protection Agency, National Risk Management Research Laboratory Office of Research and Development, Cincinnati, OH.
- Nara, Y., and R. Pitt. 2005. *Alabama Highway Drainage Conservation Design Practices - Particulate Transport in Grass Swales and Grass Filters*. University of Alabama, University Transportation Center for Alabama, Tuscaloosa, AL.
- Nara, Y., R. Pitt, S.R. Durrans, and J. Kirby. 2006. Sediment transport in grass swales. In *Stormwater and Urban Water Systems Modeling*. Monograph 14, ed. W. James, K.N. Irvine, E.A. McBean, and R.E. Pitt. CHI. Guelph, Ontario, pp. 379–402.
- Narayanan, A., and R. Pitt. 2005. *Costs of Urban Stormwater Control Practices*. Stormwater Management Authority of Jefferson County, AL.
- Pitt, R. 1979. *Demonstration of Nonpoint Pollution Abatement Through Improved Street Cleaning Practices*, EPA-600/2-79-161. U.S. Environmental Protection Agency, Cincinnati, OH.
- Pitt, R. 1986. The Incorporation of Urban Runoff Controls in the Wisconsin Priority Watershed Program. In *Advanced Topics in Urban Runoff Research*, ed. B. Urbonas and L.A. Roesner. Engineering Foundation and ASCE, New York, pp. 290–3136.
- Pitt, R. 1987. *Small Storm Urban Flow and Particulate Washoff Contributions to Outfall Discharges*. Ph.D. dissertation. Department of Civil and Environmental Engineering, University of Wisconsin, Madison.
- Pitt, R. 1997. Unique Features of the Source Loading and Management Model (SLAMM). In *Advances in Modeling the Management of Stormwater Impacts*, Volume 6, ed. W. James. Computational Hydraulics International, Guelph, Ontario and Lewis Publishers/CRC Press, pp. 13–37i.
- Pitt, R. 1999. Small storm hydrology and why it is important for the design of stormwater control practices. In *Advances in Modeling the Management of Stormwater Impacts*, Volume 7, ed. W. James. Computational Hydraulics International, Guelph, Ontario and Lewis Publishers/CRC Press.
- Pitt, R., and M. Bozeman. 1982. *Sources of Urban Runoff Pollution and Its Effects on an Urban Creek*, EPA-600/S2-82-090, PB 83-111-021. U.S. Environmental Protection Agency, Cincinnati, OH.
- Pitt, R., and G. Shawley. 1982. *A Demonstration of Non-Point Source Pollution Management on Castro Valley Creek*. Alameda County Flood Control and Water Conservation District and the U.S. Environmental Protection Agency, Water Planning Division (Nationwide Urban Runoff Program), Washington, DC.
- Pitt, R., and P. Bissonnette. 1984. *Bellevue Urban Runoff Program, Summary Report*. PB84 237213. U.S. Environmental Protection Agency, Water Planning Division, and the Storm and Surface Water Utility, Bellevue, WA.
- Pitt, R., and J. McLean. 1986. *Humber River Pilot Watershed Project*, Ontario Ministry of the Environment, Toronto, Canada.

- Pitt, R., J. Lantrip, R. Harrison, C. Henry, and D. Hue. 1999. *Infiltration through Disturbed Urban Soils and Compost-Amended Soil Effects on Runoff Quality and Quantity*. U.S. Environmental Protection Agency, Water Supply and Water Resources Division, National Risk Management Research Laboratory. EPA 600/R-00/016. Cincinnati, Ohio. 231 pgs. Pitt, R., and J. Voorhees. 2002. SLAMM, the Source Loading and Management Model. In *Wet-Weather Flow in the Urban Watershed*, ed. R. Field and D. Sullivan). CRC Press, Boca Raton. FL, pp. 103–139.
- Pitt, R., R. Bannerman, S. Clark, and D. Williamson. 2005a. Sources of pollutants in urban areas (Part 1) – Older monitoring projects. In *Effective Modeling of Urban Water Systems*, Monograph 13, ed. W. James, K.N. Irvine, E.A. McBean, and R.E. Pitt. CHI. Guelph, Ontario, pp. 465–484 and 507–530.
- Pitt, R., R. Bannerman, S. Clark, and D. Williamson. 2005b. Sources of pollutants in urban areas (Part 2) – Recent sheetflow monitoring results. In *Effective Modeling of Urban Water Systems*, Monograph 13, ed. W. James, K.N. Irvine, E.A. McBean, and R.E. Pitt. CHI. Guelph, Ontario, pp. 485–530.
- Pitt, R., D. Williamson, and J. Voorhees. 2005c. Review of historical street dust and dirt accumulation and washoff data. *Effective Modeling of Urban Water Systems*, Monograph 13, ed. W. James, K.N. Irvine, E.A. McBean, and R.E. Pitt. CHI. Guelph, Ontario, pp 203 – 246.
- Pitt, R., and J. Voorhees. 2007. Using decision analyses to select an urban runoff control program. Chapter 4 in *Contemporary Modeling of Urban Water Systems*. ISBN 0-9736716-3-7, Monograph 15, ed. W. James, E.A. McBean, R.E. Pitt, and S.J. Wright. CHI. Guelph, Ontario, pp 71–107.
- Pitt, R., and S.E. Clark. 2008. Integrated stormwater management for watershed sustainability. *Journal of Irrigation and Drainage Engineering* 134(5):548–555.
- Pitt, R., J. Voorhees, and S. Clark. 2008a. Evapotranspiration and related calculations for stormwater biofiltration devices: Proposed calculation scenario and data. In *Stormwater and Urban Water Systems Modeling*, Monograph 16, ed. W. James, E.A. McLean, R.E. Pitt, and S.J. Wright. CHI. Guelph, Ontario, pp. 309–340.
- Pitt, R., S.-E. Chen, S.E. Clark, J. Lantrip, and C.K. Ong. 2008b. Compaction’s impacts on urban stormwater infiltration. *Journal of Irrigation and Drainage Engineering* 134(5):652–658.
- Pitt, R., and J. Voorhees. 2009. Green infrastructure performance modeling with WinSLAMM. 2009 *World Environmental and Water Resources Congress Proceedings*, Kansas City, MO, May 18–22, 2009.
- Pitt, R., Y. Nara, J. Kirby, and S.R. Durrans. 2009. Particulate transport in grass swales. In *Low Impact Development; New and Continuing Applications*, ed. Michael Clar. ISBN 978-0-7844-1007-3. ASCE, Reston, VA, pp. 191–204.
- Pitt, R., and J. Voorhees. 2010. Modeling green infrastructure components in a combined sewer area. In *Modeling Urban Water Systems*. Monograph 18, ed. W. James, E.A. McBean, R.E. Pitt, and S.J. Wright). CHI. Guelph, Ontario,
- Pitt, R., S.E. Clark, and R. Field. 2010a. Groundwater contamination potential from infiltration of urban stormwater runoff. ISBN: 978-0-7844-1078-3. ASCE/EWRI Technical Committee Report Effects of Urbanization on Groundwater: An Engineering Case-Based Approach for Sustainable Development, ed. Ni-Bin Chang. ASCE Press, Reston, VA.

- Pitt, R., S. Clark, and B. Steets. 2010b. Evaluation of the contaminant removal potential of biofiltration media. *2010 International Low Impact Development Conference: Redefining Water in the City*. San Francisco, CA, April 11–14, 2010.
- Pitt, R., and J. Voorhees. 2011. Modeling green infrastructure components in a combined sewer area. Monograph 19. ISBN 978-0-9808853-4-7. *Modeling Urban Water Systems. Cognitive Modeling of Urban Water Systems*, ed. James, W., K.N. Irvine, James Y. Li, E.A. McBean, R.E. Pitt, and S.J. Wright. Computational Hydraulics International, Guelph, Ontario, pp. 139–156.
- Pitt, R., L. Talebi, R. Bean, and S. Clark. 2011b. *Stormwater Non-Potable Beneficial Uses and Effects on Urban Infrastructure*, Water Environment Research Foundation, Report No. INFR3SG09. Alexandria, VA.
- Pitt, R., J. Voorhees, and C. Burger. 2012. Simple hydrograph shapes for urban stormwater water quality analyses. In *Modeling of Urban Water Systems*, Monograph 20, ed. James, W., K.N. Irvine, James Y. Li, E.A. McBean, R.E. Pitt, and S.J. Wright. ISBN 978-0-9808853-7-8. Computational Hydraulics International, Guelph, Ontario, pp. 279–302.
- Pitt, R., and L. Talebi. 2012. *Evaluation and Demonstration of Stormwater Dry Wells and Cisterns in Milburn Township, New Jersey*. Prepared for PARS Environmental, Inc., and Urban Watershed Management Branch, U.S. Environmental Protection Agency.
- Sample, D.J., J.P.Heaney, L.T.Wright, C.Y.Fan, F.H.Lai, and R.Field. 2003. Cost of best management practices and associated land for urban stormwater control. *Journal of Water Resources Planning and Management* 129(1):59-68.
- Selbig, W.R., and R.T. Bannerman. 2008. *A comparison of runoff quantity and quality from two small basins undergoing implementation of conventional- and low-impact-development (LID) strategies: Cross Plains, Wisconsin, water years 1999–2005*: U.S. Geological Survey Scientific Investigations Report 2008–5008.
- Selbig, W.R., and N. Balster. 2010. *Evaluation of turf-grass and prairie-vegetated rain gardens in a clay and sand soil, Madison, Wisconsin, water years 2004–08*: U.S. Geological Survey Scientific Investigations Report 2010–5077.
- SEWRPC (Southeastern Wisconsin Regional Planning Commission). 1991. *Costs of Urban Nonpoint Source Water Pollution Control Measure*. Southeastern Wisconsin Regional Planning Commission, Waukesha, WI.
- Sileshi, R., R. Pitt, and S. Clark. 2010. Enhanced biofilter treatment of stormwater by optimizing the residence time. *2010 International Low Impact Development Conference: Redefining Water in the City*. April 11–14, 2010, San Francisco, CA. Conference CD.
- Sileshi, R., Pitt, R., and Clark, S. 2012a. Assessing the Impact of Soil Media Characteristics on Stormwater Bioinfiltration Device Performance: Lab and Field Studies, ASCE/EWRI, *Proceedings of the 2012 World Environmental and Water Resources Congress*, May 2012, pp. 3505-3516.
- Sileshi, R., R. Pitt, S. Clark, and C. Christian. 2012b. Laboratory and Field Studies of Soil Characteristics of Proposed Stormwater Bioinfiltration Sites. Water Environment Federation (WEF) Stormwater Symposium 2012. July 18-20, 2012. Baltimore, MD.

- Struck, S.D. 2009. Green infrastructure for CSO control in Kansas City, Missouri. *2009 Water Environment Federation Technical Exposition and Conference*, Orlando, FL, October 11–14, 2009. Conference CD.
- Thompson, A.M., A.C. Paul, and N.J. Balster. 2008. Physical and Hydraulic Properties of Engineered Soil Media for Bioretention Basins. *Transactions of the American Society of Agricultural Engineers* 51(2):499-514.
- Urbonas, B.R. 1999. Design of a sand filter for stormwater quality enhancement. *Water Environment Research* 71(1):102–112.
- USEPA (U.S. Environmental Protection Agency). 1983. *Results of the Nationwide Urban Runoff Program*. PB 84-185552. U.S. Environmental Protection Agency, Water Planning Division, Washington, DC.
- Wiegand, C., T. Schueler, W.Chittenden, and D.Jellick. 1986. Cost of urban runoff quality controls. In *Urban Runoff Quality*. Engineering Foundation Conference, Henniker, NH, June 23–27, 1986, pp. 366–380 i.
- Wossink, A., and B. Hunt. 2003. *An Evaluation of Cost and Benefits of Structural Stormwater Best Management Practices in North Carolina*. North Carolina State University.

## **APPENDICES**

Modeling of Green Infrastructure Components and Large-Scale Test and Control Watersheds at Kansas City, MO




## Contents

Appendix A: Monitored Biofilter Site Descriptions.....	3
1. Curb Extension with BR - 1324 E 76th St. ....	3
2. Curb Extension with Bioretention - 1325 E 76th St. ....	9
3. Curb Extension with BR - 1419 E 76th Terr.....	15
4. Rain Garden Extension - 1612 E 76 <sup>th</sup> St.....	22
5. Rain Garden Extension - 1336 E 76 <sup>th</sup> St.....	27
6. Site #6 was abandoned and is not being monitored .....	31
7. <i>Shallow Bioretention Device w/ Smart Drain - 1140 E 76th Terr.</i> .....	31
8. Rain Garden w/ Smart Drain - 1222 E 76 <sup>th</sup> St.....	36
9. Cascade - 1112 E 76th Terr. ....	42
10. Private rain garden - 1312 E. 79 <sup>th</sup> St. - Mrs. Thomas .....	47
11. 1505 E 76 <sup>th</sup> St, #11; Mrs. Moss rain garden (no details); level recorders for inlet and bottom of garden).....	49
Appendix B: Details of typical stormwater controls in test area .....	50
Appendix B-1. Rain garden typical details for residential streets.....	51
Appendix B-2. Shallow bioretention device typical details for residential streets.....	52
Appendix B-3. Cascade rain garden typical details for residential streets .....	54
Appendix B-3. Cascade rain garden typical details for residential streets (continued).....	55
Appendix C: Measured Infiltration Rates in Biofilters .....	56
Appendix D: Large-Scale Combined Sewer Monitoring Data (based on Tetra Tech Compilations from KCMO and UMKC Data) .....	120
Appendix E: Residential Area Production Function Calculations using WinSLAMM .....	155

## Appendix A: Monitored Biofilter Site Descriptions

### 1. Curb Extension with BR - 1324 E 76th St.



**DRAFT**

Location	Urban Classification	Area (ac)	Note
Figure 1-b	Driveway	0.04524	There is no overflow from upstream as shown in Figure 1-b.
	Landscaped area	0.246	
	Roof	0.07541	
	Sidewalk	0.01603	
	Street	0.03869	
Total area (ac)		0.42137	
Figure 1-c	Driveway	0.12188	Overflow from device#1-u1 as shown in figure 1-c.
	Landscaped area	0.29362	
	Roof	0.14325	
	Sidewalk	0.03706	
	Street	0.06726	
Total area (ac)		0.66307	



**DRAFT**

**1324 E 76<sup>th</sup> St #1 (sheet 305 for as-built details); no underdrains**



Only received flows from W along E 76<sup>th</sup> St (from driveway up)



2 samplers and 2 level recorders (inlet and bottom of garden)



Two inlet samples from small event in morning of Oct 25, 2012







Leaves washed into inlet




Porous concrete alongside of rain garden collects yard runoff to garden

**DRAFT**


Date of Construction	Dwelling Type	Building Maintenance	Building Height	Pervious %	Impervious %	Underground %	Roof Type	Sediment Source	Treated Wood	Landscaping Quantity	Landscaping Type	Landscaping Mainten.	% Connected Sidewalk	% Connected Driveway	Driveway Type	Driveway Condition	Driveway Texture	Stormwater Control Potential
<1960	Single	Adequate	2	50	50	0	Composite Shingle	Yes	1 pole	Much	Lawn	Poor	0	100	Unpaved	Poor	Rough	Poor







**2. Curb Extension with Bioretention - 1325 E 76th St.**



Location	Urban Classification	Area (ac)	Note/Assumption
----------	----------------------	-----------	-----------------

From downstream of device#2-u1 to device#2	Driveway	0.01137	There is no overflow from upstream.
	Sidewalk	0.00636	
	Landscaped area	0.01570	
	Street	0.06257	
Total Area (ac)		0.09600	
From downstream of device#2-u2 to device#2	Driveway	0.01420	Overflow from device#2-u1
	Sidewalk	0.01108	
	Landscaped area	0.02292	
	Street	0.08827	
Total Area (ac)		0.13647	
From downstream of device#2-u3 to device#2	Driveway	0.02054	Overflow from device#2-u1 and device#2-u2
	Sidewalk	0.01933	
	Landscaped area	0.03378	
	Street	0.12520	
Total Area (ac)		0.19885	
From upstream of device#2-u3 to device#2	Driveway	0.04243	Overflow from device#2-u1, device#2-u2, and device#2-u3
	Sidewalk	0.08235	
	Landscaped area	0.04561	
	Street	0.1925	
Total Area (ac)		0.36289	
From upstream of device#2-u4 to device#2	Driveway	0.04243	Overflow from device#2-u1, device#2-u2, device#2-u3, and device#2-u4
	Landscaped area	0.12921	
	Sidewalk	0.05392	
	Street	0.2079	
Total Area (ac)		0.43346	
From upstream of device#2-u5 to device#2	Driveway	0.08275	Overflow from device#2-u1, device#2-u2, device#2-u3, device#2-u4, and device#2-u5
	Landscaped area	0.22758	
	Parking lot	0.066	
	Roof	0.01274	
	Sidewalk	0.08054	
	Street	0.25172	
Total Area (ac)		0.72133	



**DRAFT**

1325 E 76<sup>th</sup> St #2 (sheet 305 for as-built details); no underdrains



Drains from street centerline to far side of sidewalk to centerline of Troost




Looking upgradient towards Troost (most of lawns and homes slope south away from this location)




2 inlet samples from small rain in morning of Oct 25, 2012



DRAFT




Date of Construction	Dwelling Type	Building Maintenance	Building Height	Pervious %	Impervious %	Underground %	Roof Type	Sediment Source	Treated Wood	Landscaping Quantity	Landscaping Type	Landscaping Mainten.	% Connected Sidewalk	% Connected Driveway	Driveway Type	Driveway Condition	Driveway Texture	Stormwater Control Potential
<1960	Single	Poor	1	100	0	0	Composite Shingle	Yes	No	Much	Lawn/Dec.	Poor	0	0	Unpaved	Poor	Rough	Poor








3. Curb Extension with BR - 1419 E 76th Terr.



Location	Urban Classification	Area (ac)	Note
----------	----------------------	-----------	------



Figure 3-b	Driveway	0.0875	There is no overflow from upstream as shown in Figure 3-b.
	Landscaped area	0.3388	
	Roof	0.0856	
	Sidewalk	0.0295	
	Street	0.0885	
Total area (ac)		0.6299	
Figure 3-c	Driveway	0.0875	Overflow from device#3-u1 as shown in figure 3-c.
	Landscaped area	0.4678	
	Roof	0.0856	
	Sidewalk	0.0462	
	Street	0.1376	
		0.8247	



1419 E 76<sup>th</sup> Terrace #3 (sheet 207 for as-built details); no underdrains; reported to not drain well



Downgradient (towards east)



Upgradient (towards west to Lydia); drains from center of lots to Lydia




Showing bottom edge of drainage area



4 inlet samples from small rain of morning of Oct 25, 2012 (initial sample contains more sediment)






Porous concrete sidewalks all along street from Lydia to monitored rain garden



Corner of Lydia to E 76<sup>th</sup> Terrace (upper end of drainage)

**DRAFT**

Date of Construction	Dwelling Type	Building Maintenance	Building Height	Pervious %	Impervious %	Underground %	Roof Type	Sediment Source	Treated Wood	Landscaping Quantity	Landscaping Type	Landscaping Mainten.	% Connected Sidewalk	% Connected Driveway	Driveway Type	Driveway Condition	Driveway Texture	Stormwater Control Potential
>2000	Single	Excellent	2	100	0	0	Composite Shingle	No	1 pole	Much	Lawn	Adequate	75	100	Paved	Good	Smooth	Good











4. Rain Garden Extension - 1612 E 76<sup>th</sup> St.



Figure 4 – Aerial photos, topo map, and urban classifications for device #4

Location	Urban Classification	Area (ac)	Note/Assumption
Figure 4-b	Driveway	0.03175	Figure 4-b.
	Landscaped area	0.33922	
	Paved area	0.05197	
	Roof	0.09569	
	Sidewalk	0.02906	
	Street	0.04938	
Total Area (ac)		0.59707	



**DRAFT**

1612 E 76<sup>th</sup> St. #4 (sheet 307 for as-built details); no underdrains



No samplers but two level recorders (inlet and bottom of garden) towards East (upgradient)



Towards West (also upgradient) (treated wood pole in rain garden)








Drainage break to east (flows to left to device from edge of house)




Level sensor recorder in bottom of rain garden

**DRAFT**

Date of Construction	Dwelling Type	Building Maintenance	Building Height	Pervious %	Impervious %	Underground %	Roof Type	Sediment Source	Treated Wood	Landscaping Quantity	Landscaping Type	Landscaping Mainten.	% Connected Sidewalk	% Connected Driveway	Driveway Type	Driveway Condition	Driveway Texture	Stormwater Control Potential
<1960	Single	Poor	2	100	0	0	Composite Shingle	No	1 pole	Much	Lawn/Dec.	Good	100	100	Paved	Good	Smooth	Good







5. Rain Garden Extension - 1336 E 76<sup>th</sup> St.




Figure 5 – Aerial photos, topo map, and urban classifications for device #5

Location	Urban Classification	Area (ac)	Note/Assumption
Figure 5-b	Driveway	0.08434	
	Landscaped area	0.55210	
	Paved area	0.07051	
	Roof	0.14523	
	Sidewalk	0.02434	
	Street	0.02202	
Total Area (ac)		0.89854	



**DRAFT**

**1336 E 76<sup>th</sup> St #5 (sheet 305 for as-built details); no underdrains**



No samplers, 2 level recorders (inlet and bottom of rain garden)





Upgradient from rain garden



DRAFT



Date of Construction	Dwelling Type	Building Maintenance	Building Height	Pervious %	Impervious %	Underground %	Roof Type	Sediment Source	Treated Wood	Landscaping Quantity	Landscaping Type	Landscaping Mainten.	Connected Sidewalk %	Connected Driveway	Driveway Type	Driveway Condition	Driveway Texture	Stormwater Control Potential
<1960	Single	Good	2	50	50	0	Composite Shingle	Yes	1 pole	Much	Lawn/Dec.	Adequate	0	100	Paved	Fair	Smooth	Poor



**6. Site #6 was abandoned and is not being monitored**

**7. Shallow Bioretention Device w/ Smart Drain - 1140 E 76th Terr.**



Location	Urban Classification	Area (ac)	Note/Assumption
Figure 7-b	Driveway	0.00482	
	Landscaped area	0.00318	
	Sidewalk	0.00067	
	Street	0.01596	
Total area (ac)		0.02462	



1140 E 76<sup>th</sup> Terrace #7 (sheet 205 for as-built details); Smart Drains



Towards E showing sloping driveway from rain garden; only half of street and a bit of yard to system (near top of street slope)



Very small drainage area; large inlet right below rain garden



Yard slopes away from rain garden; sidewalk edge to street center



Driveway slopes away from rain garden towards yard inlets








No samplers, but 2 level recorders at inlet and bottom of rain garden








DRAFT



8. Rain Garden w/ Smart Drain - 1222 E 76<sup>th</sup> St.



Location	Urban Classification	Area (ac)	Note/Assumption
----------	----------------------	-----------	-----------------

Figure 8-b	Driveway	0.12166	There is no overflow from upstream, as shown in Figure 8-b.
	Landscaped area	0.30035	
	Roof	0.09538	
	Sidewalk	0.02348	
	Street	0.0442	
Total area (ac)		0.5851	
Figure 8-c	Driveway	0.17259	As shown in Figure 8-c, there is an overflow from device# 8-u1.
	Landscaped area	0.48239	
	Roof	0.17459	
	Sidewalk	0.05274	
	Street	0.10525	
Total area (ac)		0.98756	



**DRAFT**

**1222 E 76<sup>th</sup> St #8 (sheet 304 for as-built details); Smart Drains**



2 samplers and 2 level recorders (inlet and smartdrain underdrain)



E edge of drainage area slopes away from rain garden (no house or driveway)







Upgradient rain garden and signage









9. Cascade - 1112 E 76th Terr.



Figure 9 – Aerial photos, topo map, and urban classifications for device #9

Location	Urban Classification	Area (ac)	Note/Assumption
Figure 9-b	Driveway	0.0392	There is no overflow from upstream, as shown in Figure 9-b.
	Landscaped area	0.0337	
	Parking lot	0.0639	
	Roof	0.0958	
	Sidewalk	0.0101	
	Street	0.0505	
Total area (ac)		0.2931	



DRAFT

1112 E 76<sup>th</sup> Terrace #9 (sheet 205 for as-built details); cascading swale (but upper weir set high so runoff bypasses other cells), no underdrains



W towards Troost and two businesses that drain to this device





DRAFT





Towards cascade from next downgradient rain garden and drain inlet



Device #9








**DRAFT**

**10. Private rain garden - 1312 E. 79<sup>th</sup> St. - Mrs. Thomas**



**1312 E 79<sup>th</sup> St #10; Mrs. Thomas Rain Garden (no details; two level recorders, inlet and bottom of rain garden)**





Roof drains from half of front and half of side of home



Typical street without rain gardens



**DRAFT**

**11. 1505 E 76<sup>th</sup> St, #11; Mrs. Moss rain garden (no details); level recorders for inlet and bottom of garden)**



Side of house; rain garden in rear

**Appendix B: Details of typical stormwater controls in test area**

Device at Site No.	Top area (sq ft)	Bottom area (sq ft)	Pool depth	Material
1	422.9	240		
2	513.5	228.5		
3	341.5	160.5		
4	200.86	59.72	6"	3" hardwood mulch on top, Native soil amended with 3" compose, roto-tilled 8" min depth
5	222.35	93.5	6"	
7	247.06	37.9	12"	3" hardwood mulch on top, Topsoil planting mix on side slopes, Engineering soil mix 8" min depth on bottom.
8	284	36.28	6"	3" hardwood mulch on top, Native soil amended with 3" compose, roto-tilled 8" min depth
9	290.73	48.16	12"	Topsoil planting mix on side slopes, Engineering soil mix 8" min depth on bottom.

**Subsurface layer properties for applicable stormwater control layers (Source Table 2-10 of the "Report on Enhanced Framework (SUSTAIN) and Field Applications for Placement of BMPs in Urban Watersheds")**


Soil layer	Property	Value	Units
Engineered soil media	Porosity	0.4	--
	Field capacity	0.3	--
	Wilting point	0.1	--
	Holtan vegetation parameter	0.6	--
	Saturated infiltration rate	2	in./hr
Underdrain layer	Void fraction	0.4	--
Native background soil	Saturated infiltration rate	0.1	in./hr


**Private rain garden design dimensions and specifications. (Source Table 2-11 of the "Report on Enhanced Framework (SUSTAIN) and Field Applications for Placement of BMPs in Urban Watersheds")**

BMP categories	BMP dimensions				Outlet type
	Surface area	Ponding (ft)	Soil media (ft)	Underdrain	
Rain garden	200 sq ft per house (1,000 sq ft roof)	1	2	No underdrain	Weir
Influent flow monitoring device	35-gallon tank with orifice on standpipe				Weir and orifice





### Appendix B-1. Rain garden typical details for residential streets






**Appendix B-2. Shallow bioretention device typical details for residential streets**






Appendix B-3. Cascade rain garden typical details for residential streets



Appendix B-3. Cascade rain garden typical details for residential streets (continued)





### Appendix C: Measured Infiltration Rates in Biofilters

Monitored events at biofilters and rain characteristics

No.	Stormwater Control Type	Address	Rainfall Depth (in)	Start Time	End Time	Event Duration (hr:min)	Total volume of inflow (gal)	Total drainage area (ac)	Total runoff (in)	Rv: Runoff/rain fall
1	Curb Extension	1324 E 76 <sup>th</sup> St.	0.86	10/12/2012 21:00:00	10/14/2012 09:40:00	36:40	2778	0.42137	0.24	0.28
			0.43	9/13/2012 12:00:00	9/14/2012 10:45:00	22:45	2101	0.42137	0.18	0.43
			2.61	8/30/2012 22:20:00	8/31/2012 20:15:00	21:55	4000	0.42137	0.35	0.13
			0.49	7/25/2012 11:15:00	7/26/2012 12:25:00	25:10	338	0.42137	0.03	0.06
			1.03	6/20/2012 19:05:00	6/21/2012 11:55:00	16:50	916	0.42137	0.08	0.08
			0.4	5/24/2012	5/25/2012			0.42137		
			0.43	4/30/2012	5/1/2012			0.42137		
2	Curb Extension	1325 E 76 <sup>th</sup> St.	0.86	10/12/2012 19:00:00	10/14/2012 02:20:00	31:20	1553	0.096	0.60	0.69
			0.23	9/25/2012 20:30:00	9/26/2012* 02:35:00	06:05	42	0.096	0.02	0.07
			0.43	9/13/2012 11:10:00	9/14/2012 10:55:00	23:45	5954	0.096	2.28	5.31
			2.61	8/30/2012 19:00:00	8/31/2012 18:15:00	23:15	4870	0.096	1.87	0.72
			0.49	7/25/2012 17:00:00	7/26/2012 12:30:00	19:30	328	0.096	0.13	0.26
			1.03	6/20/2012 19:10:00	6/21/2012 11:55:00	16:45	1370	0.096	0.53	0.51
			0.8	6/10/2012 22:05:00	6/11/2012 13:20:00	15:15	346.5	0.096	0.13	0.17
			0.23	5/29/2012	5/30/2012			0.096		

**DRAFT**

No.	Stormwater Control Type	Address	Rainfall Depth (in)	Start Time	End Time	Event Duration (hr:min)	Total volume of inflow (gal)	Total drainage area (ac)	Total runoff (in)	Rv: Runoff/rain fall
			1.85	5/6/2012	5/7/2012			0.096		
3	Curb Extension	1419 E 76 <sup>th</sup> Terr.	0.86	10/12/2012 21:00:00	10/13/2012 22:15:00	25:15	3487	0.6299	0.20	0.24
			0.23	9/26/2012 02:25:00	9/26/2012* 04:30:00	02:05	583	0.6299	0.03	0.15
			0.43	9/13/2012 14:10:00	9/14/2012 10:10:00	20:00	3987	0.6299	0.23	0.54
			2.61	8/31/2012 11:00:00	8/31/2012 17:00:00	06:00	1940	0.6299	0.11	0.04
			0.49	7/25/2012 17:55:00	7/26/2012 08:30:00	12:35	103	0.6299	0.01	0.01
			1.03	6/21/2012 00:55:00	6/21/2012 11:25:00	10:30	232	0.6299	0.01	0.01
4	Rain Garden Extension	1612 E 76 <sup>th</sup> St.	0.86	10/12/2012 21:00:54	10/13/2012 21:05:54	24:05	754	0.59707	0.05	0.05
			0.23	9/26/2012 02:55:54	9/26/2012 05:30:54	02:35	30	0.59707	0.00	0.01
			0.43	9/13/2012 14:40:54	9/13/2012 20:25:54	05:45	40	0.59707	0.00	0.01
			5.60	8/31/2012 11:00:54	9/1/2012 15:00:54	28:00	1194	0.59707	0.07	0.01
			1.03	6/21/2012 00:12:33	6/21/2012 12:02:33	11:50	1061	0.59707	0.07	0.06
			0.8	6/10/2012 09:45:52	6/11/2012 10:00:52	24:15	1.1	0.59707	0.00	0.00
			0.4	5/24/2012	5/25/2012			0.59707		
			1.85	5/6/2012	5/7/2012			0.59707		
5	Rain Garden Extension	1336 E 76 <sup>th</sup> St.	0.86	10/11/2012 17:32:07	10/14/2012 10:47:07	65:15	293	0.3301	0.03	0.04
			0.23	9/26/2012 03:02:07	9/26/2012 07:22:07	04:20	156	0.3301	0.02	0.08

**DRAFT**

No.	Stormwater Control Type	Address	Rainfall Depth (in)	Start Time	End Time	Event Duration (hr:min)	Total volume of inflow (gal)	Total drainage area (ac)	Total runoff (in)	Rv: Runoff/rain fall
			0.43	9/13/2012 14:37:17	9/14/2012 10:47:07	20:45	1692	0.3301	0.19	0.44
			5.60	8/31/2012 15:47:07	9/2/2012 11:02:07	43:15	6877	0.3301	0.77	0.14
			0.49	7/26/2012 01:31:19	7/26/2012 12:16:19	10:45	75	0.3301	0.01	0.02
			1.03	6/21/2012 00:17:19	6/21/2012 12:02:19	11:45	3884	0.3301	0.43	0.42
			0.8	6/10/2012 07:02:19	6/11/2012 15:02:19	32:00	14.7	0.3301	0.00	0.00
			0.29	5/29/2012 05:17:19	5/30/2012 18:07:19	36:47	289	0.3301	0.03	0.11
			0.4	5/24/2012	5/25/2012			0.3301		
			0.56	4/29/2012	4/29/2012			0.3301		
			0.43	4/30/2012	5/1/2012			0.3301		
			1.85	5/6/2012	5/7/2012			0.3301		
6	Rain Garden Extension	1141 E 76 <sup>th</sup> Terr.								
7	Rain Garden w/ Smart Drain	1140 E 76 <sup>th</sup> Terr.	0.86	10/12/2012 20:59:34	10/12/2012 22:39:34	25:40	536	0.02462	0.80	0.93
			0.23	9/25/2012 23:54:34	9/26/2012 08:34:34	08:40	869	0.02462	1.30	5.65
			0.43	9/13/2012 14:37:17	9/14/2012 10:34:34	20:00	No Flume data	0.02462	No Flume data	No Flume data
			5.60	8/31/2012 11:02:17	9/1/2012 18:02:17	31:00	46827	0.02462	70.05	12.51
			1.03	6/20/2012 19:22:24	6/21/2012 11:32:24	16:10	14203	0.02462	21.25	20.63

**DRAFT**

No.	Stormwater Control Type	Address	Rainfall Depth (in)	Start Time	End Time	Event Duration (hr:min)	Total volume of inflow (gal)	Total drainage area (ac)	Total runoff (in)	Rv: Runoff/rain fall
			0.8	6/11/2012 02:03:12	6/11/2012 12:03:12	10:00	18.2	0.02462	0.03	0.03
			0.23	5/29/2012	5/30/2012			0.02462		
			0.4	5/24/2012	5/30/2012			0.02462		
8	Rain Garden w/ Smart Drain	1222 E 76 <sup>th</sup> St.	0.86	10/13/2012 00:30:00	10/13/2012 22:00:00	21:30	547	0.5851	0.03	0.04
			0.23	9/26/2012 02:00:00	9/26/2012 09:15:00	07:15	527	0.5851	0.03	0.14
			0.43	9/13/2012 14:30:00	9/13/2012 20:30:00	06:00	762	0.5851	0.05	0.11
			2.61	8/31/2012 11:35:00	8/31/2012 23:00:00	11:25	1492	0.5851	0.09	0.04
			0.49	7/25/2012 18:00:00	7/26/2012 05:00:00	11:00	82	0.5851	0.01	0.01
			0.8	6/11/2012 02:05:00	6/11/2012 06:50:00	04:55	6.7	0.5851	0.00	0.00
			0.4	5/24/2012	5/25/2012			0.5851		
9	Cascade	1112 E 76 <sup>th</sup> Terr.	0.86	10/12/2012 00:03:23	10/14/2012 07:48:23	55:45	1197	0.2931	0.15	0.17
			0.23	9/26/2012 02:08:23	9/26/2012 04:53:23	02:45	261	0.2931	0.03	0.14
			0.43	9/13/2012 14:08:23	9/14/2012 10:23:23	20:15	2098	0.2931	0.26	0.61
			5.60	8/31/2012 11:08:23	9/1/2012 15:08:23	28:00	8533	0.2931	1.07	0.19


\* ISCO flume stopped at this time, but the rain was still on.

**DRAFT**




Curb Extension with BR – 1324 E 76<sup>th</sup> St.


1324 76th Raingarden on Rainevent 10/13




1324 76th Raingarden on Rainevent 09/13




1324 76th Flume on Rainevent 08/31




Graph for 1324 76th Rainevent 07/26




1324 76th Flume on Rainevent 06/21






Graph for 1324 76th Raingarden on Rainevent 5/24--5/25






Graph for 1324 76th Raingarden on Rainevent 4/30--5/1






Rainfall Depth (in.)	Start Time	End Time	Event Duration (hr:min)	Total volume of inflow (gal)	Max Water Depth in Garden (in)	Time Duration before Ponding Occurred (hr:min)	f (in/hr)
0.86	10/12/2012 21:00:00	10/14/2012 09:40:00	36:40	2778	0.84	24:00	>3.36
0.43	9/13/2012 12:00:00	9/14/2012 10:45:00	22:45	2101	0.84	17:30	0.288
					0.24	18:45	1.44
					0.36	20:00	0.96
2.61	8/30/2012 22:20:00	8/31/2012 20:15:00	21:55	4000	0.72	18:00	>0.72
0.49	7/25/2012 11:15:00	7/26/2012 12:25:00	25:10	338	0		
1.03	6/20/2012 19:05:00	6/21/2012 11:55:00	16:50	916	0		
0.4	5/29/2012	5/30/2012			2.64	11:45	5.04
					3.72	14:00	4.85
0.43	4/30/2012	5/1/2012			3.6	6:00	0.08
					2.52	78:40	0.28











1- Curb Extension with BR – 1325 E 76<sup>th</sup> St.


1325 76th Raingarden on Rainevent 10/13




1325 76th Raingarden on Rainevent 09/26




### 1325 76th Raingarden on Rainevent 09/13




### 1325 76th Flume on Rainevent 08/31




Graph for 1325 76th Rainevent 07/26




1325 76th Flume on Rainevent 06/21



### 1325 76th Raingarden on Rainevent 06/11




### Graph for 1325 76th Raingarden on Rainevent 30/5










Graph for 1325 76th Raingarden on Rainevent on 5/6-5/7




Rainfall Depth (in.)	Start Time	End Time	Event Duration (hr:min)	Total volume of inflow (gal)	Max Water Depth in Garden (in)	Time Duration before Ponding Occurred (hr:min)	f (in/hr)
0.86	10/12/2012 19:00:00	10/14/2012 02:20:00	31:20	1553	0.24		
0.23	9/25/2012 20:30:00	9/26/2012* 02:35:00	06:05	42	0		
0.43	9/13/2012 11:10:00	9/14/2012 10:55:00	23:45	5954	1.56	0:15	0.9
2.61	8/30/2012 19:00:00	8/31/2012 18:15:00	23:15	4870	1.8	20:15	0.24
0.49	7/25/2012 17:00:00	7/26/2012 12:30:00	19:30	328	0		
1.03	6/20/2012 19:10:00	6/21/2012 11:55:00	16:45	1370	0.96	9:45	0.47
0.8	6/10/2012 22:05:00	6/11/2012 13:20:00	15:15	346.5	0.12		
0.23	5/29/2012	5/30/2012			1.2	1:30	4.8
1.85	5/6/2012	5/7/2012			5.64	2:00	0.48






2- Curb Extension with BR – 1419 E 76<sup>th</sup> Terr.


1419 76th terr Raingarden on Rainevent 10/13




1419 76th terr Raingarden on Rainevent 09/26




1419 76th Terr Raingarden on Rainevent 09/13




1419 76th Terr Flume on Rainevent 08/31



Graph for 1419 76 Terr Rainevent 07/26





1419 76th Terrace Flume on Rainevent 06/21






Rainfall	Start Time	End Time	Event Duration	Total volume of	Max Water	Time Duration	f (in/hr)
----------	------------	----------	----------------	-----------------	-----------	---------------	-----------



Depth (in.)			(hr:min)	inflow (gal)	Depth in Garden (in)	before Ponding Occurred (hr:min)	
0.86	10/12/2012 21:00:00	10/13/2012 22:15:00	25:15	3487	5.57	4:55	0.62
					7.04	13:45	0.49
0.23	9/26/2012 02:25:00	9/26/2012* 04:30:00	02:05	583	0		
0.43	9/13/2012 14:10:00	9/14/2012 10:10:00	20:00	3987	6.5	2:30	0.24
2.61	8/31/2012 11:00:00	8/31/2012 17:00:00	06:00	1940	5.4	4:15	0.19
0.49	7/25/2012 17:55:00	7/26/2012 08:30:00	12:35	103	2.35	7:30	0.24
1.03	6/21/2012 00:55:00	6/21/2012 11:25:00	10:30	232	0		







**DRAFT**

3- Rain Garden Extension – 1612 E 76<sup>th</sup> St.


2D Graph 7




1612 76th Raingarden on Rainevent 09/26




1612 76th Raingarden on Rainevent 09/13




1612 76th on Rainevent 08/31-09/01



### 1612 76th Graphs on Rainevent 06/21




### 1612 76th Raingarden on Rainevent 06/11






Graph for 1612 76th Raingarden on Rainevent 5/24--5/25







Graph for 1612 76th Raingarden on Rainevent on 5/6-5/7






Rainfall	Start Time	End Time	Event Duration	Total volume	Max Water Depth	Time Duration before	f (in/hr)
----------	------------	----------	----------------	--------------	-----------------	----------------------	-----------

Depth (in.)			(hr:min)	of inflow (gal)	in Garden (in)	Ponding Occurred (hr:min)	
0.86	10/12/2012 21:00:54	10/13/2012 21:05:54	24:05	754	7.32	9:00	1.54
0.23	9/26/2012 02:55:54	9/26/2012 05:30:54	02:35	30	0		
0.43	9/13/2012 14:40:54	9/13/2012 20:25:54	05:45	40	0		
5.60	8/31/2012 11:00:54	9/1/2012 15:00:54	28:00	1194	0		
1.03	6/21/2012 00:12:33	6/21/2012 12:02:33	11:50	1061	9.84	1:45	>3.14
0.8	6/10/2012 09:45:52	6/11/2012 10:00:52	24:15	1.1	1.92	20:00	2.54
0.4	5/24/2012	5/25/2012			9.48	1:00	3.96
					9.48	5:45	2.49
1.85	5/6/2012	5/7/2012			4.92	2:00	3.27
					4.68	11:00	1.56









4- Rain Garden Extension – 1336 E 76<sup>th</sup> St.


1336 76th Raingarden on Rainevent 10/13



1336 76th Raingarden on Rainevent 09/26



### 1336 76th Raingarden on Rainevent 09/13




### 1336 76th on Rainevent 08/31-09/01







Graph for 1336 76 Terr Rainevent 07/26




1336 76th Graphs on Rainevent 06/21




### 1336 76th Raingarden on Rainevent 06/11




### Graph for 1336 76th flume on Rainevent 30/5-31/5




Graph for 1336 76th flume on Rainevent 5/24--5/25




Graph for 1336 76th Raingarden on Rainevent on 4/29



Graph for 1336 76th Raingarden on Rainevent 4/30--5/1






Graph for 1336 76th Raingarden on Rainevent on 5/6-5/7









**DRAFT**




Rainfall Depth (in.)	Start Time	End Time	Event Duration (hr:min)	Total volume of inflow (gal)	Max Water Depth in Garden (in)	Time Duration before Ponding Occurred (hr:min)	f (in/hr)
0.86	10/11/2012 17:32:07	10/14/2012 10:47:07	65:15	293	0		
0.23	9/26/2012 03:02:07	9/26/2012 07:22:07	04:20	156	0		
0.43	9/13/2012 14:37:17	9/14/2012 10:47:07	20:45	1692	0.48	2:00	>0.96
					0.48	6:15	>0.96
					0.6	14:30	>0.82
5.60	8/31/2012 15:47:07	9/2/2012 11:02:07	43:15	6877	3.6	9:30	>2.13
					2.4	30:15	0.82
0.49	7/26/2012 01:31:19	7/26/2012 12:16:19	10:45	75	1.6	4:00	0.62
1.03	6/21/2012 00:17:19	6/21/2012 12:02:19	11:45	3884	13.2	1:00	1.19
0.8	6/10/2012 07:02:19	6/11/2012 15:02:19	32:00	14.7	4.68	20:00	>4.94
					11.4	21:30	>2.38
0.29	5/29/2012 05:17:19	5/30/2012 18:07:19	36:47	289	4.2	12:24	>8.4
					7.44	19:54	1.4
0.4	5/24/2012	5/25/2012			4.2	0:25	1.1
					3.72	10:30	0.62
0.56	4/29/2012	4/29/2012			2.64	1:30	2.26
					2.16	6:00	1.19
0.43	4/30/2012	5/1/2012			2.16	3:15	1.47
1.85	5/6/2012	5/7/2012			3.6	1:30	4.71
					4.32	8:00	1.24
					3.84	20:00	2.69




























7- Rain Garden - 1140 E 76th Terr.


1140 76th terr Raingarden on Rainevent 10/13




1140 76th terr Raingarden on Rainevent 09/26




1140 76th Terr Raingarden on Rainevent 09/13




1140 76th Terrace Flume on Rainevent 08/31-09/01




### 1140 76th Terrace Graphs on Rainevent 06/21




### 1140 76th terr Flume on Rainevent 06/11



Graph for 1140 76th terr Raingarden on Rainevent 30/5







Graph for 1140 76th terr Raingarden on Rainevent 5/24--5/25




Rainfall Depth (in.)	Start Time	End Time	Event Duration (hr:min)	Total volume of inflow (gal)	Max Water Depth in Garden (in)	Time Duration before Ponding Occurred (hr:min)	f (in/hr)
0.86	10/12/2012 20:59:34	10/12/2012 22:39:34	25:40	536	0		

Rainfall Depth (in.)	Start Time	End Time	Event Duration (hr:min)	Total volume of inflow (gal)	Max Water Depth in Garden (in)	Time Duration before Ponding Occurred (hr:min)	f (in/hr)
0.23	9/25/2012 23:54:34	9/26/2012 08:34:34	08:40	869	0		
0.43	9/13/2012 14:37:17	9/14/2012 10:34:34	20:00	No Flume data	1.56	No Flume data	No Flume data
5.60	8/31/2012 11:02:17	9/1/2012 18:02:17	31:00	46827	0		
1.03	6/20/2012 19:22:24	6/21/2012 11:32:24	16:10	14203	5.4	6:35	>2.7
0.8	6/11/2012 02:03:12	6/11/2012 12:03:12	10:00	18.2	0		
0.23	5/29/2012	5/30/2012			4.68	0:15	2.74
					3.84	2:55	1.74
0.4	5/24/2012	5/30/2012			3.48	20:40	1.1
					3.84	30:30	0.71











8- Rain Garden - 1222 E 76th St.


1222 76th Raingarden on Rainevent 10/13




1222 76th Raingarden on Rainevent 09/26




### 1222 76th Flume on Rainevent 09/13




### 1222 76th Flume on Rainevent 08/31




Graph for 1222 76th Rainevent 07/26






1222 76th Raingarden on Rainevent 06/11



Graph for 1222 76th Raingarden on Rainevent 5/24--5/25




Rainfall Depth (in.)	Start Time	End Time	Event Duration (hr:min)	Total volume of inflow (gal)	Max Water Depth in Garden (in)	Time Duration before Ponding Occurred (hr:min)	f (in/hr)
0.86	10/13/2012 00:30:00	10/13/2012 22:00:00	21:30	547	0		
0.23	9/26/2012 02:00:00	9/26/2012 09:15:00	07:15	527	0		
0.43	9/13/2012 14:30:00	9/13/2012 20:30:00	06:00	762	0		
2.61	8/31/2012 11:35:00	8/31/2012 23:00:00	11:25	1492	0.12		
0.49	7/25/2012 18:00:00	7/26/2012 05:00:00	11:00	82	0		
0.8	6/11/2012 02:05:00	6/11/2012 06:50:00	04:55	6.7	0.84	3:40	3.36
0.4	5/24/2012	5/25/2012			2.88	1:30	3.36
					2.64	11:45	1.17






9- Cascade - 1112 E 76th Terr.


1112 76 terr 10/13




1112 76th terr Raingarden on Rainevent 09/26




1112 76th Terr Raingarden on Rainevent 09/13









1112 76th Terr on Rainevent 08/31-09/01




Rainfall Depth (in.)	Start Time	End Time	Event Duration (hr:min)	Total volume of inflow (gal)	Max Water Depth in Garden (in)	Time Duration before Ponding Occurred (hr:min)	f (in/hr)
0.86	10/12/2012 00:03:23	10/14/2012 07:48:23	55:45	1197	6.73	25:15	>7.21
					2.75	35:15	>3.76
					8.28	39:00	>4.69
0.23	9/26/2012 02:08:23	9/26/2012 04:53:23	02:45	261	2.96	2:15	>4.8
0.43	9/13/2012 14:08:23	9/14/2012 10:23:23	20:15	2098	5.8	1:45	>5.33
					5.79	4:15	>4.9
5.60	8/31/2012 11:08:23	9/1/2012 15:08:23	28:00	8533	6.35	4:15	3.85
					4.69	26:15	4.99











**DRAFT**

**Appendix D: Large-Scale Combined Sewer Monitoring Data (based on Tetra Tech  
Compilations from KCMO and UMKC Data)**

## Large-Scale Rainfall and Runoff Monitoring from Combined Sewer System for Test and Control Areas (data from KCMO, UMKC, and Tetra Tech)

Site	Area (acres)	Event #	Rain start date	Rain start time	Rain end date	Rain end time	Antecedent dry days	Rain dur. (hrs)	Total rain <sup>a</sup> (in)	5-minute peak rain intensity <sup>a</sup> (in/hr)	Avg rain int. (in/hr)
Test	100	1	9/2/2008	16:45	9/4/2008	22:05	1.70	41.42	1.85	1.89	0.04
Control	80	1	9/2/2008	16:45	9/4/2008	22:05	1.70	41.42	1.85	1.89	0.04
Test	100	2	9/8/2008	4:35	9/8/2008	19:35	3.77	3.08	0.47	3.31	0.15
Control	80	2	9/8/2008	4:35	9/8/2008	19:35	3.77	3.08	0.47	3.31	0.15
Test	100	3	9/11/2008	11:20	9/13/2008	19:45	3.15	44.50	3.98	2.36	0.09
Control	80	3	9/11/2008	11:20	9/13/2008	19:45	3.15	44.50	3.98	2.36	0.09
Test	100	4	9/13/2008	20:15	9/14/2008	14:20	0.52	6.17	0.47	0.47	0.08
Control	80	4	9/13/2008	20:15	9/14/2008	14:20	0.52	6.17	0.47	0.47	0.08
Test	100	5	9/24/2008	6:35	9/24/2008	20:55	10.17	2.42	0.67	2.36	0.28
Control	80	5	9/24/2008	6:35	9/24/2008	20:55	10.17	2.42	0.67	2.36	0.28
Test	100	6	10/7/2008	8:00	10/7/2008	20:45	12.96	0.83	0.12	0.47	0.14
Control	80	6	10/7/2008	8:00	10/7/2008	20:45	12.96	0.83	0.12	0.47	0.14
Test	100	7	10/13/2008	14:20	10/14/2008	12:40	6.23	10.42	0.35	0.47	0.03
Control	80	7	10/13/2008	14:20	10/14/2008	12:40	6.23	10.42	0.35	0.47	0.03
Test	100	8	10/15/2008	3:25	10/16/2008	0:40	1.11	9.33	0.87	0.95	0.09
Control	80	8	10/15/2008	3:25	10/16/2008	0:40	1.11	9.33	0.87	0.95	0.09
Test	100	9	10/17/2008	11:25	10/18/2008	0:15	1.94	0.92	0.12	0.47	0.13
Control	80	9	10/17/2008	11:25	10/18/2008	0:15	1.94	0.92	0.12	0.47	0.13
Test	100	10	3/23/2009	21:10	3/24/2009	17:55	157.37	8.83	0.55	0.47	0.06
Control	80	10	3/23/2009	21:10	3/24/2009	17:55	157.37	8.83	0.55	0.47	0.06
Test	100	11	3/26/2009	19:55	3/27/2009	13:20	2.58	5.50	0.28	0.95	0.05

**DRAFT**

**Large-Scale Rainfall and Runoff Monitoring from Combined Sewer System for Test and Control Areas (data from KCMO, UMKC, and Tetra Tech) (cont.)**

Site	Area (acres)	Event #	Rain start date	Rain start time	Rain end date	Rain end time	Antecedent dry days	Rain dur. (hrs)	Total rain <sup>a</sup> (in)	5-minute peak rain intensity <sup>a</sup> (in/hr)	Avg rain int. (in/hr)
Control	80	11	3/26/2009	19:55	3/27/2009	13:20	2.58	5.50	0.28	0.95	0.05
Test	100	12	3/28/2009	9:15	3/29/2009	6:45	1.33	9.58	0.55	0.95	0.06
Control	80	12	3/28/2009	9:15	3/29/2009	6:45	1.33	9.58	0.55	0.95	0.06
Test	100	13	3/29/2009	8:50	3/30/2009	2:10	0.58	5.42	0.39	0.47	0.07
Control	80	13	3/29/2009	8:50	3/30/2009	2:10	0.58	5.42	0.39	0.47	0.07
Test	100	14	3/30/2009	23:20	3/31/2009	12:25	1.38	1.17	0.24	0.95	0.20
Control	80	14	3/30/2009	23:20	3/31/2009	12:25	1.38	1.17	0.24	0.95	0.20
Test	100	15	4/2/2009	5:50	4/2/2009	23:40	2.22	5.92	0.12	0.47	0.02
Control	80	15	4/2/2009	5:50	4/2/2009	23:40	2.22	5.92	0.12	0.47	0.02
Test	100	16	4/9/2009	20:05	4/11/2009	1:15	7.35	17.25	0.95	1.42	0.05
Control	80	16	4/9/2009	20:05	4/11/2009	1:15	7.35	17.25	0.95	1.42	0.05
Test	100	17	4/12/2009	14:05	4/13/2009	19:55	2.03	17.92	0.43	0.47	0.02
Control	80	17	4/12/2009	14:05	4/13/2009	19:55	2.03	17.92	0.43	0.47	0.02
Test	100	18	4/18/2009	7:15	4/19/2009	0:40	4.97	5.50	0.55	0.95	0.10
Control	80	18	4/18/2009	7:15	4/19/2009	0:40	4.97	5.50	0.55	0.95	0.10
Test	100	19	4/19/2009	3:15	4/19/2009	18:55	0.60	3.75	0.28	0.47	0.07
Control	80	19	4/19/2009	3:15	4/19/2009	18:55	0.60	3.75	0.28	0.47	0.07
Test	100	20	4/26/2009	22:45	4/28/2009	0:05	7.66	13.42	2.17	1.89	0.16
Control	80	20	4/26/2009	22:45	4/28/2009	0:05	7.66	13.42	2.17	1.89	0.16
Test	100	21	4/29/2009	14:50	4/30/2009	6:15	2.11	3.50	0.67	1.42	0.19
Control	80	21	4/29/2009	14:50	4/30/2009	6:15	2.11	3.50	0.67	1.42	0.19
Test	100	22	4/30/2009	6:20	5/1/2009	8:10	0.50	13.92	1.46	3.31	0.10
Control	80	22	4/30/2009	6:20	5/1/2009	8:10	0.50	13.92	1.46	3.31	0.10

**DRAFT****Large-Scale Rainfall and Runoff Monitoring from Combined Sewer System for Test and Control Areas (data from KCMO, UMKC, and Tetra Tech) (cont.)**

Site	Area (acres)	Event #	Rain start date	Rain start time	Rain end date	Rain end time	Antecedent dry days	Rain dur. (hrs)	Total rain <sup>a</sup> (in)	5-minute peak rain intensity <sup>a</sup> (in/hr)	Avg rain int. (in/hr)
Test	100	23	5/8/2009	6:00	5/8/2009	20:15	7.41	2.33	0.32	0.47	0.14
Control	80	23	5/8/2009	6:00	5/8/2009	20:15	7.41	2.33	0.32	0.47	0.14
Test	100	24	5/13/2009	18:05	5/14/2009	6:30	5.41	0.50	0.28	1.42	0.55
Control	80	24	5/13/2009	18:05	5/14/2009	6:30	5.41	0.50	0.28	1.42	0.55
Test	100	25	5/15/2009	17:10	5/16/2009	9:00	1.94	3.92	1.34	3.78	0.34
Control	80	25	5/15/2009	17:10	5/16/2009	9:00	1.94	3.92	1.34	3.78	0.34
Test	100	26	5/25/2009	23:35	5/26/2009	16:30	10.10	5.00	0.24	0.95	0.05
Control	80	26	5/25/2009	23:35	5/26/2009	16:30	10.10	5.00	0.24	0.95	0.05
Test	100	27	6/2/2009	13:10	6/3/2009	6:45	7.36	5.67	0.39	0.95	0.07
Control	80	27	6/2/2009	13:10	6/3/2009	6:45	7.36	5.67	0.39	0.95	0.07
Test	100	28	6/8/2009	2:35	6/8/2009	14:55	5.32	0.42	0.20	0.95	0.47
Control	80	28	6/8/2009	2:35	6/8/2009	14:55	5.32	0.42	0.20	0.95	0.47
Test	100	29	6/9/2009	10:35	6/10/2009	10:00	1.32	11.50	2.09	2.84	0.18
Control	80	29	6/9/2009	10:35	6/10/2009	10:00	1.32	11.50	2.09	2.84	0.18
Test	100	30	6/11/2009	2:40	6/11/2009	16:10	1.19	1.58	0.43	1.42	0.27
Control	80	30	6/11/2009	2:40	6/11/2009	16:10	1.19	1.58	0.43	1.42	0.27
Test	100	31	6/15/2009	2:35	6/15/2009	21:50	3.93	7.33	0.95	2.84	0.13
Control	80	31	6/15/2009	2:35	6/15/2009	21:50	3.93	7.33	0.95	2.84	0.13
Test	100	32	6/15/2009	22:35	6/16/2009	18:15	0.53	7.75	1.58	2.84	0.20
Control	80	32	6/15/2009	22:35	6/16/2009	18:15	0.53	7.75	1.58	2.84	0.20
Test	100	33	6/23/2009	23:30	6/24/2009	12:20	7.72	0.92	0.35	1.42	0.39
Control	80	33	6/23/2009	23:30	6/24/2009	12:20	7.72	0.92	0.35	1.42	0.39
Test	100	34	7/3/2009	8:20	7/3/2009	23:20	9.33	3.08	0.32	0.47	0.10

**DRAFT**

**Large-Scale Rainfall and Runoff Monitoring from Combined Sewer System for Test and Control Areas (data from KCMO, UMKC, and Tetra Tech) (cont.)**

Site	Area (acres)	Event #	Rain start date	Rain start time	Rain end date	Rain end time	Antecedent dry days	Rain dur. (hrs)	Total rain <sup>a</sup> (in)	5-minute peak rain intensity <sup>a</sup> (in/hr)	Avg rain int. (in/hr)
Control	80	34	7/3/2009	8:20	7/3/2009	23:20	9.33	3.08	0.32	0.47	0.10
Test	100	35	7/4/2009	0:40	7/4/2009	17:15	0.55	4.67	1.30	1.89	0.28
Control	80	35	7/4/2009	0:40	7/4/2009	17:15	0.55	4.67	1.30	1.89	0.28
Test	100	36	7/6/2009	20:00	7/7/2009	8:05	2.61	0.17	0.28	1.89	1.65
Control	80	36	7/6/2009	20:00	7/7/2009	8:05	2.61	0.17	0.28	1.89	1.65
Test	100	37	7/10/2009	5:10	7/10/2009	17:20	3.38	0.25	0.16	0.95	0.63
Control	80	37	7/10/2009	5:10	7/10/2009	17:20	3.38	0.25	0.16	0.95	0.63
Test	100	38	7/12/2009	7:55	7/13/2009	5:45	2.10	9.92	0.79	2.84	0.08
Control	80	38	7/12/2009	7:55	7/13/2009	5:45	2.10	9.92	0.79	2.84	0.08
Test	100	39	7/20/2009	16:45	7/21/2009	14:35	7.95	9.92	0.63	0.95	0.06
Control	80	39	7/20/2009	16:45	7/21/2009	14:35	7.95	9.92	0.63	0.95	0.06
Test	100	40	7/27/2009	21:35	7/29/2009	3:40	6.79	18.17	1.69	3.31	0.09
Control	80	40	7/27/2009	21:35	7/29/2009	3:40	6.79	18.17	1.69	3.31	0.09
Test	100	41	8/1/2009	4:00	8/1/2009	17:45	3.51	1.83	0.32	0.95	0.17
Control	80	41	8/1/2009	4:00	8/1/2009	17:45	3.51	1.83	0.32	0.95	0.17
Test	100	42	8/4/2009	5:55	8/4/2009	19:40	3.00	1.83	0.55	1.89	0.30
Control	80	42	8/4/2009	5:55	8/4/2009	19:40	3.00	1.83	0.55	1.89	0.30
Test	100	43	8/10/2009	1:15	8/10/2009	14:55	5.73	1.75	0.20	0.47	0.11
Control	80	43	8/10/2009	1:15	8/10/2009	14:55	5.73	1.75	0.20	0.47	0.11
Test	100	44	8/15/2009	19:40	8/16/2009	21:50	5.69	14.25	2.29	1.89	0.16
Control	80	44	8/15/2009	19:40	8/16/2009	21:50	5.69	14.25	2.29	1.89	0.16
Test	100	45	8/17/2009	7:35	8/17/2009	23:55	0.90	4.42	1.10	2.84	0.25
Control	80	45	8/17/2009	7:35	8/17/2009	23:55	0.90	4.42	1.10	2.84	0.25

**DRAFT**

**Large-Scale Rainfall and Runoff Monitoring from Combined Sewer System for Test and Control Areas (data from KCMO, UMKC, and Tetra Tech) (cont.)**

Site	Area (acres)	Event #	Rain start date	Rain start time	Rain end date	Rain end time	Antecedent dry days	Rain dur. (hrs)	Total rain <sup>a</sup> (in)	5-minute peak rain intensity <sup>a</sup> (in/hr)	Avg rain int. (in/hr)
Test	100	46	8/19/2009	7:00	8/20/2009	12:05	1.79	17.17	0.91	0.95	0.05
Control	80	46	8/19/2009	7:00	8/20/2009	12:05	1.79	17.17	0.91	0.95	0.05
Test	100	47	8/27/2009	1:30	8/27/2009	17:45	7.06	4.33	0.12	0.47	0.03
Control	80	47	8/27/2009	1:30	8/27/2009	17:45	7.06	4.33	0.12	0.47	0.03
Test	100	48	9/4/2009	10:30	9/5/2009	17:05	8.19	18.67	0.40	0.63	0.02
Control	80	48	9/4/2009	10:30	9/5/2009	17:05	8.19	18.67	0.40	0.63	0.02
Test	100	49	9/8/2009	15:55	9/10/2009	5:20	3.45	25.50	0.32	0.49	0.01
Control	80	49	9/8/2009	15:55	9/10/2009	5:20	3.45	25.50	0.32	0.49	0.01
Test	100	50	9/21/2009	9:50	9/22/2009	10:10	11.68	12.42	0.76	0.64	0.06
Control	80	50	9/21/2009	9:50	9/22/2009	10:10	11.68	12.42	0.76	0.64	0.06
Test	100	51	9/26/2009	0:20	9/26/2009	16:30	4.09	4.25	0.40	0.52	0.09
Control	80	51	9/26/2009	0:20	9/26/2009	16:30	4.09	4.25	0.40	0.52	0.09
Test	100	52	9/30/2009	16:10	10/1/2009	23:05	4.48	19.00	0.14	0.44	0.01
Control	80	52	9/30/2009	16:10	10/1/2009	23:05	4.48	19.00	0.14	0.44	0.01
Test	100	53	10/6/2009	2:15	10/6/2009	18:05	4.63	3.92	0.11	0.30	0.03
Control	80	53	10/6/2009	2:15	10/6/2009	18:05	4.63	3.92	0.11	0.30	0.03
Test	100	54	10/7/2009	19:50	10/9/2009	17:25	1.57	33.67	1.98	1.43	0.06
Control	80	54	10/7/2009	19:50	10/9/2009	17:25	1.57	33.67	1.98	1.43	0.06
Test	100	55	10/13/2009	17:30	10/14/2009	16:20	4.50	10.92	0.34	0.61	0.03
Control	80	55	10/13/2009	17:30	10/14/2009	16:20	4.50	10.92	0.34	0.61	0.03
Test	100	56	10/14/2009	18:40	10/15/2009	12:05	0.59	5.50	0.12	0.29	0.02
Control	80	56	10/14/2009	18:40	10/15/2009	12:05	0.59	5.50	0.12	0.29	0.02
Test	100	57	10/20/2009	5:25	10/20/2009	22:25	5.22	5.08	0.31	1.10	0.06



**DRAFT****Large-Scale Rainfall and Runoff Monitoring from Combined Sewer System for Test and Control Areas (data from KCMO, UMKC, and Tetra Tech) (cont.)**

Site	Area (acres)	Event #	Rain start date	Rain start time	Rain end date	Rain end time	Antecedent dry days	Rain dur. (hrs)	Total rain <sup>a</sup> (in)	5-minute peak rain intensity <sup>a</sup> (in/hr)	Avg rain int. (in/hr)
Control	80	57	10/20/2009	5:25	10/20/2009	22:25	5.22	5.08	0.31	1.10	0.06
Test	100	58	10/21/2009	15:15	10/23/2009	3:00	1.20	23.83	1.01	0.41	0.04
Control	80	58	10/21/2009	15:15	10/23/2009	3:00	1.20	23.83	1.01	0.41	0.04
Test	100	59	10/25/2009	14:00	10/26/2009	11:45	2.95	9.83	0.71	0.58	0.07
Control	80	59	10/25/2009	14:00	10/26/2009	11:45	2.95	9.83	0.71	0.58	0.07
Test	100	60	10/29/2009	5:45	10/30/2009	11:25	3.25	17.75	0.79	0.70	0.04
Control	80	60	10/29/2009	5:45	10/30/2009	11:25	3.25	17.75	0.79	0.70	0.04
Test	100	61	11/14/2009	21:45	11/18/2009	6:05	15.93	68.42	1.24	1.63	0.02
Control	80	61	11/14/2009	21:45	11/18/2009	6:05	15.93	68.42	1.24	1.63	0.02
Test	100	62	12/22/2009	21:25	12/24/2009	23:55	35.14	38.58	1.73	4.25	0.04
Control	80	62	12/22/2009	21:25	12/24/2009	23:55	35.14	38.58	1.73	4.25	0.04
Test	100	63	12/28/2009	4:30	12/29/2009	1:15	3.69	8.83	0.12	0.47	0.01
Control	80	63	12/28/2009	4:30	12/29/2009	1:15	3.69	8.83	0.12	0.47	0.01
Test	100	64	12/30/2009	6:00	12/31/2009	6:35	1.69	12.67	0.43	1.42	0.03
Control	80	64	12/30/2009	6:00	12/31/2009	6:35	1.69	12.67	0.43	1.42	0.03
Test	100	65	1/19/2010	19:10	1/20/2010	11:35	20.02	4.50	0.12	0.94	0.03
Control	80	65	1/19/2010	19:10	1/20/2010	11:35	20.02	4.50	0.12	0.94	0.03
Test	100	66	2/5/2010	9:55	2/6/2010	15:05	16.43	17.25	0.28	0.47	0.02
Control	80	66	2/5/2010	9:55	2/6/2010	15:05	16.43	17.25	0.28	0.47	0.02
Test	100	67	2/19/2010	6:55	2/20/2010	4:20	13.16	9.50	0.43	0.47	0.05
Control	80	67	2/19/2010	6:55	2/20/2010	4:20	13.16	9.50	0.43	0.47	0.05
Test	100	68	2/21/2010	5:30	2/22/2010	6:10	1.55	12.75	0.51	1.42	0.04
Control	80	68	2/21/2010	5:30	2/22/2010	6:10	1.55	12.75	0.51	1.42	0.04

**DRAFT****Large-Scale Rainfall and Runoff Monitoring from Combined Sewer System for Test and Control Areas (data from KCMO, UMKC, and Tetra Tech) (cont.)**

Site	Area (acres)	Event #	Rain start date	Rain start time	Rain end date	Rain end time	Antecedent dry days	Rain dur. (hrs)	Total rain <sup>a</sup> (in)	5-minute peak rain intensity <sup>a</sup> (in/hr)	Avg rain int. (in/hr)
Test	100	69	3/8/2010	20:40	3/10/2010	1:50	15.10	17.25	0.32	0.94	0.02
Control	80	69	3/8/2010	20:40	3/10/2010	1:50	15.10	17.25	0.32	0.94	0.02
Test	100	70	3/10/2010	18:50	3/11/2010	14:20	1.20	7.58	0.94	2.36	0.12
Control	80	70	3/10/2010	18:50	3/11/2010	14:20	1.20	7.58	0.94	2.36	0.12
Test	100	71	3/21/2010	12:20	3/22/2010	2:30	10.41	2.25	0.20	1.42	0.09
Control	80	71	3/21/2010	12:20	3/22/2010	2:30	10.41	2.25	0.20	1.42	0.09
Test	100	72	3/24/2010	12:55	3/25/2010	8:15	2.93	7.42	0.20	0.47	0.03
Control	80	72	3/24/2010	12:55	3/25/2010	8:15	2.93	7.42	0.20	0.47	0.03
Test	100	73	3/27/2010	8:00	3/27/2010	22:20	2.49	2.42	0.12	0.94	0.05
Control	80	73	3/27/2010	8:00	3/27/2010	22:20	2.49	2.42	0.12	0.94	0.05
Test	100	74	4/2/2010	9:50	4/3/2010	0:45	5.98	3.00	0.38	1.35	0.13
Control	80	74	4/2/2010	9:50	4/3/2010	0:45	5.98	3.00	0.38	1.35	0.13
Test	100	75	4/5/2010	7:25	4/5/2010	21:20	2.77	2.00	0.76	2.34	0.38
Control	80	75	4/5/2010	7:25	4/5/2010	21:20	2.77	2.00	0.76	2.34	0.38
Test	100	76	4/6/2010	19:55	4/7/2010	12:35	1.44	4.75	0.69	1.37	0.15
Control	80	76	4/6/2010	19:55	4/7/2010	12:35	1.44	4.75	0.69	1.37	0.15
Test	100	77	4/16/2010	5:10	4/16/2010	21:05	9.19	4.00	0.11	0.35	0.03
Control	80	77	4/16/2010	5:10	4/16/2010	21:05	9.19	4.00	0.11	0.35	0.03
Test	100	78	4/22/2010	10:05	4/23/2010	19:35	6.04	21.58	2.43	0.98	0.11
Control	80	78	4/22/2010	10:05	4/23/2010	19:35	6.04	21.58	2.43	0.98	0.11
Test	100	79	4/24/2010	11:15	4/25/2010	22:35	1.15	23.42	0.85	0.43	0.04
Control	80	79	4/24/2010	11:15	4/25/2010	22:35	1.15	23.42	0.85	0.43	0.04
Test	100	80	4/30/2010	6:15	5/1/2010	1:15	4.82	7.08	0.75	1.23	0.11

**DRAFT**

**Large-Scale Rainfall and Runoff Monitoring from Combined Sewer System for Test and Control Areas (data from KCMO, UMKC, and Tetra Tech) (cont.)**

Site	Area (acres)	Event #	Rain start date	Rain start time	Rain end date	Rain end time	Antecedent dry days	Rain dur. (hrs)	Total rain <sup>a</sup> (in)	5-minute peak rain intensity <sup>a</sup> (in/hr)	Avg rain int. (in/hr)
Control	80	80	4/30/2010	6:15	5/1/2010	1:15	4.82	7.08	0.75	1.23	0.11
Test	100	81	5/10/2010	4:20	5/11/2010	13:20	9.63	21.08	1.35	2.98	0.06
Control	80	81	5/10/2010	4:20	5/11/2010	13:20	9.63	21.08	1.35	2.98	0.06
Test	100	82	5/12/2010	3:50	5/13/2010	20:25	1.10	28.67	1.82	2.62	0.06
Control	80	82	5/12/2010	3:50	5/13/2010	20:25	1.10	28.67	1.82	2.62	0.06
Test	100	83	5/15/2010	7:20	5/16/2010	22:40	1.95	27.42	0.72	0.64	0.03
Control	80	83	5/15/2010	7:20	5/16/2010	22:40	1.95	27.42	0.72	0.64	0.03
Test	100	84	5/19/2010	11:25	5/20/2010	12:55	3.03	13.58	1.17	0.69	0.09
Control	80	84	5/19/2010	11:25	5/20/2010	12:55	3.03	13.58	1.17	0.69	0.09
Test	100	85	5/20/2010	16:10	5/21/2010	13:45	0.63	9.67	0.17	0.61	0.02
Control	80	85	5/20/2010	16:10	5/21/2010	13:45	0.63	9.67	0.17	0.61	0.02
Test	100	86	6/2/2010	6:20	6/2/2010	19:35	12.19	1.33	0.70	2.59	0.52
Control	80	86	6/2/2010	6:20	6/2/2010	19:35	12.19	1.33	0.70	2.59	0.52
Test	100	87	6/7/2010	13:45	6/8/2010	1:45	5.25	0.08	0.22	2.64	2.64
Control	80	87	6/7/2010	13:45	6/8/2010	1:45	5.25	0.08	0.22	2.64	2.64
Test	100	88	6/8/2010	8:30	6/10/2010	0:30	0.78	28.08	2.06	2.16	0.07
Control	80	88	6/8/2010	8:30	6/10/2010	0:30	0.78	28.08	2.06	2.16	0.07
Test	100	89	6/12/2010	10:05	6/13/2010	1:40	2.90	3.67	2.39	2.81	0.65
Control	80	89	6/12/2010	10:05	6/13/2010	1:40	2.90	3.67	2.39	2.81	0.65
Test	100	90	6/13/2010	7:15	6/15/2010	0:45	0.73	29.58	3.45	4.20	0.12
Control	80	90	6/13/2010	7:15	6/15/2010	0:45	0.73	29.58	3.45	4.20	0.12
Test	100	91	6/15/2010	13:25	6/16/2010	16:40	1.02	15.33	0.30	0.68	0.02
Control	80	91	6/15/2010	13:25	6/16/2010	16:40	1.02	15.33	0.30	0.68	0.02

**DRAFT****Large-Scale Rainfall and Runoff Monitoring from Combined Sewer System for Test and Control Areas (data from KCMO, UMKC, and Tetra Tech) (cont.)**

Site	Area (acres)	Event #	Rain start date	Rain start time	Rain end date	Rain end time	Antecedent dry days	Rain dur. (hrs)	Total rain <sup>a</sup> (in)	5-minute peak rain intensity <sup>a</sup> (in/hr)	Avg rain int. (in/hr)
Test	100	92	6/16/2010	18:10	6/17/2010	8:00	0.56	1.92	0.88	1.72	0.46
Control	80	92	6/16/2010	18:10	6/17/2010	8:00	0.56	1.92	0.88	1.72	0.46
Test	100	93	6/19/2010	12:40	6/20/2010	13:10	2.69	12.58	0.41	1.50	0.03
Control	80	93	6/19/2010	12:40	6/20/2010	13:10	2.69	12.58	0.41	1.50	0.03
Test	100	94	6/21/2010	12:30	6/22/2010	0:30	1.47	0.08	0.18	2.16	2.16
Control	80	94	6/21/2010	12:30	6/22/2010	0:30	1.47	0.08	0.18	2.16	2.16
Test	100	95	7/3/2010	16:35	7/4/2010	4:55	12.17	0.42	0.13	1.08	0.31
Control	80	95	7/3/2010	16:35	7/4/2010	4:55	12.17	0.42	0.13	1.08	0.31
Test	100	96	7/4/2010	20:50	7/7/2010	2:45	1.16	42.00	1.60	2.31	0.04
Control	80	96	7/4/2010	20:50	7/7/2010	2:45	1.16	42.00	1.60	2.31	0.04
Test	100	97	7/11/2010	9:15	7/12/2010	14:45	4.77	17.58	2.29	7.84	0.13
Control	80	97	7/11/2010	9:15	7/12/2010	14:45	4.77	17.58	2.29	7.84	0.13
Test	100	98	7/19/2010	12:20	7/20/2010	2:10	7.40	1.92	0.16	1.68	0.08
Control	80	98	7/19/2010	12:20	7/20/2010	2:10	7.40	1.92	0.16	1.68	0.08
Test	100	99	7/20/2010	17:20	7/21/2010	11:55	1.13	6.67	1.78	8.61	0.27
Control	80	99	7/20/2010	17:20	7/21/2010	11:55	1.13	6.67	1.78	8.61	0.27
Test	100	100	7/24/2010	16:35	7/25/2010	13:15	3.69	8.75	0.64	1.15	0.07
Control	80	100	7/24/2010	16:35	7/25/2010	13:15	3.69	8.75	0.64	1.15	0.07
Test	100	101	7/30/2010	7:50	7/30/2010	20:10	5.27	0.42	0.13	0.62	0.31
Control	80	101	7/30/2010	7:50	7/30/2010	20:10	5.27	0.42	0.13	0.62	0.31
Test	100	102	8/13/2010	20:15	8/14/2010	11:10	14.50	3.00	0.39	0.86	0.13
Control	80	102	8/13/2010	20:15	8/14/2010	11:10	14.50	3.00	0.39	0.86	0.13
Test	100	103	8/16/2010	15:55	8/17/2010	4:40	2.69	0.83	0.21	2.28	0.25

**DRAFT****Large-Scale Rainfall and Runoff Monitoring from Combined Sewer System for Test and Control Areas (data from KCMO, UMKC, and Tetra Tech) (cont.)**

Site	Area (acres)	Event #	Rain start date	Rain start time	Rain end date	Rain end time	Antecedent dry days	Rain dur. (hrs)	Total rain <sup>a</sup> (in)	5-minute peak rain intensity <sup>a</sup> (in/hr)	Avg rain int. (in/hr)
Control	80	103	8/16/2010	15:55	8/17/2010	4:40	2.69	0.83	0.21	2.28	0.25
Test	100	104	8/20/2010	15:15	8/21/2010	11:45	3.94	8.58	1.92	3.20	0.22
Control	80	104	8/20/2010	15:15	8/21/2010	11:45	3.94	8.58	1.92	3.20	0.22
Test	100	105	8/31/2010	9:55	8/31/2010	22:05	10.42	0.25	0.11	0.73	0.44
Control	80	105	8/31/2010	9:55	8/31/2010	22:05	10.42	0.25	0.11	0.73	0.44
Test	100	106	8/31/2010	23:40	9/1/2010	22:50	0.56	11.25	0.93	1.91	0.08
Control	80	106	8/31/2010	23:40	9/1/2010	22:50	0.56	11.25	0.93	1.91	0.08
Test	100	107	9/10/2010	15:15	9/11/2010	13:15	9.18	10.08	0.23	0.31	0.02
Control	80	107	9/10/2010	15:15	9/11/2010	13:15	9.18	10.08	0.23	0.31	0.02
Test	100	108	9/13/2010	22:25	9/14/2010	18:10	2.88	7.83	1.68	1.72	0.21
Control	80	108	9/13/2010	22:25	9/14/2010	18:10	2.88	7.83	1.68	1.72	0.21
Test	100	109	9/15/2010	9:10	9/16/2010	8:35	1.12	11.50	0.58	0.46	0.05
Control	80	109	9/15/2010	9:10	9/16/2010	8:35	1.12	11.50	0.58	0.46	0.05
Test	100	110	9/18/2010	18:50	9/19/2010	9:40	2.92	2.92	0.16	0.43	0.05
Control	80	110	9/18/2010	18:50	9/19/2010	9:40	2.92	2.92	0.16	0.43	0.05
Test	100	111	9/21/2010	23:35	9/22/2010	18:05	3.08	6.58	0.75	1.65	0.11
Control	80	111	9/21/2010	23:35	9/22/2010	18:05	3.08	6.58	0.75	1.65	0.11
Test	100	112	9/23/2010	19:30	9/24/2010	14:25	1.56	7.00	0.43	0.67	0.06
Control	80	112	9/23/2010	19:30	9/24/2010	14:25	1.56	7.00	0.43	0.67	0.06
Test	100	113	9/25/2010	15:05	9/26/2010	7:35	1.52	4.58	0.14	0.58	0.03
Control	80	113	9/25/2010	15:05	9/26/2010	7:35	1.52	4.58	0.14	0.58	0.03
Test	100	114	10/11/2010	1:55	10/13/2010	5:00	15.26	39.17	0.91	0.87	0.02
Control	80	114	10/11/2010	1:55	10/13/2010	5:00	15.26	39.17	0.91	0.87	0.02

**DRAFT****Large-Scale Rainfall and Runoff Monitoring from Combined Sewer System for Test and Control Areas (data from KCMO, UMKC, and Tetra Tech) (cont.)**

Site	Area (acres)	Event #	Rain start date	Rain start time	Rain end date	Rain end time	Antecedent dry days	Rain dur. (hrs)	Total rain <sup>a</sup> (in)	5-minute peak rain intensity <sup>a</sup> (in/hr)	Avg rain int. (in/hr)
Test	100	115	10/22/2010	14:15	10/23/2010	15:35	9.88	13.42	0.23	0.93	0.02
Control	80	115	10/22/2010	14:15	10/23/2010	15:35	9.88	13.42	0.23	0.93	0.02
Test	100	116	11/11/2010	17:35	11/13/2010	9:20	19.58	27.83	1.69	0.94	0.06
Control	80	116	11/11/2010	17:35	11/13/2010	9:20	19.58	27.83	1.69	0.94	0.06
Test	100	117	11/17/2010	15:35	11/18/2010	5:35	4.76	2.08	0.12	0.47	0.06
Control	80	117	11/17/2010	15:35	11/18/2010	5:35	4.76	2.08	0.12	0.47	0.06
Test	100	118	12/31/2010	5:00	12/31/2010	20:45	43.47	3.83	0.39	0.94	0.10
Control	80	118	12/31/2010	5:00	12/31/2010	20:45	43.47	3.83	0.39	0.94	0.10
Test	100	119	1/22/2011	12:20	1/23/2011	3:40	22.15	3.42	0.12	0.47	0.03
Control	80	119	1/22/2011	12:20	1/23/2011	3:40	22.15	3.42	0.12	0.47	0.03
Test	100	120	2/24/2011	9:00	2/25/2011	3:00	32.72	6.08	0.35	0.47	0.06
Control	80	120	2/24/2011	9:00	2/25/2011	3:00	32.72	6.08	0.35	0.47	0.06
Test	100	121	2/26/2011	13:50	2/28/2011	8:20	1.95	30.58	1.22	2.36	0.04
Control	80	121	2/26/2011	13:50	2/28/2011	8:20	1.95	30.58	1.22	2.36	0.04
Test	100	122	3/4/2011	11:10	3/5/2011	1:40	4.61	2.58	0.24	0.94	0.09
Control	80	122	3/4/2011	11:10	3/5/2011	1:40	4.61	2.58	0.24	0.94	0.09
Test	100	123	3/8/2011	8:10	3/9/2011	1:10	3.77	5.08	0.39	0.47	0.08
Control	80	123	3/8/2011	8:10	3/9/2011	1:10	3.77	5.08	0.39	0.47	0.08
Test	100	124	3/13/2011	23:00	3/15/2011	0:25	5.41	13.50	0.20	0.47	0.01
Control	80	124	3/13/2011	23:00	3/15/2011	0:25	5.41	13.50	0.20	0.47	0.01
Test	100	125	3/19/2011	14:30	3/20/2011	4:15	5.08	1.83	0.32	0.94	0.17
Control	80	125	3/19/2011	14:30	3/20/2011	4:15	5.08	1.83	0.32	0.94	0.17
Test	100	126	4/3/2011	21:15	4/4/2011	10:20	15.20	1.17	0.31	0.94	0.27



**DRAFT****Large-Scale Rainfall and Runoff Monitoring from Combined Sewer System for Test and Control Areas (data from KCMO, UMKC, and Tetra Tech) (cont.)**

Site	Area (acres)	Event #	Rain start date	Rain start time	Rain end date	Rain end time	Antecedent dry days	Rain dur. (hrs)	Total rain <sup>a</sup> (in)	5-minute peak rain intensity <sup>a</sup> (in/hr)	Avg rain int. (in/hr)
Control	80	126	4/3/2011	21:15	4/4/2011	10:20	15.20	1.17	0.31	0.94	0.27
Test	100	127	4/7/2011	15:00	4/8/2011	13:15	3.69	10.33	0.12	0.47	0.01
Control	80	127	4/7/2011	15:00	4/8/2011	13:15	3.69	10.33	0.12	0.47	0.01
Test	100	128	4/8/2011	22:40	4/9/2011	13:00	0.89	2.42	0.32	1.89	0.13
Control	80	128	4/8/2011	22:40	4/9/2011	13:00	0.89	2.42	0.32	1.89	0.13
Test	100	129	4/14/2011	21:00	4/15/2011	21:05	5.83	12.17	1.10	2.36	0.09
Control	80	129	4/14/2011	21:00	4/15/2011	21:05	5.83	12.17	1.10	2.36	0.09
Test	100	130	4/21/2011	21:30	4/22/2011	22:45	6.51	13.33	0.39	0.94	0.03
Control	80	130	4/21/2011	21:30	4/22/2011	22:45	6.51	13.33	0.39	0.94	0.03
Test	100	131	4/25/2011	6:40	4/26/2011	12:30	2.83	17.92	1.02	0.94	0.06
Control	80	131	4/25/2011	6:40	4/26/2011	12:30	2.83	17.92	1.02	0.94	0.06
Test	100	132	5/5/2011	9:30	5/6/2011	5:45	9.37	8.33	0.59	0.47	0.07
Control	80	132	5/5/2011	9:30	5/6/2011	5:45	9.37	8.33	0.59	0.47	0.07
Test	100	133	5/7/2011	2:40	5/7/2011	17:00	1.37	2.42	0.55	2.83	0.23
Control	80	133	5/7/2011	2:40	5/7/2011	17:00	1.37	2.42	0.55	2.83	0.23
Test	100	134	5/11/2011	9:10	5/12/2011	10:00	4.17	12.92	0.71	1.89	0.05
Control	80	134	5/11/2011	9:10	5/12/2011	10:00	4.17	12.92	0.71	1.89	0.05
Test	100	135	5/19/2011	3:40	5/19/2011	23:30	7.23	7.92	0.67	0.94	0.08
Control	80	135	5/19/2011	3:40	5/19/2011	23:30	7.23	7.92	0.67	0.94	0.08
Test	100	136	5/20/2011	10:05	5/21/2011	0:30	0.94	2.50	0.51	0.94	0.20
Control	80	136	5/20/2011	10:05	5/21/2011	0:30	0.94	2.50	0.51	0.94	0.20
Test	100	137	5/21/2011	23:45	5/22/2011	12:40	1.47	1.00	0.47	1.89	0.47
Control	80	137	5/21/2011	23:45	5/22/2011	12:40	1.47	1.00	0.47	1.89	0.47

**DRAFT****Large-Scale Rainfall and Runoff Monitoring from Combined Sewer System for Test and Control Areas (data from KCMO, UMKC, and Tetra Tech) (cont.)**

Site	Area (acres)	Event #	Rain start date	Rain start time	Rain end date	Rain end time	Antecedent dry days	Rain dur. (hrs)	Total rain <sup>a</sup> (in)	5-minute peak rain intensity <sup>a</sup> (in/hr)	Avg rain int. (in/hr)
Test	100	138	5/24/2011	10:35	5/26/2011	11:30	2.41	37.00	1.38	1.89	0.04
Control	80	138	5/24/2011	10:35	5/26/2011	11:30	2.41	37.00	1.38	1.89	0.04
Test	100	139	6/10/2011	23:25	6/11/2011	14:15	15.99	2.92	0.60	3.84	0.21
Control	80	139	6/10/2011	23:25	6/11/2011	14:15	15.99	2.92	0.60	3.84	0.21
Test	100	140	6/16/2011	11:35	6/17/2011	21:10	5.39	21.67	0.60	1.44	0.03
Control	80	140	6/16/2011	11:35	6/17/2011	21:10	5.39	21.67	0.60	1.44	0.03
Test	100	141	6/18/2011	1:25	6/18/2011	16:20	0.67	3.00	0.70	1.75	0.23
Control	80	141	6/18/2011	1:25	6/18/2011	16:20	0.67	3.00	0.70	1.75	0.23
Test	100	142	6/19/2011	1:30	6/19/2011	22:00	0.88	8.58	0.36	1.08	0.04
Control	80	142	6/19/2011	1:30	6/19/2011	22:00	0.88	8.58	0.36	1.08	0.04
Test	100	143	6/20/2011	22:45	6/21/2011	12:25	1.53	1.75	0.22	0.54	0.13
Control	80	143	6/20/2011	22:45	6/21/2011	12:25	1.53	1.75	0.22	0.54	0.13
Test	100	144	6/27/2011	2:40	6/27/2011	18:15	6.09	3.67	0.55	1.24	0.15
Control	80	144	6/27/2011	2:40	6/27/2011	18:15	6.09	3.67	0.55	1.24	0.15
Test	100	145	7/2/2011	23:20	7/4/2011	2:30	5.71	15.25	0.49	1.88	0.03
Control	80	145	7/2/2011	23:20	7/4/2011	2:30	5.71	15.25	0.49	1.88	0.03
Test	100	146	7/6/2011	12:05	7/7/2011	0:05	2.90	0.08	0.37	4.44	4.44
Control	80	146	7/6/2011	12:05	7/7/2011	0:05	2.90	0.08	0.37	4.44	4.44
Test	100	147	7/7/2011	6:10	7/8/2011	6:45	0.75	12.67	0.75	2.25	0.06
Control	80	147	7/7/2011	6:10	7/8/2011	6:45	0.75	12.67	0.75	2.25	0.06
Test	100	148	7/12/2011	21:10	7/13/2011	12:00	5.10	2.92	1.38	3.06	0.47
Control	80	148	7/12/2011	21:10	7/13/2011	12:00	5.10	2.92	1.38	3.06	0.47
Test	100	149	7/30/2011	8:20	7/30/2011	20:50	17.34	0.58	0.22	1.06	0.38

**DRAFT****Large-Scale Rainfall and Runoff Monitoring from Combined Sewer System for Test and Control Areas (data from KCMO, UMKC, and Tetra Tech) (cont.)**

Site	Area (acres)	Event #	Rain start date	Rain start time	Rain end date	Rain end time	Antecedent dry days	Rain dur. (hrs)	Total rain <sup>a</sup> (in)	5-minute peak rain intensity <sup>a</sup> (in/hr)	Avg rain int. (in/hr)
Control	80	149	7/30/2011	8:20	7/30/2011	20:50	17.34	0.58	0.22	1.06	0.38
Test	100	150	8/8/2011	2:40	8/8/2011	22:40	8.74	8.08	0.12	0.47	0.01
Control	80	150	8/8/2011	2:40	8/8/2011	22:40	8.74	8.08	0.12	0.47	0.01
Test	100	151	8/12/2011	11:20	8/13/2011	1:30	4.02	2.25	0.91	1.89	0.40
Control	80	151	8/12/2011	11:20	8/13/2011	1:30	4.02	2.25	0.91	1.89	0.40
Test	100	152	8/15/2011	8:55	8/16/2011	1:00	2.81	4.17	1.02	1.89	0.25
Control	80	152	8/15/2011	8:55	8/16/2011	1:00	2.81	4.17	1.02	1.89	0.25
Test	100	153	8/18/2011	23:30	8/19/2011	13:20	3.43	1.92	0.83	2.36	0.43
Control	80	153	8/18/2011	23:30	8/19/2011	13:20	3.43	1.92	0.83	2.36	0.43
Test	100	154	8/20/2011	1:55	8/20/2011	22:00	1.02	8.17	0.98	2.83	0.12
Control	80	154	8/20/2011	1:55	8/20/2011	22:00	1.02	8.17	0.98	2.83	0.12
Test	100	155	8/22/2011	10:35	8/22/2011	23:15	2.02	0.75	0.12	0.47	0.16
Control	80	155	8/22/2011	10:35	8/22/2011	23:15	2.02	0.75	0.12	0.47	0.16
Test	100	156	9/3/2011	16:55	9/4/2011	9:55	12.23	5.08	0.51	1.42	0.10
Control	80	156	9/3/2011	16:55	9/4/2011	9:55	12.23	5.08	0.51	1.42	0.10
Test	100	157	9/9/2011	13:20	9/10/2011	5:05	5.64	3.83	0.35	1.42	0.09
Control	80	157	9/9/2011	13:20	9/10/2011	5:05	5.64	3.83	0.35	1.42	0.09
Test	100	158	9/17/2011	12:00	9/18/2011	0:55	7.78	1.00	0.16	0.47	0.16
Control	80	158	9/17/2011	12:00	9/18/2011	0:55	7.78	1.00	0.16	0.47	0.16
Test	100	159	9/18/2011	6:15	9/18/2011	21:45	0.72	3.58	0.47	0.94	0.13
Control	80	159	9/18/2011	6:15	9/18/2011	21:45	0.72	3.58	0.47	0.94	0.13
Test	100	160	11/2/2011	16:20	11/3/2011	15:20	45.27	11.08	1.18	0.94	0.11
Control	80	160	11/2/2011	16:20	11/3/2011	15:20	45.27	11.08	1.18	0.94	0.11

**DRAFT****Large-Scale Rainfall and Runoff Monitoring from Combined Sewer System for Test and Control Areas (data from KCMO, UMKC, and Tetra Tech) (cont.)**

Site	Area (acres)	Event #	Rain start date	Rain start time	Rain end date	Rain end time	Antecedent dry days	Rain dur. (hrs)	Total rain <sup>a</sup> (in)	5-minute peak rain intensity <sup>a</sup> (in/hr)	Avg rain int. (in/hr)
Test	100	161	11/7/2011	14:15	11/9/2011	15:40	4.45	37.50	2.01	2.83	0.05
Control	80	161	11/7/2011	14:15	11/9/2011	15:40	4.45	37.50	2.01	2.83	0.05
Test	100	162	11/22/2011	2:20	11/22/2011	18:20	12.94	4.08	0.28	0.47	0.07
Control	80	162	11/22/2011	2:20	11/22/2011	18:20	12.94	4.08	0.28	0.47	0.07
Test	100	163	11/25/2011	23:05	11/26/2011	20:45	3.69	9.75	1.06	0.94	0.11
Control	80	163	11/25/2011	23:05	11/26/2011	20:45	3.69	9.75	1.06	0.94	0.11
Test	100	164	12/2/2011	22:25	12/4/2011	7:10	6.57	20.83	0.79	0.94	0.04
Control	80	164	12/2/2011	22:25	12/4/2011	7:10	6.57	20.83	0.79	0.94	0.04
Test	100	165	12/13/2011	9:05	12/14/2011	16:40	9.58	19.67	0.35	0.47	0.02
Control	80	165	12/13/2011	9:05	12/14/2011	16:40	9.58	19.67	0.35	0.47	0.02
Test	100	166	12/19/2011	11:30	12/20/2011	22:35	5.28	23.17	1.34	0.47	0.06
Control	80	166	12/19/2011	11:30	12/20/2011	22:35	5.28	23.17	1.34	0.47	0.06
Test	100	167	1/22/2012	18:30	1/23/2012	8:30	33.33	2.08	0.28	1.42	0.13
Control	80	167	1/22/2012	18:30	1/23/2012	8:30	33.33	2.08	0.28	1.42	0.13
Test	100	168	2/3/2012	6:55	2/4/2012	14:15	11.43	19.42	1.18	1.42	0.06
Control	80	168	2/3/2012	6:55	2/4/2012	14:15	11.43	19.42	1.18	1.42	0.06
Test	100	169	2/13/2012	13:20	2/14/2012	9:55	9.46	8.67	0.12	0.47	0.01
Control	80	169	2/13/2012	13:20	2/14/2012	9:55	9.46	8.67	0.12	0.47	0.01
Test	100	170	2/20/2012	19:35	2/21/2012	8:25	6.90	0.92	0.35	0.94	0.39
Control	80	170	2/20/2012	19:35	2/21/2012	8:25	6.90	0.92	0.35	0.94	0.39
Test	100	171	2/28/2012	13:35	2/29/2012	10:15	7.71	8.75	0.20	0.94	0.02
Control	80	171	2/28/2012	13:35	2/29/2012	10:15	7.71	8.75	0.20	0.94	0.02
Test	100	172	3/8/2012	2:10	3/8/2012	16:30	8.16	2.42	0.32	0.47	0.13

**DRAFT****Large-Scale Rainfall and Runoff Monitoring from Combined Sewer System for Test and Control Areas (data from KCMO, UMKC, and Tetra Tech) (cont.)**

Site	Area (acres)	Event #	Rain start date	Rain start time	Rain end date	Rain end time	Antecedent dry days	Rain dur. (hrs)	Total rain <sup>a</sup> (in)	5-minute peak rain intensity <sup>a</sup> (in/hr)	Avg rain int. (in/hr)
Control	80	172	3/8/2012	2:10	3/8/2012	16:30	8.16	2.42	0.32	0.47	0.13
Test	100	173	3/11/2012	8:30	3/12/2012	13:15	3.16	16.83	0.59	0.94	0.04
Control	80	173	3/11/2012	8:30	3/12/2012	13:15	3.16	16.83	0.59	0.94	0.04
Test	100	174	3/19/2012	14:25	3/21/2012	7:55	7.55	29.58	1.77	1.32	0.06
Control	80	174	3/19/2012	14:25	3/21/2012	7:55	7.55	29.58	1.77	1.32	0.06
Test	100	175	3/21/2012	11:30	3/22/2012	8:50	0.65	9.42	0.25	0.50	0.03
Control	80	175	3/21/2012	11:30	3/22/2012	8:50	0.65	9.42	0.25	0.50	0.03
Test	100	176	3/22/2012	16:10	3/23/2012	12:25	0.80	8.33	0.36	0.64	0.04
Control	80	176	3/22/2012	16:10	3/23/2012	12:25	0.80	8.33	0.36	0.64	0.04
Test	100	177	4/4/2012	20:45	4/5/2012	9:10	12.84	0.50	0.18	0.54	0.36
Control	80	177	4/4/2012	20:45	4/5/2012	9:10	12.84	0.50	0.18	0.54	0.36
Test	100	178	4/12/2012	15:20	4/13/2012	4:15	7.75	1.00	0.12	0.72	0.12
Control	80	178	4/12/2012	15:20	4/13/2012	4:15	7.75	1.00	0.12	0.72	0.12
Test	100	179	4/27/2012	20:40	4/28/2012	8:40	15.18	0.08	0.12	1.44	1.44
Control	80	179	4/27/2012	20:40	4/28/2012	8:40	15.18	0.08	0.12	1.44	1.44
Test	100	180	4/28/2012	22:45	4/30/2012	7:50	1.08	21.17	0.75	0.87	0.04
Control	80	180	4/28/2012	22:45	4/30/2012	7:50	1.08	21.17	0.75	0.87	0.04
Test	100	181	5/1/2012	1:40	5/1/2012	22:30	1.24	8.92	0.43	0.74	0.05
Control	80	181	5/1/2012	1:40	5/1/2012	22:30	1.24	8.92	0.43	0.74	0.05
Test	100	182	5/6/2012	10:05	5/7/2012	20:55	4.98	22.92	1.85	2.04	0.08
Control	80	182	5/6/2012	10:05	5/7/2012	20:55	4.98	22.92	1.85	2.04	0.08
Test	100	183	5/24/2012	20:35	5/25/2012	20:10	17.48	11.67	0.40	1.60	0.03
Control	80	183	5/24/2012	20:35	5/25/2012	20:10	17.48	11.67	0.40	1.60	0.03

**DRAFT**

**Large-Scale Rainfall and Runoff Monitoring from Combined Sewer System for Test and Control Areas (data from KCMO, UMKC, and Tetra Tech) (cont.)**

Site	Area (acres)	Event #	Rain start date	Rain start time	Rain end date	Rain end time	Antecedent dry days	Rain dur. (hrs)	Total rain <sup>a</sup> (in)	5-minute peak rain intensity <sup>a</sup> (in/hr)	Avg rain int. (in/hr)
Test	100	184	6/11/2012	2:50	6/11/2012	19:35	16.77	4.83	1.22	1.89	0.25
Control	80	184	6/11/2012	2:50	6/11/2012	19:35	16.77	4.83	1.22	1.89	0.25
Test	100	185	6/21/2012	1:20	6/21/2012	21:00	9.74	7.75	0.91	2.83	0.12
Control	80	185	6/21/2012	1:20	6/21/2012	21:00	9.74	7.75	0.91	2.83	0.12
Test	100	186	7/26/2012	0:45	7/26/2012	16:50	34.65	4.17	0.39	0.95	0.09
Control	80	186	7/26/2012	0:45	7/26/2012	16:50	34.65	4.17	0.39	0.95	0.09



**DRAFT**

**Calculated Rainfall and Runoff Characteristics from Combined Sewage Monitoring (data from KCMO, UMKC, and TetraTech)**

Site	Area (acres)	Evt #	Pipeflow start date	Pipeflow start time	Pipeflow end date	Flow end time	Flow dur. (hrs)	Total pipeflow discharge volume (ft3)	Total disch. (in)	Peak flow disch. rate (CFS)	Avg flow disch. rate (CFS)	Peak /avg pipe flow rate ratio	Rv	flow/ rain dur. ratio
Test	100	1	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	1	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	2	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	2	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	3	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	3	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	4	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	4	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	5	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	5	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	6	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	6	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	7	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	7	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	8	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	8	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	9	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	9	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	10	3/23/2009	21:10	3/24/2009	17:55	20.75	30,064	0.08	3.90	0.50	7.7	0.15	2.3
Control	80	10	3/23/2009	21:10	3/24/2009	17:55	20.75	22,401	0.08	1.63	0.48	3.4	0.14	2.3
Test	100	11	3/26/2009	19:55	3/27/2009	13:20	17.42	6,629	0.02	0.86	0.33	2.6	0.07	3.2
Control	80	11	3/26/2009	19:55	3/27/2009	13:20	17.42	55,182	0.19	1.63	0.98	1.7	0.69	3.2
Test	100	12	3/28/2009	9:15	3/29/2009	6:45	21.50	79,097	0.22	4.04	1.12	3.6	0.40	2.2

**DRAFT****Calculated Rainfall and Runoff Characteristics from Combined Sewage Monitoring (data from KCMO, UMKC, and TetraTech) (cont.)**

Site	Area (acres)	Evt #	Pipeflow start date	Pipeflow start time	Pipeflow end date	Flow end time	Flow dur. (hrs)	Total pipeflow discharge volume (ft3)	Total disch. (in)	Peak flow disch. rate (CFS)	Avg flow disch. rate (CFS)	Peak /avg pipe flow rate ratio	Rv	flow/ rain dur. ratio
Control	80	12	3/28/2009	9:15	3/29/2009	6:45	21.50	103,525	0.36	4.99	1.89	2.6	0.65	2.2
Test	100	13	3/29/2009	8:50	3/30/2009	2:10	17.33	52,158	0.14	2.47	1.58	1.6	0.36	3.2
Control	80	13	3/29/2009	8:50	3/30/2009	2:10	17.33	40,909	0.14	5.17	2.33	2.2	0.36	3.2
Test	100	14	3/30/2009	23:20	3/31/2009	12:25	13.08	21,517	0.06	3.65	1.87	2.0	0.25	11.2
Control	80	14	3/30/2009	23:20	3/31/2009	12:25	13.08	7,661	0.03	1.38	1.16	1.2	0.11	11.2
Test	100	15	4/2/2009	5:55	4/2/2009	23:40	17.75	10,892	0.03	0.64	0.83	0.8	0.25	3.0
Control	80	15	4/2/2009	5:50	4/2/2009	23:40	17.83	31,433	0.11	2.04	1.16	1.8	0.92	3.0
Test	100	16	4/9/2009	20:05	4/11/2009	1:15	29.17	92,607	0.26	2.89	1.18	2.5	0.27	1.7
Control	80	16	4/9/2009	20:05	4/11/2009	1:15	29.17	297,763	1.03	5.21	3.05	1.7	1.08	1.7
Test	100	17	4/12/2009	14:05	4/13/2009	19:55	29.83	40,657	0.11	1.40	0.85	1.6	0.26	1.7
Control	80	17	4/12/2009	14:05	4/13/2009	19:55	29.83	30,600	0.11	2.67	1.47	1.8	0.24	1.7
Test	100	18	4/18/2009	7:30	4/19/2009	0:40	17.17	27,438	0.08	5.33	0.87	6.2	0.14	3.1
Control	80	18	4/18/2009	7:15	4/19/2009	0:40	17.42	23,220	0.08	5.26	1.23	4.3	0.14	3.2
Test	100	19	4/19/2009	3:25	4/19/2009	18:55	15.50	36,594	0.10	5.71	1.03	5.6	0.37	4.1
Control	80	19	4/19/2009	3:15	4/19/2009	18:55	15.67	57,349	0.20	3.44	1.63	2.1	0.72	4.2
Test	100	20	4/26/2009	22:45	4/28/2009	0:05	25.33	220,686	0.61	10.68	2.78	3.8	0.28	1.9
Control	80	20	4/26/2009	22:45	4/28/2009	0:05	25.33	445,788	1.54	11.74	5.39	2.2	0.71	1.9
Test	100	21	4/29/2009	14:50	4/30/2009	6:15	15.42	67,222	0.19	12.48	1.91	6.5	0.28	4.4
Control	80	21	4/29/2009	14:50	4/30/2009	6:15	15.42	37,279	0.13	10.09	1.10	9.2	0.19	4.4
Test	100	22	4/30/2009	6:20	5/1/2009	8:10	25.83	21,063	0.06	2.02	1.26	1.6	0.04	1.9
Control	80	22	4/30/2009	6:20	5/1/2009	8:10	25.83	78,316	0.27	2.13	1.02	2.1	0.18	1.9
Test	100	23	5/8/2009	6:10	5/8/2009	20:15	14.08	13,574	0.04	2.03	0.50	4.1	0.12	6.0
Control	80	23	5/8/2009	6:00	5/8/2009	20:15	14.25	10,945	0.04	2.63	0.64	4.1	0.12	6.1

**DRAFT****Calculated Rainfall and Runoff Characteristics from Combined Sewage Monitoring (data from KCMO, UMKC, and TetraTech) (cont.)**

Site	Area (acres)	Evt #	Pipeflow start date	Pipeflow start time	Pipeflow end date	Flow end time	Flow dur. (hrs)	Total pipeflow discharge volume (ft3)	Total disch. (in)	Peak flow disch. rateb (CFS)	Avg flow disch. rate (CFS)	Peak /avg pipe flow rate ratio	Rv	flow/ rain dur. ratio
Test	100	24	5/13/2009	18:10	5/14/2009	6:30	12.33	8,072	0.02	10.60	0.36	29.5	0.08	24.7
Control	80	24	5/13/2009	18:05	5/14/2009	6:30	12.42	7,822	0.03	6.98	0.43	16.1	0.10	24.8
Test	100	25	5/15/2009	17:15	5/16/2009	9:00	15.75	60,140	0.17	17.02	1.26	13.5	0.12	4.0
Control	80	25	5/15/2009	17:10	5/16/2009	9:00	15.83	60,075	0.21	19.67	1.32	14.9	0.15	4.0
Test	100	26	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	26	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	27	6/2/2009	13:10	6/3/2009	6:45	17.58	53,648	0.15	12.61	0.96	13.1	0.38	3.1
Control	80	27	6/2/2009	13:10	6/3/2009	6:45	17.58	25,810	0.09	6.65	0.62	10.7	0.23	3.1
Test	100	28	6/8/2009	2:35	6/8/2009	14:55	12.33	3,975	0.01	1.71	0.21	8.1	0.06	29.6
Control	80	28	6/8/2009	2:35	6/8/2009	14:55	12.33	4,745	0.02	1.60	0.28	5.8	0.08	29.6
Test	100	29	6/9/2009	10:40	6/10/2009	10:00	23.33	48,996	0.13	25.71	0.67	38.4	0.06	2.0
Control	80	29	6/9/2009	10:35	6/10/2009	10:00	23.42	124,631	0.43	35.27	4.50	7.8	0.21	2.0
Test	100	30	6/11/2009	2:40	6/11/2009	16:10	13.50	10,503	0.03	3.63	0.24	15.4	0.07	8.5
Control	80	30	6/11/2009	2:40	6/11/2009	16:10	13.50	17,489	0.06	12.84	1.74	7.4	0.14	8.5
Test	100	31	6/15/2009	2:35	6/15/2009	21:50	19.25	14,795	0.04	8.92	0.21	41.7	0.04	2.6
Control	80	31	6/15/2009	2:35	6/15/2009	21:50	19.25	68,965	0.24	23.01	1.23	18.7	0.25	2.6
Test	100	32	6/15/2009	22:45	6/16/2009	18:15	19.50	59,214	0.16	8.24	0.89	9.3	0.10	2.5
Control	80	32	6/15/2009	22:35	6/16/2009	18:15	19.67	170,626	0.59	19.98	2.59	7.7	0.37	2.5
Test	100	33	6/23/2009	23:40	6/24/2009	12:20	12.67	8,703	0.02	2.77	0.39	7.0	0.07	13.8
Control	80	33	6/23/2009	23:30	6/24/2009	12:20	12.83	6,012	0.02	2.73	0.34	8.1	0.06	14.0
Test	100	34	7/3/2009	8:20	7/3/2009	23:20	15.00	15,025	0.04	2.54	0.53	4.8	0.13	4.9
Control	80	34	7/3/2009	8:20	7/3/2009	23:20	15.00	10,723	0.04	2.17	0.44	5.0	0.12	4.9
Test	100	35	7/4/2009	0:45	7/4/2009	17:15	16.50	90,892	0.25	14.80	1.70	8.7	0.19	3.5

**DRAFT****Calculated Rainfall and Runoff Characteristics from Combined Sewage Monitoring (data from KCMO, UMKC, and TetraTech) (cont.)**

Site	Area (acres)	Evt #	Pipeflow start date	Pipeflow start time	Pipeflow end date	Flow end time	Flow dur. (hrs)	Total pipeflow discharge volume (ft3)	Total disch. (in)	Peak flow disch. rateb (CFS)	Avg flow disch. rate (CFS)	Peak /avg pipe flow rate ratio	Rv	flow/ rain dur. ratio
Control	80	35	7/4/2009	0:40	7/4/2009	17:15	16.58	54,185	0.19	9.32	1.12	8.3	0.14	3.6
Test	100	36	7/6/2009	20:05	7/7/2009	8:05	12.00	3,560	0.01	0.27	0.39	0.7	0.04	72.0
Control	80	36	7/6/2009	20:00	7/7/2009	8:05	12.08	3,184	0.01	0.45	0.33	1.4	0.04	72.5
Test	100	37	7/10/2009	5:15	7/10/2009	17:20	12.08	5,273	0.01	2.95	0.38	7.8	0.09	48.3
Control	80	37	7/10/2009	5:10	7/10/2009	17:20	12.17	4,994	0.02	2.25	0.27	8.2	0.11	48.7
Test	100	38	7/12/2009	8:00	7/13/2009	5:45	21.75	55,946	0.15	30.80	1.00	30.7	0.20	2.2
Control	80	38	7/12/2009	7:55	7/13/2009	5:45	21.83	35,357	0.12	47.96	0.69	69.9	0.15	2.2
Test	100	39	7/20/2009	16:45	7/21/2009	14:35	21.83	31,973	0.09	3.53	0.73	4.9	0.14	2.2
Control	80	39	7/20/2009	16:45	7/21/2009	14:35	21.83	14,855	0.05	1.52	0.41	3.7	0.08	2.2
Test	100	40	7/27/2009	21:35	7/29/2009	3:40	30.08	57,422	0.16	14.58	0.81	17.9	0.09	1.7
Control	80	40	7/27/2009	21:35	7/29/2009	3:40	30.08	36,446	0.13	14.11	0.52	27.0	0.07	1.7
Test	100	41	8/1/2009	4:00	8/1/2009	17:45	13.75	18,127	0.05	2.29	0.58	3.9	0.16	7.5
Control	80	41	8/1/2009	4:00	8/1/2009	17:45	13.75	5,912	0.02	1.74	0.44	3.9	0.06	7.5
Test	100	42	8/4/2009	5:55	8/4/2009	19:40	13.75	28,008	0.08	10.51	0.62	16.9	0.14	7.5
Control	80	42	8/4/2009	5:55	8/4/2009	19:40	13.75	10,753	0.04	5.82	0.41	14.2	0.07	7.5
Test	100	43	8/10/2009	1:20	8/10/2009	14:55	13.58	16,860	0.05	4.86	0.39	12.5	0.24	7.8
Control	80	43	8/10/2009	1:15	8/10/2009	14:55	13.67	5,777	0.02	1.99	0.27	7.4	0.10	7.8
Test	100	44	8/15/2009	19:45	8/16/2009	21:50	26.08	126,506	0.35	13.34	1.54	8.6	0.15	1.8
Control	80	44	8/15/2009	19:40	8/16/2009	21:50	26.17	67,821	0.23	9.49	0.93	10.2	0.10	1.8
Test	100	45	8/17/2009	7:35	8/17/2009	23:55	16.33	76,509	0.21	28.27	1.83	15.4	0.19	3.7
Control	80	45	8/17/2009	7:35	8/17/2009	23:55	16.33	41,390	0.14	15.91	1.04	15.3	0.13	3.7
Test	100	46	8/19/2009	7:00	8/20/2009	12:05	29.08	65,378	0.18	11.86	1.14	10.4	0.20	1.7
Control	80	46	8/19/2009	7:00	8/20/2009	12:05	29.08	29,237	0.10	7.63	0.56	13.6	0.11	1.7

**DRAFT****Calculated Rainfall and Runoff Characteristics from Combined Sewage Monitoring (data from KCMO, UMKC, and TetraTech) (cont.)**

Site	Area (acres)	Evt #	Pipeflow start date	Pipeflow start time	Pipeflow end date	Flow end time	Flow dur. (hrs)	Total pipeflow discharge volume (ft3)	Total disch. (in)	Peak flow disch. rateb (CFS)	Avg flow disch. rate (CFS)	Peak /avg pipe flow rate ratio	Rv	flow/ rain dur. ratio
Test	100	47	8/27/2009	1:35	8/27/2009	17:45	16.17	11,322	0.03	0.65	0.42	1.5	0.26	3.7
Control	80	47	8/27/2009	1:30	8/27/2009	17:45	16.25	7,329	0.03	0.71	0.27	2.6	0.21	3.8
Test	100	48	9/4/2009	10:40	9/5/2009	17:05	30.42	26,421	0.07	2.76	0.38	7.3	0.18	1.6
Control	80	48	9/4/2009	10:30	9/5/2009	17:05	30.58	10,135	0.03	1.38	0.23	6.0	0.09	1.6
Test	100	49	9/8/2009	16:00	9/10/2009	5:20	37.33	22,964	0.06	1.98	0.32	6.3	0.20	1.5
Control	80	49	9/8/2009	15:55	9/10/2009	5:20	37.42	12,939	0.04	2.00	0.26	7.6	0.14	1.5
Test	100	50	9/21/2009	9:55	9/22/2009	10:10	24.25	39,203	0.11	2.79	0.58	4.8	0.14	2.0
Control	80	50	9/21/2009	9:50	9/22/2009	10:10	24.33	25,220	0.09	2.50	0.48	5.3	0.11	2.0
Test	100	51	9/26/2009	0:25	9/26/2009	16:30	16.08	24,862	0.07	3.98	0.49	8.2	0.17	3.8
Control	80	51	9/26/2009	0:20	9/26/2009	16:30	16.17	15,214	0.05	2.11	0.42	5.1	0.13	3.8
Test	100	52	9/30/2009	16:15	10/1/2009	23:05	30.83	8,773	0.02	0.69	0.16	4.4	0.17	1.6
Control	80	52	9/30/2009	16:10	10/1/2009	23:05	30.92	15,937	0.05	1.13	0.33	3.5	0.39	1.6
Test	100	53	10/6/2009	2:15	10/6/2009	18:05	15.83	5,227	0.01	1.00	0.14	7.1	0.13	4.0
Control	80	53	10/6/2009	2:15	10/6/2009	18:05	15.83	5,658	0.02	1.01	0.26	3.8	0.18	4.0
Test	100	54	10/7/2009	19:55	10/9/2009	17:25	45.50	118,767	0.33	7.97	0.75	10.6	0.17	1.4
Control	80	54	10/7/2009	19:50	10/9/2009	17:25	45.58	51,645	0.18	4.77	0.46	10.5	0.09	1.4
Test	100	55	10/13/2009	17:30	10/14/2009	16:20	22.83	18,008	0.05	2.34	0.43	5.5	0.15	2.1
Control	80	55	10/13/2009	17:30	10/14/2009	16:20	22.83	16,653	0.06	2.11	0.36	5.8	0.17	2.1
Test	100	56	10/14/2009	18:45	10/15/2009	12:05	17.33	5,819	0.02	0.50	0.35	1.4	0.13	3.2
Control	80	56	10/14/2009	18:40	10/15/2009	12:05	17.42	5,833	0.02	0.80	0.28	2.8	0.17	3.2
Test	100	57	10/20/2009	5:25	10/20/2009	22:25	17.00	13,571	0.04	5.84	0.32	18.0	0.12	3.3
Control	80	57	10/20/2009	5:25	10/20/2009	22:25	17.00	7,830	0.03	4.13	0.29	14.4	0.09	3.3
Test	100	58	10/21/2009	15:25	10/23/2009	3:00	35.58	81,098	0.22	2.53	0.70	3.6	0.22	1.5

**DRAFT****Calculated Rainfall and Runoff Characteristics from Combined Sewage Monitoring (data from KCMO, UMKC, and TetraTech) (cont.)**

Site	Area (acres)	Evt #	Pipeflow start date	Pipeflow start time	Pipeflow end date	Flow end time	Flow dur. (hrs)	Total pipeflow discharge volume (ft3)	Total disch. (in)	Peak flow disch. rateb (CFS)	Avg flow disch. rate (CFS)	Peak /avg pipe flow rate ratio	Rv	flow/ rain dur. ratio
Control	80	58	10/21/2009	15:15	10/23/2009	3:00	35.75	39,163	0.13	1.61	0.43	3.7	0.13	1.5
Test	100	59	10/25/2009	14:00	10/26/2009	11:45	21.75	48,723	0.13	4.28	0.83	5.1	0.19	2.2
Control	80	59	10/25/2009	14:00	10/26/2009	11:45	21.75	24,491	0.08	2.46	0.57	4.3	0.12	2.2
Test	100	60	10/29/2009	5:50	10/30/2009	11:25	29.58	56,675	0.16	6.76	0.81	8.4	0.20	1.7
Control	80	60	10/29/2009	5:45	10/30/2009	11:25	29.67	34,620	0.12	3.01	0.54	5.6	0.15	1.7
Test	100	61	11/14/2009	21:55	11/18/2009	6:05	80.17	102,841	0.28	1.43	0.40	3.6	0.23	1.2
Control	80	61	11/14/2009	21:45	11/18/2009	6:05	80.33	97,034	0.33	1.56	0.54	2.9	0.27	1.2
Test	100	62	12/22/2009	21:35	12/24/2009	23:55	50.33	76,184	0.21	4.72	0.43	10.9	0.12	1.3
Control	80	62	12/22/2009	21:25	12/24/2009	23:55	50.50	55,517	0.19	2.48	0.58	4.3	0.11	1.3
Test	100	63	12/28/2009	4:35	12/29/2009	1:15	20.67	8,777	0.02	0.25	0.21	1.2	0.20	2.3
Control	80	63	12/28/2009	4:30	12/29/2009	1:15	20.75	5,838	0.02	0.61	0.44	1.4	0.17	2.3
Test	100	64	12/30/2009	6:00	12/31/2009	6:35	24.58	7,666	0.02	0.23	0.24	1.0	0.05	1.9
Control	80	64	12/30/2009	6:00	12/31/2009	6:35	24.58	6,887	0.02	0.73	0.50	1.5	0.05	1.9
Test	100	65	1/19/2010	19:10	1/20/2010	11:35	16.42	2,591	0.01	0.15	0.52	0.3	0.06	3.6
Control	80	65	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	66	2/5/2010	10:05	2/6/2010	15:05	29.00	9,221	0.03	0.33	0.21	1.5	0.09	1.7
Control	80	66	2/5/2010	9:55	2/6/2010	15:05	29.17	16,573	0.06	0.99	0.53	1.9	0.21	1.7
Test	100	67	2/19/2010	6:55	2/20/2010	4:20	21.42	21,898	0.06	1.50	0.45	3.3	0.14	2.3
Control	80	67	2/19/2010	6:55	2/20/2010	4:20	21.42	25,295	0.09	1.65	0.70	2.3	0.20	2.3
Test	100	68	2/21/2010	5:30	2/22/2010	6:10	24.67	17,532	0.05	1.76	1.05	1.7	0.09	1.9
Control	80	68	2/21/2010	5:30	2/22/2010	6:10	24.67	14,083	0.05	2.28	0.99	2.3	0.09	1.9
Test	100	69	3/8/2010	20:40	3/10/2010	1:50	29.17	12,837	0.04	0.97	0.32	3.1	0.11	1.7
Control	80	69	3/8/2010	20:40	3/10/2010	1:50	29.17	19,122	0.07	1.32	0.52	2.5	0.21	1.7

**DRAFT**

**Calculated Rainfall and Runoff Characteristics from Combined Sewage Monitoring (data from KCMO, UMKC, and TetraTech) (cont.)**

Site	Area (acres)	Evt #	Pipeflow start date	Pipeflow start time	Pipeflow end date	Flow end time	Flow dur. (hrs)	Total pipeflow discharge volume (ft3)	Total disch. (in)	Peak flow disch. rateb (CFS)	Avg flow disch. rate (CFS)	Peak /avg pipe flow rate ratio	Rv	flow/ rain dur. ratio
Test	100	70	3/10/2010	19:00	3/11/2010	14:20	19.33	49,191	0.14	6.16	0.93	6.6	0.14	2.5
Control	80	70	3/10/2010	18:50	3/11/2010	14:20	19.50	29,437	0.10	4.74	1.09	4.4	0.11	2.6
Test	100	71	3/21/2010	12:20	3/22/2010	2:30	14.17	4,150	0.01	0.28	0.58	0.5	0.06	6.3
Control	80	71	3/21/2010	12:20	3/22/2010	2:30	14.17	6,072	0.02	1.26	0.87	1.5	0.11	6.3
Test	100	72	3/24/2010	12:55	3/25/2010	8:15	19.33	8,362	0.02	0.84	0.64	1.3	0.12	2.6
Control	80	72	3/24/2010	12:55	3/25/2010	8:15	19.33	14,448	0.05	1.05	0.72	1.5	0.25	2.6
Test	100	73	3/27/2010	8:05	3/27/2010	22:20	14.25	6,826	0.02	0.85	0.47	1.8	0.16	5.9
Control	80	73	3/27/2010	8:00	3/27/2010	22:20	14.33	5,391	0.02	0.97	0.60	1.6	0.16	5.9
Test	100	74	4/2/2010	9:50	4/3/2010	0:45	14.92	16,218	0.04	5.56	0.53	10.5	0.12	5.0
Control	80	74	4/2/2010	9:50	4/3/2010	0:45	14.92	12,897	0.04	4.02	0.71	5.7	0.12	5.0
Test	100	75	4/5/2010	7:30	4/5/2010	21:20	13.83	50,939	0.14	18.93	1.30	14.6	0.18	6.9
Control	80	75	4/5/2010	7:25	4/5/2010	21:20	13.92	39,710	0.14	23.38	1.16	20.2	0.18	7.0
Test	100	76	4/6/2010	19:55	4/7/2010	12:35	16.67	87,792	0.24	9.28	1.98	4.7	0.35	3.5
Control	80	76	4/6/2010	19:55	4/7/2010	12:35	16.67	25,707	0.09	6.70	0.84	8.0	0.13	3.5
Test	100	77	4/16/2010	5:25	4/16/2010	21:05	15.67	5,100	0.01	0.43	0.23	1.9	0.13	3.9
Control	80	77	4/16/2010	5:10	4/16/2010	21:05	15.92	4,760	0.02	0.77	0.32	2.4	0.15	4.0
Test	100	78	4/22/2010	10:05	4/23/2010	19:35	33.50	215,945	0.59	10.08	1.85	5.4	0.24	1.6
Control	80	78	4/22/2010	10:05	4/23/2010	19:35	33.50	70,013	0.24	6.32	1.11	5.7	0.10	1.6
Test	100	79	4/24/2010	11:20	4/25/2010	22:35	35.25	65,821	0.18	1.83	1.05	1.7	0.21	1.5
Control	80	79	4/24/2010	11:15	4/25/2010	22:35	35.33	44,101	0.15	1.25	0.65	1.9	0.18	1.5
Test	100	80	4/30/2010	6:15	5/1/2010	1:15	19.00	44,181	0.12	11.44	0.86	13.3	0.16	2.7
Control	80	80	4/30/2010	6:15	5/1/2010	1:15	19.00	23,794	0.08	7.16	0.65	11.1	0.11	2.7
Test	100	81	-	-	-	-	-	-	-	-	-	-	-	-



**DRAFT**

**Calculated Rainfall and Runoff Characteristics from Combined Sewage Monitoring (data from KCMO, UMKC, and TetraTech) (cont.)**

Site	Area (acres)	Evt #	Pipeflow start date	Pipeflow start time	Pipeflow end date	Flow end time	Flow dur. (hrs)	Total pipeflow discharge volume (ft3)	Total disch. (in)	Peak flow disch. rateb (CFS)	Avg flow disch. rate (CFS)	Peak /avg pipe flow rate ratio	Rv	flow/ rain dur. ratio
Control	80	81	5/10/2010	4:20	5/11/2010	13:20	33.00	53,716	0.18	17.06	0.63	27.3	0.14	1.6
Test	100	82	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	82	5/12/2010	3:50	5/13/2010	20:25	40.58	131,847	0.45	50.58	1.12	45.0	0.25	1.4
Test	100	83	5/15/2010	7:20	5/16/2010	22:40	39.33	48,586	0.13	2.14	0.80	2.7	0.19	1.4
Control	80	83	5/15/2010	7:20	5/16/2010	22:40	39.33	22,562	0.08	1.10	0.33	3.3	0.11	1.4
Test	100	84	5/19/2010	11:30	5/20/2010	12:55	25.42	106,124	0.29	9.28	1.48	6.3	0.25	1.9
Control	80	84	5/19/2010	11:25	5/20/2010	12:55	25.50	67,112	0.23	6.93	0.95	7.3	0.20	1.9
Test	100	85	5/20/2010	16:20	5/21/2010	13:45	21.42	6,251	0.02	0.64	0.79	0.8	0.10	2.2
Control	80	85	5/20/2010	16:10	5/21/2010	13:45	21.58	5,411	0.02	0.87	0.36	2.4	0.11	2.2
Test	100	86	6/2/2010	6:25	6/2/2010	19:35	13.17	28,892	0.08	8.36	0.63	13.2	0.11	9.9
Control	80	86	6/2/2010	6:20	6/2/2010	19:35	13.25	11,612	0.04	4.47	0.43	10.4	0.06	9.9
Test	100	87	6/7/2010	13:50	6/8/2010	1:45	11.92	362	0.00	0.04	0.01	4.3	0.00	143.0
Control	80	87	6/7/2010	13:45	6/8/2010	1:45	12.00	1,501	0.01	0.30	0.23	1.3	0.02	144.0
Test	100	88	6/8/2010	8:40	6/10/2010	0:30	39.83	31,877	0.09	6.12	0.23	26.9	0.04	1.4
Control	80	88	6/8/2010	8:30	6/10/2010	0:30	40.00	67,227	0.23	18.52	0.63	29.4	0.11	1.4
Test	100	89	6/12/2010	10:05	6/13/2010	1:40	15.58	54,635	0.15	11.82	0.97	12.2	0.06	4.2
Control	80	89	6/12/2010	10:05	6/13/2010	1:40	15.58	176,663	0.61	44.85	3.30	13.6	0.25	4.2
Test	100	90	6/13/2010	7:20	6/15/2010	0:45	41.42	139,811	0.39	19.64	0.97	20.3	0.11	1.4
Control	80	90	6/13/2010	7:15	6/15/2010	0:45	41.50	602,981	2.08	109.39	4.24	25.8	0.60	1.4
Test	100	91	6/15/2010	13:25	6/16/2010	16:35	27.17	2,693	0.01	3.20	0.03	110.3	0.02	1.8
Control	80	91	6/15/2010	13:25	6/16/2010	16:40	27.25	14,541	0.05	6.79	0.47	14.4	0.17	1.8
Test	100	92	6/16/2010	18:15	6/17/2010	8:00	13.75	20,253	0.06	6.54	0.40	16.2	0.06	7.2

**DRAFT**

**Calculated Rainfall and Runoff Characteristics from Combined Sewage Monitoring (data from KCMO, UMKC, and TetraTech) (cont.)**

Site	Area (acres)	Evt #	Pipeflow start date	Pipeflow start time	Pipeflow end date	Flow end time	Flow dur. (hrs)	Total pipeflow discharge volume (ft3)	Total disch. (in)	Peak flow disch. rateb (CFS)	Avg flow disch. rate (CFS)	Peak /avg pipe flow rate ratio	Rv	flow/ rain dur. ratio
Control	80	92	6/16/2010	18:10	6/17/2010	8:00	13.83	48,655	0.17	20.60	1.39	14.9	0.19	7.2
Test	100	93	6/19/2010	12:55	6/20/2010	13:00	24.08	3,752	0.01	3.78	0.04	89.3	0.03	1.9
Control	80	93	6/19/2010	12:40	6/20/2010	13:10	24.50	24,780	0.09	4.63	0.44	10.5	0.21	1.9
Test	100	94	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	94	6/21/2010	12:30	6/22/2010	0:30	12.00	1,930	0.01	0.34	0.22	1.6	0.04	144.0
Test	100	95	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	95	7/3/2010	16:35	7/4/2010	4:55	12.33	3,240	0.01	2.04	0.19	11.0	0.09	29.6
Test	100	96	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	96	7/4/2010	20:50	7/7/2010	2:45	53.92	37,260	0.13	11.06	0.31	35.8	0.08	1.3
Test	100	97	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	97	7/11/2010	9:15	7/12/2010	14:45	29.50	121,291	0.42	55.92	1.27	44.2	0.18	1.7
Test	100	98	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	98	7/19/2010	12:20	7/20/2010	2:10	13.83	2,693	0.01	0.93	0.21	4.4	0.06	7.2
Test	100	99	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	99	7/20/2010	17:20	7/21/2010	11:55	18.58	61,557	0.21	51.15	1.12	45.5	0.12	2.8
Test	100	100	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	100	7/24/2010	16:35	7/25/2010	13:15	20.67	10,455	0.04	5.54	0.22	25.6	0.06	2.4
Test	100	101	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	101	7/30/2010	7:50	7/30/2010	20:10	12.33	5,055	0.02	1.77	0.19	9.4	0.13	29.6
Test	100	102	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	102	8/13/2010	20:15	8/14/2010	11:10	14.92	8,035	0.03	2.99	0.31	9.6	0.07	5.0
Test	100	103	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	103	8/16/2010	15:55	8/17/2010	4:40	12.75	2,140	0.01	0.40	0.32	1.3	0.04	15.3

**DRAFT****Calculated Rainfall and Runoff Characteristics from Combined Sewage Monitoring (data from KCMO, UMKC, and TetraTech) (cont.)**

Site	Area (acres)	Evt #	Pipeflow start date	Pipeflow start time	Pipeflow end date	Flow end time	Flow dur. (hrs)	Total pipeflow discharge volume (ft3)	Total disch. (in)	Peak flow disch. rate (CFS)	Avg flow disch. rate (CFS)	Peak /avg pipe flow rate ratio	Rv	flow/ rain dur. ratio
Test	100	104	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	104	8/20/2010	15:15	8/21/2010	11:45	20.50	50,740	0.17	17.29	0.80	21.7	0.09	2.4
Test	100	105	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	105	8/31/2010	9:55	8/31/2010	22:05	12.17	3,548	0.01	1.58	0.17	9.1	0.11	48.7
Test	100	106	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	106	8/31/2010	23:40	9/1/2010	22:50	23.17	17,027	0.06	7.86	0.34	23.1	0.06	2.1
Test	100	107	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	107	9/10/2010	15:15	9/11/2010	13:15	22.00	10,590	0.04	1.51	0.25	6.0	0.16	2.2
Test	100	108	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	108	9/13/2010	22:25	9/14/2010	18:10	19.75	48,094	0.17	13.31	0.92	14.5	0.10	2.5
Test	100	109	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	109	9/15/2010	9:10	9/16/2010	8:35	23.42	17,335	0.06	1.48	0.31	4.8	0.10	2.0
Test	100	110	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	110	9/18/2010	18:50	9/19/2010	9:40	14.83	5,940	0.02	1.93	0.24	8.0	0.13	5.1
Test	100	111	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	111	9/21/2010	23:35	9/22/2010	18:05	18.50	17,439	0.06	7.75	0.40	19.4	0.08	2.8
Test	100	112	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	112	9/23/2010	19:30	9/24/2010	14:25	18.92	9,498	0.03	2.30	0.27	8.4	0.08	2.7
Test	100	113	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	113	9/25/2010	15:05	9/26/2010	7:35	16.50	4,387	0.02	1.63	0.28	5.8	0.11	3.6
Test	100	114	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	114	10/11/2010	1:55	10/13/2010	5:00	51.08	25,883	0.09	3.11	0.21	15.0	0.10	1.3
Test	100	115	-	-	-	-	-	-	-	-	-	-	-	-

**DRAFT**

**Calculated Rainfall and Runoff Characteristics from Combined Sewage Monitoring (data from KCMO, UMKC, and TetraTech) (cont.)**

Site	Area (acres)	Evt #	Pipeflow start date	Pipeflow start time	Pipeflow end date	Flow end time	Flow dur. (hrs)	Total pipeflow discharge volume (ft3)	Total disch. (in)	Peak flow disch. rate <sup>b</sup> (CFS)	Avg flow disch. rate (CFS)	Peak /avg pipe flow rate ratio	Rv	flow/ rain dur. ratio
Control	80	115	10/22/2010	14:15	10/23/2010	15:35	-	-	-	-	-	-	-	-
Test	100	116	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	116	11/11/2010	17:35	11/13/2010	9:20	39.75	38,643	0.13	3.17	0.34	9.3	0.08	1.4
Test	100	117	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	117	11/17/2010	15:35	11/18/2010	5:35	14.00	3,315	0.01	0.79	0.17	4.6	0.10	6.7
Test	100	118	12/31/2010	5:10	12/31/2010	20:45	15.58	2,091,602	5.76	77.95	60.22	1.3	14.63	4.1
Control	80	118	12/31/2010	5:00	12/31/2010	20:45	15.75	10,718	0.04	1.92	0.26	7.3	0.09	4.1
Test	100	119	1/22/2011	12:25	1/23/2011	3:40	15.25	2,246	0.01	0.12	0.18	0.7	0.05	4.5
Control	80	119	1/22/2011	12:20	1/23/2011	3:40	15.33	2,143	0.01	0.39	0.16	2.4	0.06	4.5
Test	100	120	2/24/2011	9:05	2/25/2011	3:00	17.92	33,011	0.09	1.81	0.91	2.0	0.26	2.9
Control	80	120	2/24/2011	9:00	2/25/2011	3:00	18.00	8,661	0.03	1.78	0.60	3.0	0.08	3.0
Test	100	121	2/26/2011	13:50	2/28/2011	8:20	42.50	129,497	0.36	16.84	1.18	14.3	0.29	1.4
Control	80	121	2/26/2011	13:50	2/28/2011	8:20	42.50	88,973	0.31	7.94	0.72	11.1	0.25	1.4
Test	100	122	3/4/2011	11:10	3/5/2011	1:40	14.50	23,412	0.06	6.15	0.73	8.4	0.27	5.6
Control	80	122	3/4/2011	11:10	3/5/2011	1:40	14.50	8,129	0.03	2.78	0.30	9.3	0.12	5.6
Test	100	123	3/8/2011	8:10	3/9/2011	1:10	17.00	13,056	0.04	1.78	0.65	2.7	0.09	3.3
Control	80	123	3/8/2011	8:10	3/9/2011	1:10	17.00	12,952	0.04	1.33	0.42	3.1	0.11	3.3
Test	100	124	3/13/2011	23:05	3/15/2011	0:20	25.25	10,708	0.03	0.36	0.39	0.9	0.15	1.9
Control	80	124	3/13/2011	23:00	3/15/2011	0:25	25.42	6,038	0.02	0.64	0.29	2.3	0.11	1.9
Test	100	125	3/19/2011	14:30	3/20/2011	4:15	13.75	5,900	0.02	1.55	0.37	4.2	0.05	7.5
Control	80	125	3/19/2011	14:30	3/20/2011	4:15	13.75	4,312	0.01	0.93	0.31	3.0	0.05	7.5
Test	100	126	-	-	-	-	-	-	-	-	-	-	-	-

**DRAFT**

**Calculated Rainfall and Runoff Characteristics from Combined Sewage Monitoring (data from KCMO, UMKC, and TetraTech) (cont.)**

Site	Area (acres)	Evt #	Pipeflow start date	Pipeflow start time	Pipeflow end date	Flow end time	Flow dur. (hrs)	Total pipeflow discharge volume (ft3)	Total disch. (in)	Peak flow disch. rateb (CFS)	Avg flow disch. rate (CFS)	Peak /avg pipe flow rate ratio	Rv	flow/ rain dur. ratio
Control	80	126	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	127	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	127	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	128	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	128	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	129	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	129	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	130	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	130	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	131	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	131	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	132	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	132	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	133	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	133	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	134	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	134	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	135	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	135	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	136	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	136	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	137	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	137	-	-	-	-	-	-	-	-	-	-	-	-

**DRAFT**

**Calculated Rainfall and Runoff Characteristics from Combined Sewage Monitoring (data from KCMO, UMKC, and TetraTech) (cont.)**

Site	Area (acres)	Evt #	Pipeflow start date	Pipeflow start time	Pipeflow end date	Flow end time	Flow dur. (hrs)	Total pipeflow discharge volume (ft3)	Total disch. (in)	Peak flow disch. rate (CFS)	Avg flow disch. rate (CFS)	Peak /avg pipe flow rate ratio	Rv	flow/ rain dur. ratio
Test	100	138	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	138	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	139	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	139	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	140	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	140	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	141	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	141	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	142	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	142	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	143	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	143	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	144	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	144	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	145	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	145	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	146	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	146	7/6/2011	12:05	7/7/2011	0:05	12.00	1,628	0.01	0.28	0.15	1.9	0.02	144.0
Test	100	147	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	147	7/7/2011	6:10	7/8/2011	6:45	24.58	5,538	0.02	6.96	0.49	14.2	0.03	1.9
Test	100	148	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	148	7/12/2011	21:10	7/13/2011	12:00	14.83	19,751	0.07	23.61	0.99	23.8	0.05	5.1
Test	100	149	-	-	-	-	-	-	-	-	-	-	-	-

**DRAFT**

**Calculated Rainfall and Runoff Characteristics from Combined Sewage Monitoring (data from KCMO, UMKC, and TetraTech) (cont.)**

Site	Area (acres)	Evt #	Pipeflow start date	Pipeflow start time	Pipeflow end date	Flow end time	Flow dur. (hrs)	Total pipeflow discharge volume (ft3)	Total disch. (in)	Peak flow disch. rateb (CFS)	Avg flow disch. rate (CFS)	Peak /avg pipe flow rate ratio	Rv	flow/ rain dur. ratio
Control	80	149	7/30/2011	8:20	7/30/2011	20:50	12.50	2,401	0.01	4.46	0.57	7.8	0.04	21.4
Test	100	150	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	150	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	151	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	151	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	152	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	152	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	153	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	153	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	154	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	154	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	155	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	155	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	156	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	156	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	157	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	157	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	158	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	158	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	159	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	159	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	160	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	160	-	-	-	-	-	-	-	-	-	-	-	-



**DRAFT****Calculated Rainfall and Runoff Characteristics from Combined Sewage Monitoring (data from KCMO, UMKC, and TetraTech) (cont.)**

Site	Area (acres)	Evt #	Pipeflow start date	Pipeflow start time	Pipeflow end date	Flow end time	Flow dur. (hrs)	Total pipeflow discharge volume (ft3)	Total disch. (in)	Peak flow disch. rate (CFS)	Avg flow disch. rate (CFS)	Peak /avg pipe flow rate ratio	Rv	flow/ rain dur. ratio
Test	100	161	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	161	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	162	11/22/2011	2:35	11/22/2011	18:20	15.75	17,998	0.05	0.88	0.31	2.8	0.18	3.9
Control	80	162	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	163	11/25/2011	23:05	11/26/2011	20:45	21.67	49,516	0.14	2.36	0.74	3.2	0.13	2.2
Control	80	163	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	164	12/2/2011	22:35	12/4/2011	7:10	32.58	42,340	0.12	1.24	0.48	2.6	0.15	1.6
Control	80	164	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	165	12/13/2011	9:15	12/14/2011	16:40	31.42	22,396	0.06	0.96	0.34	2.8	0.17	1.6
Control	80	165	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	166	12/19/2011	11:30	12/20/2011	22:35	35.08	120,835	0.33	8.43	0.98	8.6	0.25	1.5
Control	80	166	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	167	1/22/2012	18:40	1/23/2012	8:30	13.83	2,708	0.01	0.62	0.11	5.4	0.03	6.6
Control	80	167	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	168	2/3/2012	7:00	2/4/2012	14:15	31.25	81,419	0.22	10.95	0.83	13.2	0.19	1.6
Control	80	168	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	169	2/13/2012	13:30	2/14/2012	9:55	20.42	2,720	0.01	0.12	0.21	0.6	0.06	2.4
Control	80	169	-	-	-	-	-	-	-	-	-	-	-	-
Test	100	170	2/20/2012	19:45	2/21/2012	8:25	12.67	12,176	0.03	6.75	0.50	13.6	0.09	13.8
Control	80	170	2/20/2012	19:35	2/21/2012	8:25	12.83	6,478	0.02	3.30	0.29	11.3	0.06	14.0
Test	100	171	2/28/2012	13:45	2/29/2012	10:15	20.50	13,916	0.04	1.10	0.32	3.5	0.19	2.3
Control	80	171	2/28/2012	13:35	2/29/2012	10:15	20.67	8,516	0.03	0.88	0.22	3.9	0.15	2.4
Test	100	172	3/8/2012	2:15	3/8/2012	16:30	14.25	16,585	0.05	1.05	0.42	2.5	0.14	5.9

**DRAFT****Calculated Rainfall and Runoff Characteristics from Combined Sewage Monitoring (data from KCMO, UMKC, and TetraTech) (cont.)**

Site	Area (acres)	Evt #	Pipeflow start date	Pipeflow start time	Pipeflow end date	Flow end time	Flow dur. (hrs)	Total pipeflow discharge volume (ft3)	Total disch. (in)	Peak flow disch. rateb (CFS)	Avg flow disch. rate (CFS)	Peak /avg pipe flow rate ratio	Rv	flow/ rain dur. ratio
Control	80	172	3/8/2012	2:10	3/8/2012	16:30	14.33	9,890	0.03	1.15	0.29	4.0	0.11	5.9
Test	100	173	3/11/2012	8:40	3/12/2012	13:15	28.58	33,143	0.09	1.90	0.54	3.5	0.15	1.7
Control	80	173	3/11/2012	8:30	3/12/2012	13:15	28.75	25,908	0.09	1.70	0.35	4.9	0.15	1.7
Test	100	174	3/19/2012	14:35	3/21/2012	7:55	41.33	37,356	0.10	0.64	0.86	0.7	0.06	1.4
Control	80	174	3/19/2012	14:25	3/21/2012	7:55	41.50	56,497	0.19	3.88	0.65	6.0	0.11	1.4
Test	100	175	3/21/2012	11:30	3/22/2012	8:50	21.33	10,889	0.03	0.47	0.60	0.8	0.12	2.3
Control	80	175	3/21/2012	11:30	3/22/2012	8:50	21.33	13,666	0.05	1.17	0.43	2.7	0.19	2.3
Test	100	176	3/22/2012	16:10	3/23/2012	12:25	20.25	11,018	0.03	0.89	0.73	1.2	0.09	2.4
Control	80	176	3/22/2012	16:10	3/23/2012	12:25	20.25	11,267	0.04	1.24	0.43	2.9	0.11	2.4
Test	100	177	4/4/2012	20:45	4/5/2012	9:10	12.42	1,818	0.01	0.17	0.17	1.0	0.03	24.8
Control	80	177	4/4/2012	20:45	4/5/2012	9:10	12.42	5,378	0.02	2.93	0.35	8.5	0.10	24.8
Test	100	178	4/12/2012	15:20	4/13/2012	4:15	12.92	2,546	0.01	0.62	0.19	3.2	0.06	12.9
Control	80	178	4/12/2012	15:20	4/13/2012	4:15	12.92	8,466	0.03	1.60	0.41	3.9	0.24	12.9
Test	100	179	4/27/2012	20:50	4/28/2012	8:40	11.83	1,249	0.00	0.08	0.11	0.7	0.03	142.0
Control	80	179	4/27/2012	20:40	4/28/2012	8:40	12.00	3,245	0.01	2.19	0.22	9.8	0.09	144.0
Test	100	180	4/28/2012	22:45	4/30/2012	7:50	33.08	20,505	0.06	2.91	0.26	11.4	0.08	1.6
Control	80	180	4/28/2012	22:45	4/30/2012	7:50	33.08	26,044	0.09	3.13	0.39	7.9	0.12	1.6
Test	100	181	5/1/2012	1:45	5/1/2012	22:30	20.75	6,626	0.02	0.64	0.31	2.0	0.04	2.3
Control	80	181	5/1/2012	1:40	5/1/2012	22:30	20.83	4,468	0.02	2.09	0.39	5.3	0.04	2.3
Test	100	182	5/6/2012	10:05	5/7/2012	20:55	34.83	34,962	0.10	11.89	0.85	13.9	0.05	1.5
Control	80	182	5/6/2012	10:05	5/7/2012	20:55	34.83	88,622	0.31	22.12	0.81	27.4	0.17	1.5
Test	100	183	5/24/2012	20:35	5/25/2012	20:10	23.58	43,119	0.12	8.38	0.67	12.4	0.30	2.0
Control	80	183	5/24/2012	20:35	5/25/2012	20:10	23.58	148,512	0.51	15.82	1.88	8.4	1.28	2.0

**DRAFT**

**Calculated Rainfall and Runoff Characteristics from Combined Sewage Monitoring (data from KCMO, UMKC, and TetraTech) (cont.)**

Site	Area (acres)	Evt #	Pipeflow start date	Pipeflow start time	Pipeflow end date	Flow end time	Flow dur. (hrs)	Total pipeflow discharge volume (ft3)	Total disch. (in)	Peak flow disch. rateb (CFS)	Avg flow disch. rate (CFS)	Peak /avg pipe flow rate ratio	Rv	flow/ rain dur. ratio
Test	100	184	6/11/2012	2:50	6/11/2012	19:35	16.75	15,514	0.04	18.36	0.26	71.7	0.04	3.5
Control	80	184	6/11/2012	2:50	6/11/2012	19:35	16.75	53,119	0.18	17.27	0.99	17.4	0.15	3.5
Test	100	185	6/21/2012	1:25	6/21/2012	21:00	19.58	30,410	0.08	13.02	0.55	23.8	0.09	2.5
Control	80	185	6/21/2012	1:20	6/21/2012	21:00	19.67	52,399	0.18	12.74	1.08	11.8	0.20	2.5
Test	100	186	-	-	-	-	-	-	-	-	-	-	-	-
Control	80	186	-	-	-	-	-	-	-	-	-	-	-	-

## Appendix E: Residential Area Production Function Calculations using WinSLAMM

### Production Functions for 0.2 in/hr Native Soil Infiltration Rate

gravel layer?	underdrain?	surface area %	infiltration rate, in/hr	total inflow CF	infiltration vol CF	underdrain CF	ET CF	surface bypass CF	#>3day s ponding in 4.11 yrs)	sum out CF	out/in ratio	sum infiltr plus ET	% captured by biofilm	% volume reduction to infiltr	% to underdrain	% as ET	% surface bypass	surface area m2	part. solids kg/yr (125 mg/L and 4.11 yrs)	part. Solids kg/m2/yr	years to 10 kg/m2	years to 25 kg/m2
no	no	0.5	0.2	144,209	39,128	0	929	103,558	17	143,615	1.00	40,057	27.8	27.1	0.0	0.6	71.8	20.3	35	1.70	5.87	14.67
no	no	1.0	0.2	144,209	63,298	0	1,858	78,397	17	143,553	1.00	65,156	45.2	43.9	0.0	1.3	54.4	40.5	56	1.39	7.22	18.04
no	no	2.0	0.2	144,209	94,694	0	3,717	45,110	14	143,521	1.00	98,411	68.2	65.7	0.0	2.6	31.3	81.0	85	1.05	9.56	23.89
no	no	3.0	0.2	144,209	110,596	0	5,609	27,334	11	143,539	1.00	116,205	80.6	76.7	0.0	3.9	19.0	121.5	100	0.82	12.14	30.35
no	no	5.0	0.2	144,209	124,593	0	9,283	9,415	4	143,291	0.99	133,876	92.8	86.4	0.0	6.4	6.5	202.5	115	0.57	17.56	43.91
no	no	8.0	0.2	144,209	126,184	0	14,858	2,046	0	143,088	0.99	141,042	97.8	87.5	0.0	10.3	1.4	324.0	121	0.37	26.67	66.68
no	no	10.0	0.2	144,209	123,408	0	18,566	750	0	142,724	0.99	141,974	98.5	85.6	0.0	12.9	0.5	405.0	122	0.30	33.12	82.80
no	no	15.0	0.2	144,209	115,063	0	27,926	0	0	142,989	0.99	142,989	99.2	79.8	0.0	19.4	0.0	607.5	123	0.20	49.33	123.32
yes	no	0.5	0.2	144,209	51,914	0	929	90,593	8	143,436	0.99	52,843	36.6	36.0	0.0	0.6	62.8	20.3	46	2.25	4.45	11.12
yes	no	1.0	0.2	144,209	80,117	0	1,858	61,149	11	143,124	0.99	81,975	56.8	55.6	0.0	1.3	42.4	40.5	71	1.74	5.74	14.34
yes	no	2.0	0.2	144,209	109,021	0	3,717	30,225	9	142,963	0.99	112,738	78.2	75.6	0.0	2.6	21.0	81.0	97	1.20	8.34	20.86
yes	no	3.0	0.2	144,209	122,711	0	5,609	14,618	5	142,938	0.99	128,320	89.0	85.1	0.0	3.9	10.1	121.5	111	0.91	10.99	27.48
yes	no	5.0	0.2	144,209	129,344	0	9,283	3,972	0	142,599	0.99	138,627	96.1	89.7	0.0	6.4	2.8	202.5	119	0.59	16.96	42.40
yes	no	8.0	0.2	144,209	127,031	0	14,858	375	0	142,264	0.99	141,889	98.4	88.1	0.0	10.3	0.3	324.0	122	0.38	26.51	66.28

Production Functions for 0.2 in/hr Native Soil Infiltration Rate (cont.)

gravel layer ?	underdrain?	surface area %	infiltration rate, in/hr	total inflow CF	infiltration vol CF	underdrain CF	ET CF	surface bypass CF	#>3days ponding in 4.11 yrs)	sum out CF	out/in ratio	sum infiltr plus ET	% captured by biofilt	% vol reduction to infiltr	% to underdrain	% as ET	% surface bypass	surface area m2	part. solids kg/yr (125 mg/L and 4.11 yrs)	part. Solids kg/m2/yr	years to 10 kg/m2	years to 25 kg/m2
yes	no	10.0	0.2	144,209	123,648	0	18,566	0	0	142,214	0.99	142,214	98.6	85.7	0.0	12.9	0.0	405.0	122	0.30	33.07	82.66
yes	yes, 3"	0.5	0.2	144,209	30,083	42,169	929	70,252	1	143,433	0.99	31,012	21.5	20.9	29.2	0.6	48.7	20.3	63	3.11	3.21	8.03
yes	yes, 3"	1.0	0.2	144,209	47,629	55,438	1,858	38,303	1	143,228	0.99	49,487	34.3	33.0	38.4	1.3	26.6	40.5	90	2.23	4.48	11.20
yes	yes, 3"	2.0	0.2	144,209	71,322	55,216	3,717	12,677	1	142,932	0.99	75,039	52.0	49.5	38.3	2.6	8.8	81.0	112	1.39	7.22	18.05
yes	yes, 3"	3.0	0.2	144,209	88,024	44,292	5,609	4,786	0	142,711	0.99	93,633	64.9	61.0	30.7	3.9	3.3	121.5	119	0.98	10.23	25.57
yes	yes, 3"	5.0	0.2	144,209	105,288	27,872	9,283	6	0	142,449	0.99	114,571	79.4	73.0	19.3	6.4	0.0	202.5	123	0.61	16.51	41.26
yes	yes, 3"	8.0	0.2	144,209	116,366	11,103	14,858	0	0	142,327	0.99	131,224	91.0	80.7	7.7	10.3	0.0	324.0	123	0.38	26.43	66.08
yes	yes, 3"	10.0	0.2	144,209	118,235	5,467	18,566	0	0	142,268	0.99	136,801	94.9	82.0	3.8	12.9	0.0	405.0	123	0.30	33.05	82.63
yes	yes, 3"	15.0	0.2	144,209	113,226	1,361	27,926	0	0	142,513	0.99	141,152	97.9	78.5	0.9	19.4	0.0	607.5	123	0.20	49.49	123.73
yes	yes, 3"	20.0	0.2	144,209	105,809	0	37,133	0	0	142,942	0.99	142,942	99.1	73.4	0.0	25.7	0.0	810.0	123	0.15	65.79	164.48
yes	yes, smartdrain	0.5	0.2	144,209	37,945	29,098	929	72,606	1	140,578	0.97	38,874	27.0	26.3	20.2	0.6	50.3	20.3	59	2.89	3.46	8.65
yes	yes, smartdrain	1.0	0.2	144,209	62,414	26,575	1,858	46,825	1	137,672	0.95	64,272	44.6	43.3	18.4	1.3	32.5	40.5	78	1.93	5.18	12.94
yes	yes, smartdrain	2.0	0.2	144,209	92,686	19,346	3,717	22,454	1	138,203	0.96	96,403	66.8	64.3	13.4	2.6	15.6	81.0	100	1.23	8.13	20.31
yes	yes, smartdrain	3.0	0.2	144,209	109,911	13,543	5,609	10,609	0	139,672	0.97	115,520	80.1	76.2	9.4	3.9	7.4	121.5	111	0.91	10.93	27.33
yes	yes, smartdrain	5.0	0.2	144,209	122,141	7,011	9,283	2,833	0	141,268	0.98	131,424	91.1	84.7	4.9	6.4	2.0	202.5	119	0.59	16.98	42.46
yes	yes, smartdrain	8.0	0.2	144,209	124,848	2,219	14,858	31	0	141,956	0.98	139,706	96.9	86.6	1.5	10.3	0.0	324.0	122	0.38	26.51	66.26
yes	yes, smartdrain	10.0	0.2	144,209	122,427	1,082	18,566	0	0	142,075	0.99	140,993	97.8	84.9	0.8	12.9	0.0	405.0	122	0.30	33.10	82.74
yes	yes, smartdrain	15.0	0.2	144,209	114,457	173	27,849	0	0	142,479	0.99	142,306	98.7	79.4	0.1	19.3	0.0	607.5	123	0.20	49.51	123.76
yes	yes, smartdrain	20.0	0.2	144,209	105,809	0	37,133	0	0	142,942	0.99	142,942	99.1	73.4	0.0	25.7	0.0	810.0	123	0.15	65.79	164.48

Production Functions for 0.5 in/hr Native Soil Infiltration Rate

gravel layer?	underdrain?	surface area %	infiltration rate, in/hr	total inflow CF	infiltration vol CF	underdrain CF	ET CF	surface bypass CF	#>3day ponding in 4.11 yrs)	sum out CF	out/in ratio	sum infiltr plus ET	% captured by biofilt	% vol reduction to infiltr	% to underdrain	% as ET	% surface bypass	surface area m2	part. solids kg/yr (125 mg/L and 4.11 yrs)	part. Solids kg/m2/yr	years to 10 kg/m2	years to 25 kg/m2
no	no	0.5	0.5	144,209	58,565	0	929	84,162	3	143,656	1.00	59,494	41.3	40.6	0.0	0.6	58.4	20.3	51	2.53	3.95	9.88
no	no	1.0	0.5	144,209	87,551	0	1,858	54,229	2	143,638	1.00	89,409	62.0	60.7	0.0	1.3	37.6	40.5	77	1.90	5.26	13.15
no	no	2.0	0.5	144,209	115,104	0	3,717	25,116	1	143,937	1.00	118,821	82.4	79.8	0.0	2.6	17.4	81.0	102	1.26	7.91	19.79
no	no	3.0	0.5	144,209	127,607	0	5,609	11,084	0	144,300	1.00	133,216	92.4	88.5	0.0	3.9	7.7	121.5	115	0.94	10.59	26.47
no	no	5.0	0.5	144,209	132,382	0	9,283	1,898	0	143,563	1.00	141,665	98.2	91.8	0.0	6.4	1.3	202.5	122	0.60	16.60	41.49
no	no	8.0	0.5	144,209	129,159	0	14,858	0	0	144,017	1.00	144,017	99.9	89.6	0.0	10.3	0.0	324.0	124	0.38	26.12	65.30
no	no	10.0	0.5	144,209	124,431	0	18,566	0	0	142,997	0.99	142,997	99.2	86.3	0.0	12.9	0.0	405.0	123	0.30	32.88	82.21
no	no	15.0	0.5	144,209	115,063	0	27,926	0	0	142,989	0.99	142,989	100.0	80.6	0.0	19.4	0.0	607.5	123	0.20	49.33	123.32
yes	no	0.5	0.5	144,209	71,747	0	929	70,837	1	143,513	1.00	72,676	50.4	49.8	0.0	0.6	49.1	20.3	63	3.09	3.24	8.09
yes	no	1.0	0.5	144,209	101,168	0	1,858	40,768	0	143,794	1.00	103,026	71.4	70.2	0.0	1.3	28.3	40.5	89	2.19	4.56	11.41
yes	no	2.0	0.5	144,209	125,070	0	3,717	14,672	1	143,459	0.99	128,787	89.3	86.7	0.0	2.6	10.2	81.0	111	1.37	7.30	18.26
yes	no	3.0	0.5	144,209	132,145	0	5,609	5,430	0	143,184	0.99	137,754	95.5	91.6	0.0	3.9	3.8	121.5	119	0.98	10.24	25.60
yes	no	5.0	0.5	144,209	133,182	0	9,283	615	0	143,080	0.99	142,465	98.8	92.4	0.0	6.4	0.4	202.5	123	0.61	16.50	41.26
yes	no	8.0	0.5	144,209	128,075	0	14,858	0	0	142,933	0.99	142,933	99.1	88.8	0.0	10.3	0.0	324.0	123	0.38	26.32	65.80
yes	no	10.0	0.5	144,209	123,648	0	18,566	0	0	142,214	0.99	142,214	100.0	87.1	0.0	12.9	0.0	405.0	122	0.30	33.07	82.66

Production Functions for 0.5 in/hr Native Soil Infiltration Rate (cont.)

gravel layer ?	underdrain?	surface area %	infiltration rate, in/hr	total inflow CF	infiltration vol CF	underdrain CF	ET CF	surface bypass CF	#>3days ponding in 4.11 yrs)	sum out CF	out/in ratio	sum infiltr plus ET	% capture d by biofilt	% vol reduction to infiltr	% to underdrain	% as ET	% surface bypass	surface area m2	part. solids kg/yr (125 mg/L and 4.11 yrs)	part. Solids kg/m2/yr	years to 10 kg/m2	years to 25 kg/m2
yes	yes, 3"	0.5	0.5	144,209	53,052	22,470	929	67,046	1	143,497	1.00	53,981	37.4	36.8	15.6	0.6	46.5	20.3	66	3.25	3.08	7.69
yes	yes, 3"	1.0	0.5	144,209	76,036	29,782	1,858	35,661	1	143,337	0.99	77,894	54.0	52.7	20.7	1.3	24.7	40.5	93	2.29	4.37	10.92
yes	yes, 3"	2.0	0.5	144,209	101,592	26,338	3,717	11,552	1	143,199	0.99	105,309	73.0	70.4	18.3	2.6	8.0	81.0	113	1.40	7.14	17.86
yes	yes, 3"	3.0	0.5	144,209	113,880	19,499	5,609	4,071	0	143,059	0.99	119,489	82.9	79.0	13.5	3.9	2.8	121.5	120	0.99	10.15	25.37
yes	yes, 3"	5.0	0.5	144,209	124,568	9,117	9,283	0	0	142,968	0.99	133,851	92.8	86.4	6.3	6.4	0.0	202.5	123	0.61	16.45	41.11
yes	yes, 3"	8.0	0.5	144,209	126,251	1,839	14,858	0	0	142,948	0.99	141,109	97.9	87.5	1.3	10.3	0.0	324.0	123	0.38	26.32	65.79
yes	yes, 3"	10.0	0.5	144,209	124,197	216	18,566	0	0	142,979	0.99	142,763	99.0	86.1	0.1	12.9	0.0	405.0	123	0.30	32.89	82.22
yes	yes, 3"	15.0	0.5	144,209	115,167	0	27,926	0	0	143,093	0.99	143,093	99.2	79.9	0.0	19.4	0.0	607.5	123	0.20	49.29	123.23
yes	yes, 3"	20.0	0.5	144,209	105,809	0	37,133	0	0	142,942	0.99	142,942	100.0	74.3	0.0	25.7	0.0	810.0	123	0.15	65.79	164.48
yes	yes, smartdrain	0.5	0.5	144,209	60,400	15,028	929	67,045	1	143,402	0.99	61,329	42.5	41.9	10.4	0.6	46.5	20.3	66	3.25	3.08	7.70
yes	yes, smartdrain	1.0	0.5	144,209	90,447	13,383	1,858	36,496	1	142,184	0.99	92,305	64.0	62.7	9.3	1.3	25.3	40.5	91	2.25	4.45	11.12
yes	yes, smartdrain	2.0	0.5	144,209	117,974	7,421	3,717	12,760	1	141,872	0.98	121,691	84.4	81.8	5.1	2.6	8.8	81.0	111	1.37	7.28	18.21
yes	yes, smartdrain	3.0	0.5	144,209	127,691	4,128	5,609	4,963	0	142,391	0.99	133,300	92.4	88.5	2.9	3.9	3.4	121.5	118	0.97	10.26	25.66
yes	yes, smartdrain	5.0	0.5	144,209	131,736	1,481	9,283	283	0	142,783	0.99	141,019	97.8	91.4	1.0	6.4	0.2	202.5	123	0.61	16.50	41.25
yes	yes, smartdrain	8.0	0.5	144,209	127,844	236	14,858	0	0	142,938	0.99	142,702	99.0	88.7	0.2	10.3	0.0	324.0	123	0.38	26.32	65.80
yes	yes, smartdrain	10.0	0.5	144,209	124,396	15	18,566	0	0	142,977	0.99	142,962	99.1	86.3	0.0	12.9	0.0	405.0	123	0.30	32.89	82.22
yes	yes, smartdrain	15.0	0.5	144,209	115,235	0	27,849	0	0	143,084	0.99	143,084	99.2	79.9	0.0	19.3	0.0	607.5	123	0.20	49.30	123.24
yes	yes, smartdrain	20.0	0.5	144,209	105,809	0	37,133	0	0	142,942	0.99	142,942	100.0	74.3	0.0	25.7	0.0	810.0	123	0.15	65.79	164.48



Production Functions for 1.0 in/hr Native Soil Infiltration Rate

gravel layer?	underdrain?	surface area %	infiltration rate, in/hr	total inflow CF	infiltration vol CF	underdrain CF	ET CF	surface bypass CF	#>3day ponding in 4.11 yrs)	sum out CF	out/in ratio	sum infiltr plus ET	% captured by biofilt	% vol reduction to infiltr	% to underdrain	% as ET	% surface bypass	surface area m2	part. solids kg/yr (125 mg/L and 4.11 yrs)	part. Solids kg/m2/yr	years to 10 kg/m2	years to 25 kg/m2
no	no	0.5	1	144,209	78,731	0	929	64,026	1	143,686	1.00	79,660	55.2	54.6	0.0	0.6	44.4	20.3	69	3.39	2.95	7.38
no	no	1.0	1	144,209	107,421	0	1,858	34,555	1	143,834	1.00	109,279	75.8	74.5	0.0	1.3	24.0	40.5	94	2.32	4.30	10.76
no	no	2.0	1	144,209	128,621	0	3,717	11,234	1	143,572	1.00	132,338	91.8	89.2	0.0	2.6	7.8	81.0	114	1.41	7.11	17.77
no	no	3.0	1	144,209	134,173	0	5,609	3,574	0	143,356	0.99	139,782	96.9	93.0	0.0	3.9	2.5	121.5	120	0.99	10.09	25.23
no	no	5.0	1	144,209	134,694	0	9,283	0	0	143,977	1.00	143,977	99.8	93.4	0.0	6.4	0.0	202.5	124	0.61	16.33	40.83
no	no	8.0	1	144,209	129,159	0	14,858	0	0	144,017	1.00	144,017	100.0	89.7	0.0	10.3	0.0	324.0	124	0.38	26.12	65.30
no	no	10.0	1	144,209	124,431	0	18,566	0	0	142,997	0.99	142,997	100.0	87.1	0.0	12.9	0.0	405.0	123	0.30	32.88	82.21
no	no	15.0	1	144,209	115,063	0	27,926	0	0	142,989	0.99	142,989	100.0	80.6	0.0	19.4	0.0	607.5	123	0.20	49.33	123.32
yes	no	0.5	1	144,209	80,506	0	929	62,080	1	143,515	1.00	81,435	56.5	55.8	0.0	0.6	43.0	20.3	70	3.46	2.89	7.22
yes	no	1.0	1	144,209	109,738	0	1,858	31,801	1	143,397	0.99	111,596	77.4	76.1	0.0	1.3	22.1	40.5	96	2.37	4.21	10.53
yes	no	2.0	1	144,209	129,662	0	3,717	9,911	1	143,290	0.99	133,379	92.5	89.9	0.0	2.6	6.9	81.0	115	1.42	7.05	17.63
yes	no	3.0	1	144,209	134,543	0	5,609	3,087	0	143,239	0.99	140,152	97.2	93.3	0.0	3.9	2.1	121.5	121	0.99	10.07	25.16
yes	no	5.0	1	144,209	133,940	0	9,282	0	0	143,222	0.99	143,222	99.3	92.9	0.0	6.4	0.0	202.5	123	0.61	16.42	41.04
yes	no	8.0	1	144,209	128,075	0	14,858	0	0	142,933	0.99	142,933	100.0	89.7	0.0	10.3	0.0	324.0	123	0.38	26.32	65.80
yes	no	10.0	1	144,209	123,648	0	18,566	0	0	142,214	0.99	142,214	100.0	87.1	0.0	12.9	0.0	405.0	122	0.30	33.07	82.66

Production Functions for 1.0 in/hr Native Soil Infiltration Rate (cont.)

gravel layer ?	underdrain?	surface area %	infiltration rate, in/hr	total inflow CF	infiltration vol CF	underdrain CF	ET CF	surface bypass CF	#>3days ponding in 4.11 yrs)	sum out CF	out/in ratio	sum infiltr plus ET	% captured by biofilt	% vol reduction to infiltr	% to underdrain	% as ET	% surface bypass	surface area m2	part. solids kg/yr (125 mg/L and 4.11 yrs)	part. Solids kg/m2/yr	years to 10 kg/m2	years to 25 kg/m2
yes	yes, 3"	0.5	1	144,209	79,822	689	929	62,080	1	143,520	1.00	80,751	56.0	55.4	0.5	0.6	43.0	20.3	70	3.46	2.89	7.22
yes	yes, 3"	1.0	1	144,209	106,482	3,282	1,858	31,801	1	143,423	0.99	108,340	75.1	73.8	2.3	1.3	22.1	40.5	96	2.37	4.21	10.53
yes	yes, 3"	2.0	1	144,209	125,954	3,736	3,716	9,911	1	143,317	0.99	129,670	89.9	87.3	2.6	2.6	6.9	81.0	115	1.42	7.05	17.62
yes	yes, 3"	3.0	1	144,209	132,420	2,141	5,608	3,087	0	143,256	0.99	138,028	95.7	91.8	1.5	3.9	2.1	121.5	121	0.99	10.06	25.16
yes	yes, 3"	5.0	1	144,209	133,618	324	9,282	0	0	143,224	0.99	142,900	99.1	92.7	0.2	6.4	0.0	202.5	123	0.61	16.42	41.04
yes	yes, 3"	8.0	1	144,209	128,379	0	14,856	0	0	143,235	0.99	143,235	99.3	89.0	0.0	10.3	0.0	324.0	123	0.38	26.26	65.66
yes	yes, 3"	10.0	1	144,209	124,689	0	18,564	0	0	143,253	0.99	143,253	99.3	86.5	0.0	12.9	0.0	405.0	123	0.30	32.83	82.06
yes	yes, 3"	15.0	1	144,209	115,167	0	27,926	0	0	143,093	0.99	143,093	100.0	80.6	0.0	19.4	0.0	607.5	123	0.20	49.29	123.23
yes	yes, 3"	20.0	1	144,209	105,809	0	37,133	0	0	142,942	0.99	142,942	100.0	74.3	0.0	25.7	0.0	810.0	123	0.15	65.79	164.48
yes	yes, smartdrain	0.5	1	144,209	79,955	552	929	62,080	1	143,516	1.00	80,884	56.1	55.4	0.4	0.6	43.0	20.3	70	3.46	2.89	7.22
yes	yes, smartdrain	1.0	1	144,209	108,100	1,639	1,858	31,801	1	143,398	0.99	109,958	76.2	75.0	1.1	1.3	22.1	40.5	96	2.37	4.21	10.53
yes	yes, smartdrain	2.0	1	144,209	128,672	993	3,716	9,911	1	143,292	0.99	132,388	91.8	89.2	0.7	2.6	6.9	81.0	115	1.42	7.05	17.63
yes	yes, smartdrain	3.0	1	144,209	134,179	363	5,608	3,087	0	143,237	0.99	139,787	96.9	93.0	0.3	3.9	2.1	121.5	121	0.99	10.07	25.16
yes	yes, smartdrain	5.0	1	144,209	133,917	22	9,282	0	0	143,221	0.99	143,199	99.3	92.9	0.0	6.4	0.0	202.5	123	0.61	16.42	41.04
yes	yes, smartdrain	8.0	1	144,209	128,379	0	14,858	0	0	143,237	0.99	143,237	99.3	89.0	0.0	10.3	0.0	324.0	123	0.38	26.26	65.66
yes	yes, smartdrain	10.0	1	144,209	124,689	0	18,566	0	0	143,255	0.99	143,255	99.3	86.5	0.0	12.9	0.0	405.0	123	0.30	32.82	82.06
yes	yes, smartdrain	15.0	1	144,209	115,235	0	27,849	0	0	143,084	0.99	143,084	100.0	80.7	0.0	19.3	0.0	607.5	123	0.20	49.30	123.24
yes	yes, smartdrain	20.0	1	144,209	105,809	0	37,133	0	0	142,942	0.99	142,942	100.0	74.3	0.0	25.7	0.0	810.0	123	0.15	65.79	164.48

Production Functions for 2.5 in/hr Native Soil Infiltration Rate

gravel layer?	underdrain?	surface area %	infiltration rate, in/hr	total inflow CF	infiltration vol CF	underdrain CF	ET CF	surface bypass CF	#>3days ponding in 4.11 yrs)	sum out CF	out/in ratio	sum infiltr plus ET	% captured by biofilt	% vol reduction to infiltr	% to underdrain	% as ET	% surface bypass	surface area m2	part. solids kg/yr (125 mg/L and 4.11 yrs)	part. Solids kg/m2/yr	years to 10 kg/m2	years to 25 kg/m2
no	no	0.5	2.5	144,209	92,527	0	929	50,096	1	143,552	1.00	93,456	64.8	64.2	0.0	0.6	34.7	20.3	80	3.97	2.52	6.29
no	no	1.0	2.5	144,209	118,652	0	1,858	22,991	1	143,501	1.00	120,510	83.6	82.3	0.0	1.3	15.9	40.5	104	2.56	3.90	9.76
no	no	2.0	2.5	144,209	133,353	0	3,716	6,374	1	143,443	0.99	137,069	95.0	92.5	0.0	2.6	4.4	81.0	118	1.46	6.86	17.15
no	no	3.0	2.5	144,209	136,751	0	5,607	1,052	0	143,410	0.99	142,358	98.7	94.8	0.0	3.9	0.7	121.5	123	1.01	9.91	24.77
no	no	5.0	2.5	144,209	134,694	0	9,283	0	0	143,977	1.00	143,977	100.0	93.6	0.0	6.4	0.0	202.5	124	0.61	16.33	40.83
no	no	8.0	2.5	144,209	129,159	0	14,858	0	0	144,017	1.00	144,017	100.0	89.7	0.0	10.3	0.0	324.0	124	0.38	26.12	65.30
no	no	10.0	2.5	144,209	124,431	0	18,566	0	0	142,997	0.99	142,997	100.0	87.1	0.0	12.9	0.0	405.0	123	0.30	32.88	82.21
no	no	15.0	2.5	144,209	115,063	0	27,926	0	0	142,989	0.99	142,989	100.0	80.6	0.0	19.4	0.0	607.5	123	0.20	49.33	123.32
yes	no	0.5	2.5	144,209	92,540	0	929	50,096	1	143,565	1.00	93,469	64.8	64.2	0.0	0.6	34.7	20.3	81	3.98	2.52	6.29
yes	no	1.0	2.5	144,209	118,670	0	1,858	22,991	1	143,519	1.00	120,528	83.6	82.3	0.0	1.3	15.9	40.5	104	2.56	3.90	9.75
yes	no	2.0	2.5	144,209	133,376	0	3,717	6,374	1	143,467	0.99	137,093	95.1	92.5	0.0	2.6	4.4	81.0	118	1.46	6.86	17.15
yes	no	3.0	2.5	144,209	136,774	0	5,609	1,052	0	143,435	0.99	142,383	98.7	94.8	0.0	3.9	0.7	121.5	123	1.01	9.91	24.77
yes	no	5.0	2.5	144,209	134,122	0	9,281	0	0	143,403	0.99	143,403	99.4	93.0	0.0	6.4	0.0	202.5	124	0.61	16.40	40.99
yes	no	8.0	2.5	144,209	128,075	0	14,858	0	0	142,933	0.99	142,933	100.0	89.7	0.0	10.3	0.0	324.0	123	0.38	26.32	65.80
yes	no	10.0	2.5	144,209	123,648	0	18,566	0	0	142,214	0.99	142,214	100.0	87.1	0.0	12.9	0.0	405.0	122	0.30	33.07	82.66

Production Functions for 2.5 in/hr Native Soil Infiltration Rate (cont.)

gravel layer ?	underdrain?	surface area %	infiltration rate, in/hr	total inflow CF	infiltration vol CF	underdrain CF	ET CF	surface bypass CF	#>3day ponding in 4.11 yrs)	sum out CF	out/in ratio	sum infiltr plus ET	% captured by biofit	% vol reduction to infiltr	% to underdrain	% as ET	% surface bypass	surface area m2	part. solids kg/yr (125 mg/L and 4.11 yrs)	part. Solids kg/m2/yr	years to 10 kg/m2	years to 25 kg/m2
yes	yes, 3"	0.5	2.5	144,209	92,540	0	929	50,096	1	143,565	1.00	93,469	64.8	64.2	0.0	0.6	34.7	20.3	81	3.98	2.52	6.29
yes	yes, 3"	1.0	2.5	144,209	118,670	0	1,858	22,991	1	143,519	1.00	120,528	83.6	82.3	0.0	1.3	15.9	40.5	104	2.56	3.90	9.75
yes	yes, 3"	2.0	2.5	144,209	133,376	0	3,716	6,374	1	143,466	0.99	137,092	95.1	92.5	0.0	2.6	4.4	81.0	118	1.46	6.86	17.15
yes	yes, 3"	3.0	2.5	144,209	136,774	0	5,607	1,052	0	143,433	0.99	142,381	98.7	94.8	0.0	3.9	0.7	121.5	123	1.01	9.91	24.77
yes	yes, 3"	5.0	2.5	144,209	134,122	0	9,281	0	0	143,403	0.99	143,403	99.4	93.0	0.0	6.4	0.0	202.5	124	0.61	16.40	40.99
yes	yes, 3"	8.0	2.5	144,209	128,379	0	14,856	0	0	143,235	0.99	143,235	100.0	89.7	0.0	10.3	0.0	324.0	123	0.38	26.26	65.66
yes	yes, 3"	10.0	2.5	144,209	124,689	0	18,564	0	0	143,253	0.99	143,253	100.0	87.1	0.0	12.9	0.0	405.0	123	0.30	32.83	82.06
yes	yes, 3"	15.0	2.5	144,209	115,167	0	27,926	0	0	143,093	0.99	143,093	100.0	80.6	0.0	19.4	0.0	607.5	123	0.20	49.29	123.23
yes	yes, 3"	20.0	2.5	144,209	105,809	0	37,133	0	0	142,942	0.99	142,942	100.0	74.3	0.0	25.7	0.0	810.0	123	0.15	65.79	164.48
yes	yes, smartdrain	0.5	2.5	144,209	92,540	0	929	50,096	1	143,565	1.00	93,469	64.8	64.2	0.0	0.6	34.7	20.3	81	3.98	2.52	6.29
yes	yes, smartdrain	1.0	2.5	144,209	118,670	0	1,858	22,991	1	143,519	1.00	120,528	83.6	82.3	0.0	1.3	15.9	40.5	104	2.56	3.90	9.75
yes	yes, smartdrain	2.0	2.5	144,209	133,376	0	3,716	6,374	1	143,466	0.99	137,092	95.1	92.5	0.0	2.6	4.4	81.0	118	1.46	6.86	17.15
yes	yes, smartdrain	3.0	2.5	144,209	136,774	0	5,607	1,052	0	143,433	0.99	142,381	98.7	94.8	0.0	3.9	0.7	121.5	123	1.01	9.91	24.77
yes	yes, smartdrain	5.0	2.5	144,209	134,122	0	9,281	0	0	143,403	0.99	143,403	99.4	93.0	0.0	6.4	0.0	202.5	124	0.61	16.40	40.99
yes	yes, smartdrain	8.0	2.5	144,209	128,379	0	14,858	0	0	143,237	0.99	143,237	100.0	89.7	0.0	10.3	0.0	324.0	123	0.38	26.26	65.66
yes	yes, smartdrain	10.0	2.5	144,209	124,776	0	18,566	0	0	143,342	0.99	143,342	100.0	87.1	0.0	12.9	0.0	405.0	123	0.30	32.80	82.01
yes	yes, smartdrain	15.0	2.5	144,209	115,235	0	27,849	0	0	143,084	0.99	143,084	100.0	80.7	0.0	19.3	0.0	607.5	123	0.20	49.30	123.24
yes	yes, smartdrain	20.0	2.5	144,209	105,809	0	37,133	0	0	142,942	0.99	142,942	100.0	74.3	0.0	25.7	0.0	810.0	123	0.15	65.79	164.48